

INDIAN BANK
FIELD GENERAL MANAGER OFFICE MEERUT

Sealed quotation are invited from the eligible empaneled contractors of INDIAN BANK & ALLAHABAD BANK as per the following details for furnishing works and A.C works of our FGM OFFICE Distt Meerut.

Sl No	Type of Works
1	Furnishing Works
2	Electrical Works
3	A C Works

Last Date for submission in sealed cover envelope in the office of The General manager, Indian Bank, Field General Manager Office, 55 The Mall Road, Meerut Cantt, Meerut is 26.06.2020. The bids will be opened on the same day at 4.00 P.M.

Format for tender document can be collected from Indian Bank, Field General Manager Office, 55 The Mall Road, Meerut Cantt, Meerut or either download from our Bank's site www.allahabadbank.in or www.indianbank.in

Please ensure that:-

- | | |
|-------------------|---|
| 1. Ply-Board | Duro, Century, Green, First |
| 2. Glass | Modi Guard float, Saint Gobin |
| 3. Adhesive | Fevicol SHL |
| 4. Aluminum Grill | Powder coated in off white shade |
| 5. Chandel, Rail | Ebco |
| 6. Paint Primer | Nerolac first quality |
| 7. Laminate | Century 303,191 Formica F1 1224 F1 1517(SF)
Sunmica E 224/1224, Sunmica terracotta G448/1448 |

List of Approved Make for Electrical works

- | | |
|---------------------------------------|---------------------------------------|
| 1. Wire | Finolex, Havels, Plaza, Kalinga |
| 2. Associre Modular Switch socket etc | M K White, Ankor, Havels |
| 3. PVC pipe | AKG, Plaza, Sapia 2mm th. |
| 4. Fan | Usha, Khetan, Crompton, Bajaj, Pollar |
| 5. Fitting | Philips, Bajaj, Havels, Siska |
| 6. MCD DB | Havels, Marlin Jarhn, HPL, L&T |

All wiring, switch board etc shall be concealed

The Bank reserves the right to accept/reject any tender/quotation without assigning any reason whatsoever.

Date: 20.06.2020

Field General Manager
Field General Manager Office

Estimate for Furnishing Work At
Indian Bank, F.G.M. office, Distt.: Meerut.

S.No.	Description of Item	Qty.	Unit Rate	Amount
1.	Floor tiles 600x600 vitrified tile as required with 25 mm approx base including supply of all materials labour & T & P etc.	1700 Sq.ft.		
2.	<u>Full Height Panelling For FGM Chamber & AGM Cabins & Chief Manager Cabin</u> Supplying and fixing 40mm x20mm kail/sal wood frame at 16" C/c both ways with 6mm thick ply board & Lamination on side. Teak wood beading and making holes for electric/telephone/fire wiring in conduits. With spirit polish on all wood work. (Full Height of 9' high.)	1400 Sq.ft		
3.	<u>Full Height Partition For FGM Chamber & AGM Cabins & Chief Manager Cabin</u> Supplying and fixing partly paneled and partly glazed with 50mm x30mm kail/sal wood frame at 16" C/c both ways with 6mm thick ply board on both sides, including provision of 1 1/2" thick solid flush doors wherever necessary with superior quality brass anodized fittings, handles provision of 6mm thick glass modi /approved make. Teak wood beading and making holes for electric/telephone/fire wiring in conduits. With spirit polish on all wood work. (Full Height of 9' high partition's for MANAGER CABIN)	560 Sq.ft		
4.	<u>Low Height Partition For Chief Manager Cabin & Officers cabin</u> Supplying and fixing partly paneled and partly glazed with 50mm x30mm kail/sal wood frame at 16" C/c both ways with 6mm thick ply board on both sides, including provision of 1 1/2" thick solid flush doors wherever necessary with superior quality brass anodized fittings, handles provision of 6mm thick glass modi /approved make. Teak wood beading and making holes for electric/telephone/fire wiring in conduits. With spirit polish on all wood work. (Full Height of 9' high partition's for MANAGER CABIN)	380 Sq.ft		
5.	<u>FGM Table</u> Supplying Manager table size 7'x3'x2-6" with 3 drawers are shape, 3 sides covered with lamination.	1 No.		
6.	<u>AGM Table</u> Supplying Manager table size 6'x3'x2-6" with 3 drawers are shape, 3 sides covered with lamination.	2 No.		
7.	<u>Chief Manger Table</u> Supplying Manager table size 6'x3'x2-6" (5'x3'x2'-6") with 3 drawers are shape, 3 sides covered with lamination.	4 No.		
8.	<u>Officer Table</u> Supplying Manager table size 5'x2'-6"x2-6" (4'x2'-6"x2'-	8 No.		

	6") with 3 drawers are shape, 3 sides covered with lamination.			
9.	Side Rack for FGM Table (3'-6"x2.5')	1 No.		
10.	Side Rack for AGM Table (3'-6"x2.5')	2 No.		
11.	Side Rack for Chief Manager Table (3'-0"x2.5')	4 No.		
12.	Side Rack for officer table (3'x2.5')	8 No.		
13.	<u>Gypsum Board False Ceiling for FGM office , AGM office & Chief Manager cabin</u> Providing & fixing false ceiling as per design in perfect level and smooth finished with edge groove and cove lighting provision as per drawings, consist of G.I. frame, which includes perimeter channels along with the parameter of ceiling, with intermediate channel of size 45mm x 0.9 mm thick with two flange of 15mm each @ 1220mm c/c with ceiling angle of size 25x10x0.55mm fixed to bottom of ceiling with G. I. cleat 27mmx37mmx25mmx1.6mm and steal expansion fastener, ceiling section of 0.55mm thick with knurled web of 80mm and two flanges of 26mm each with connecting clips in the direction perpendicular to the intermediate channel at 457mm c/c, 12.5mm thick Gypsum board shall be fixed with screw with filling and finishing the tapered edge with jointing compound, paper tape and painted with two or more coats of plastic emulsion paint over a coat of primer. The item includes P/F perimeter channel of size 20x27x30mm and 0.55mm thick for light fittings,	980 Sq.ft		
14.	Anti termite treatment on all wooden works	2000 Sq.ft.		
15.	<u>Low Height Storage Cabinet</u> Providing and erecting in position low/ Full hight storage cabinet made of 19mm thick BWR grade block board including intermediate shelves, lockable shutters etc. conforming to following specifications : Shutter faces shall be finished with 1mm thick laminate sheet of same or combination shades as per instructions with polished white or steam beech wood (6mm thick) edge lippings, Inner faces of shutters shall be finished with 1mm thick white laminate, Shutters will be hung by auto-closing hinges of "Ebco" or equivalent locks, magnetic door [Payment shall be on the area of cabinet face]	125.0 Sq.Ft		
16.	Letter box (1'-6"x1'-0"x0'-6").	4No.		
17.	<u>Customer Stand</u> S & F in position writing desk of size 4'x15" x12" made of 114" thick block board. With place for keeping forms etc. shall have 1.00mm mica lamination and teak wood lipping on edges.	4 No		

18.	priming coat & two coats of acrylicemulsion on new & old surface internalwork incl. Supply of all material labour& material reqd. for proper completion of work.	3200 Sq.ft.		
19.	Notice Board (2'x4').	2No.		
20.	S/F Door Closer ISI marked	8 Nos.		
21.	S/F Mortice Lock	4 Nos.		
22.	S/F Alluminum Gate Partision for Branch & ATM	180 Sq.ft		
23.	<u>Dismantling & shifting of old furniture as per branch head</u>	Lumpsu m		
Amount in Words:				

G.S.T. Extra

Date:

Signature with Stamp

Name of Firm :

Address :

Phone No :

Note: 1.) Rs. 25000/- Deposit DD or FDR in favor of Indian Bank payable at Meerut (EMD)

2.) No advance will be paid. Payment will be released on satisfactory completion on job and submission of bills (only one running payment will be made). Retention money @ 10% (Including EMD) will be deducted from the bill and to be released after three month from the virtual completion provided no defects is observed during the period.

Approved color schemes for counter/partition/paneling of Braches

INDIAN BANK
Tender for Electrical Work of FGM office, Distt.: Meerut.

S.NO.	DESCRIPTION OF ITEM	QTY.	UNIT	RATE	AMOUNT
1.	SITC of Light Raw power MCB distribution board of TPN DB including all internal wiring etc complete, incoming 40 amps TP MCB- 1 No outgoing 10/16 amps SPMCB -12 Nos.	1.0	No.		
2	<u>Power wiring</u> Supply and wiring 2 runs of 2.5 sqmm and 1 run of 1.0 sqmm PVC Insulated flexible multi strand copper wire in 20 mm Dia 2 mm thick universal make PVC conduit / casing Capping as required for Lighting circuit, Raw power & wall fan points.	220 .0	Rmt.		
3	<u>Point wiring</u> Supply and wiring 2 Runs of 1.5 Sq.mm. & 1 Run 1.0 Sq.mm. PVC Insulated flexible multi strand copper wire in 20 mm Dia 2 mm thick universal make PVC conduit / casing Capping above false ceiling inside wall & floor as required from switch box to individual points switchs shall be use a) Single light point controlled by 6 amps switch (Modular).	135.00	Points		
4	<u>Sub main wiring</u> Supply and wiring 2 Runs of 6.0 Sq.mm. & 1 Run 2.5 Sq.mm. PVC Insulated flexible multi strand copper wire in 20 mm Dia 2 mm thick universal make PVC conduit / casing Capping above false ceiling inside wall & floor as required	40.00	Mts		
5	S/I of UPS points using 3 Nos. 5/15 amps sockets controlled by 15 amps switch including all accessories modular.	20.00	Nos.		

6	S/I of Power points using 1 Nos. 15 amps sockets controlled by 15 amps switch including all accessories modular.	12.00	Nos.		
7	S/I of AC Point using 1 No. 25 amps industrial socket & plug controlling 32 amps switch including all accessories modular.	12.00	Nos.		
8	S/I of fitting fixture including all accessories for fixing the fitting shall be Philips, Bajaj, Havells make 600x600 mm. recess type. LED Light fitting 36.0 Watt.	25.00	Nos.		
9	1 x 12 Watt LED down light panel with acrylic cover make Philips, Bajaj, Wipro make	30.00	Nos.		
10	Wall mounted fan Philips, Bajaj, Wipro make.	20.00	Nos.		
11	1 x 20 Watt service type LED patti fitting Philips, Bajaj, Wipro make.	5.00	Nos.		
12	1 x 9 Watt LED bulb with holder all complete with make Philips, Bajaj, Wipro .	3.00	Nos.		
13.	Telephone Points:- Supply & fixing of GI/PVC box suitable for fixing of Telephone Jack of 2 pin telephone socket as required with 2 pair of 0.63 mm Die annealed tinned copper conductor in PVC pipe for each telephone complete in all request as per drawing and specification give by architect.	15.00	Nos.		
14.	Point wiring with 2x4 Sq mm and 1x2.5 Sq mm PVC insulated single core copper wire in PVC conduit / Casing for power / Room A.C Point (Av. Run 10 Mts).	7.00	Nos.		
15.	Supplying and fixing 300 mm sweep Louverd fresher fan of Commercial/Industrial quality	3.00	Nos.		
16.	Supplying and fixing Call Bell with bell puch.	4.00	Nos.		
17.	Circuit wiring with 2x2.5+1x1.5 mm single core PVC insulated copper flexible wire in PVC flexible conduit at 15A & 5A point.	140.00	Mt.		

18.	Supply and wiring 2 Runs of 2.5 Sq.mm. & 1 Run 1.5 Sq.mm. PVC Insulated flexible multi strand copper wire in 20 mm Dia 2 mm thick universal make PVC conduit / casing Capping as required for UPS points	80.00	Mt.		
19.	Supply and wiring 2 Runs of 4.0 Sq.mm. & 1 Run 1.5 Sq.mm. PVC Insulated flexible multi strand copper wire in 20 mm Dia 2 mm thick universal make PVC conduit / casing Capping as required for AC & Power.	100.00	Mt.		
20.	DATA CABLING:-				
1.	Supplying and laying of 25 mm dia conduit.	100	Mt.		
2.	Supplying & laying of Cat - 6e UTP cable.	340.00	Mt.		
3.	Providing CAT - 6e mounting cord (1 mt)- factory crimped.	20.00	Nos.		
4.	Supplying & Fixing of CAT -6, I/O + SMB (single port	24.00	Nos.		
In Words:					

G.S.T. EXTRA

Note: 1.) Rs. 7000/- Deposit DD or FDR in favor of Indian Bank payable at Meerut (EMD)

2.) No advance will be paid. Payment will be released on satisfactory completion on job and submission of bills (only one running payment will be made). Retention money @ 10% (Including EMD) will be deducted from the bill and to be released after three month from the virtual completion provided no defects is observed during the period.

Thanking You
Signature of Contractor with Seal

ESTIMATE FOR A.C. WORKS FOR INDIAN BANK, FGM OFFICE, DISTT.: MEERUT (U.P.)					
S.NO.	PARTICULARS / DETAILS	UNIT	QTY.	RATE	AMOUNT
A	A.C. WORKS:-				
1	Air cooled Hi Wall Split AC Units Comprising Of:				
i	Nominal Capacity - 1.5 TR (Make - Voltas, Carrier) 3 Star Rating copper condensor 2018 make	Nos.	2		
ii	Nominal Capacity - 1.0 TR (Make - Voltas, Carrier) 3 Star Rating copper cpmdensor 2018 make (Manager cabin)	Nos.	1		
iii	Nominal Capacity - 2.0 TR (Make - Voltas, Carrier) 3 Star Rating copper condensor 2018 make	Nos.	2		
2	Installation testing comisioning of Hi -Wall Split AC				
i	1.5 TR. Capacity unit	Nos.	2		
ii	1.0 TR. Capacity unit	Nos.	1		
iii	2.0 TR. Capacity unit	Nos.	2		
3	Supply installation testing & comisioning of Voltage Stabilizer of approved make				
i	4 KVA for split AC (V Guard, Luminus)	Nos.	3		
ii	5 KVA (V Guard, Luminus)	Nos.	2		
	Note: All voltage stabilizer is sufficient for A.C. should have time delay facility.				
4	Copper Refrigerant Piping with electric cable :				
	Installation & commissioning of Soft copper piping with complete fitting & insulation				
i	1.5 TR. & 1.0 TR.	Rft	80		
ii	2.0 TR.	Rft	35		
5	Drain Piping				
	Hard PVC insulated drain water piping wrk of size 25 mm dia with complete fitting Etc.	Rft.	70		
6	Civil Work For cutting Chisling Plastering of walls to conseal copper pipe, Drain pipe & Electrical wire with plaster finish.	Rft	40		
7	Removing old split AC, window AC any TR. & proper cleaning indor as well as out door	Nos.	6		
	TOTAL -AC WORKS:-			Rs.	0
	G.S.T. EXTRA AS APPLICABLE				

Note: 1.) Rs. 5000/- Deposit DD or FDR in favor of Indian Bank payable at Meerut (EMD)

2.) No advance will be paid. Payment will be released on satisfactory completion on job and submission of bills (only one running payment will be made). Retention money @ 10% (Including EMD) will be deducted from the bill and to be released after three month from the virtual completion provided no defects is observed during the period.