

INDIAN BANK
ZONAL OFFICE MEERUT

Sealed quotation are invited from eligible **EMPANELED CONTRACTORS** of INDIAN BANK &/ or ALLAHABAD BANK as per the following details for execution of CIVIL, FURNISHING, ELECTRIC and A.C Works of our Zonal Office, Meerut. We expect the work to be completed within 45 days from the date of issuance of work order to the selected bidder.

Last Date for submission in sealed cover envelope in the office of The Zonal Manager, Indian Bank, Zonal Office, 55 The Mall Road, Meerut Cantt is 28.01.2021 (upto 05.00 PM). The bids will be opened on 29.01.2021 at 12.00 P.M.

Format for tender document can be collected from Indian Bank, Zonal Office, 55 The Mall Road, Meerut Cantt, from 20.01.2021 to 28.01.2021 during office hours only. Alternatively, the same can be downloaded from our Bank's website www.allahabadbank.in or www.indianbank.in. We expect you to use any of the following brands for various works. As such, quote your rates keeping the same in mind.

List of Approved Make for Furnishing works

- | | |
|-------------------|--|
| 1. Ply-Board | Duro/ Century/ Green, |
| 2. Glass | Modi Guard float/ Saint Gobin |
| 3. Adhesive | Fevicol SHL |
| 4. Aluminum Grill | Powder coated in off white shade |
| 5. Chancel, Rail | Ebco |
| 6. Paint Primer | Nerolac/Asian first quality |
| 7. Laminate | Century 303,191 Formica F1 1224 F1 1517(SF) |
| | Sunmica E 224/1224, Sunmica terracotta G448/1448 |
| 8. Tiles | Kajaria/ Nitco |

List of Approved Make for Electrical works

- | | |
|---------------------------------------|--------------------------------|
| 1. Wire | Finolex/ Havels/ Polycab/ R.R. |
| 2. Associre Modular Switch socket etc | Anckor/ Legrand/ Havels |
| 3. PVC pipe | AKG/ Plaza/ Sapia 2mm th. |
| 4. Fan | Khetan/ Bajaj/ Philips |
| 5. Fitting | Philips/ Bajaj/ Havels/ Siska |
| 6. MCD DB | Havels/ L&T |

List of Approved Make for AC works

- | | |
|----------------|--|
| 1. AC units | Voltas/ Carrier with Copper Condenser & Highly efficient compressors |
| 2. Stabilizers | V-Guard/Luminus |

All wiring, switch board etc shall be concealed

The Bank reserves the right to accept/reject any tender/quotation without assigning any reason whatsoever.

Broad Terms & condition:-

1. Payment will be released on satisfactory completion of job and submission of bills. Retention Money @10% of the contract amount will be put on hold & released after 06 months from the date of completion provided no defects are observed during the period.
2. Liquidated damage at the rate of 1% per week of the total order value subject to maximum of 10% of the contract value will be charged for delayed execution of work.
3. Before full completion of job, running payment upto 75% of the work completed will be made **ONLY ONCE** on production of bills. Payment will be released only after submission of completion certificate, as per terms and conditions specified in the work order, by the Bank's empanelled architect.

Date: 19.01.2021

Zonal Manager
Zonal Office, Meerut

Project- Proposed Flooring and Plaster Finishing works for Zonal office, Indian Bank, Mall Road, Meerut

BOQ & Estimate- Civil Works

S. No.	Particulars/ Details	Unit	Qty	Rate	Amount
1	Flooring Work				
	P/F Floor tiles 600 x 600 vetrified tile as required with 25 mm approx base Including supply of all materials labour & T&P etc. Make- Kajaria/ Somany	Sq.ft.	2400		
2	Plaster Finishing Work				
	12 mm thick plaster with cement & fine sand of 1.25 fineness modulus in 1:3 over brick work minimum thickness not to be less than 1cm Including supply of all materials labour & T&P etc.	Sq.ft.	2000		
	TOTAL				
	GST paid extra as Applicable				


Terms & Conditions:-

- Submission of bid along with empanelment letter of Indian Bank & Allahabad bank will be accepted only.
- Every Tender shall be accompanied by Earnest Money Deposit of Rs. 7000.00 to be submitted in the form of a DD in favour of Indian Bank, payable at Meerut. The Tender not accompanied by such Earnest Money are liable to be rejected straight away. (E.M.D in any other form is not accepted).
- Payment will be released on satisfactory completion on job and submission of bills (only one running payment will be made). Retention money @10% (including EMD) will be deducted from the bill and to be released after six months from the virtual completion provided no defects is observed during the period.
- Above mentioned approved makes / manufacturers shall be taken into consideration while quoting the price.
- Liquidated damage at the rate of 1% per week subject to maximum of 10% on Contract value applicable for the work completed after contractual delivery date.

Place:

Date:

Signature of contractor with seal



BOQ & Estimate- Furnishing Works

No.	Description of Items	Unit	Qty	Rate	Amount
1	PANELLING				
	Full Height Panelling for AGM Cabin Supplying and fixing 40mm x 20mm kail/sal wood frame at 16" C/C both ways with 6mm thick ply board & lamination one side. Teak wood beading and making holes for electrical / telephone/ Fire wiring in conduits. With sprite polsh on all wood work. (Full Height of 9'-0" high.)	Sq.ft.	1396		
2	PARTITIONS				
i	Full Height Partitlon for AGM Cabin & Chief Manager Cabin Supplying and fixing partly panelled partly glazed with 50mm x 30 mm kail/ sal wood frame at 16" C/C both way with 6mm thickply board on both sides, Including provision of 1"/2" thick solid flush doors wherever necessary with superior quality brass anodized fittings, handles provision of 6mm thick glass modl/ approved make. Teak wood beading and making holes for electrical/ telephone/ fire wiring in conduits. with sprit polsh on all wood work. (Full height of 9'-0" high partition's for Manager Cabin)	Sq.ft.	375		
ii	Low Height Partition for Chief Manager Cabin & Officers Cabin Supplying and fixing partly panelled partly glazed with 50mm x 30 mm kail/ sal wood frame at 16" C/C both way with 6mm thickply board on both sides, including provision of 1"/2" thick solid flush doors wherever necessary with superior quality brass anodized fittings, handles provision of 6mm thick glass modl/ approved make. Teak wood beading and making holes for electrical/ telephone/ fire wiring in conduits. with sprit polish on all wood work. (Full height of 4'-6" high partition's for Manager Cabin)	Sq.ft.	490		
3	FURNITURES				
A	TABLES				
i	AGM Table Supplying Manger table size 6'-0" 3'-0" x 2'-6" with 3 drawers are shape, 3 sides covered with lamination.	No.	1		
ii	Chief Manager Table Supplying Manger table size 5'-0" 2'-6" x 2'-6" with 3 drawers are shape, 3 sides covered with lamination.	Nos.	4		
iii	Officer Table Supplying Manger table size 4'-0" 2'-6" x 2'-6" with 3 drawers are shape, 3 sides covered with lamination.	Nos.	20		
B	STORAGES				
	Full height, Low height & Wall mounted Cabinet Providing and erecting in position low/ full height storage cabinet made of 19mm thick BWR grade block board including intermediate sheleves, lockable shutters etc. conforming to following specification: Shutter faces shall be finished with 1mm laminate sheet of same or combination shades as per instructions with polished white or steam beech wood (6mm thick) edge lipping , inner faces of shutters shall be finished with 1mm thick white laminate, shutters will be hung by auto-closing hinges hettich/godrej lockes, magnetic door (payment shall be on the area of cabinet face)	Sq.ft.	275		
	Side Storages				
	Side Storages for AGM Table (3'-6"L x 1'-3"B x 2'-6"H)	No.	1		
	Side Storages for Chief ManagerTable (3'-0" L x 1'-6" B x 2'-6"H)	Nos.	4		
	Side Storages for Officer Table (3'-0" L x 1'-6" B x 2'-6"H)	Nos.	20		



FALSE CEILINGS

Gypsum Board False Ceiling

Providing & fixing false ceiling as per design in perfect level and smooth finished with edge groov and cove lighting provision as per drawings, consist of G.I. frame, which includes perimeter channels along with the parameter of ceiling, with intermate channel of size 45mm x 0.9mm thick with two flange of 15mm each @1220mm c/c with ceiling angle of size 25x10x0.55mm fixed to bottom of ceiling with G.I. cleat 27mm x37mmx25mm x 1.6mm and steel expansion fastner, ceiling section of 0.55mm thick with knurled web of 80mm and two flnges of 26mm each with connecting clips in the direction perpendicular to the intermediate channel at 475mm c/c 12.5mm thick gypsum board shall be fixed with screw with filling and finishing the tapered edge with jointing compound, paper tape and painted with two or more coats of plastic emulsion paint over a coat of primer. The item includes P/F perlmeter channel of size 20x27x30mm and 0.55mm thick for light fittings

Sq.ft. 1575

Sq.ft. 2300

5 Anti termite treatment on all wooden works

No. 2

6 Letter box (1'-6" x 1'-0" x 0'-6")

No. 2

7 Notice Board (2'-0" x 4'-0")

Sq.ft. 180

8 S/F Aluminium gate pertition for R.M.P.C.

Nos. 8

9 S/F door Closer ISI godrej make marked

Nos. 6

10 S/F Mortice Lock Gogrej/ Ozone maked only

Sq.ft. 4750

11 Printing coat & two coats of acrylic emulsion priming coat & two coats of acrylic emulsion supply of aal materials labour and material required for proper completion of works.

LS As per site

12 Dismantling & shifting of old furnitures as per branch head.

Total

GST paid extra as Applicable

Terms & Conditions:-

1- Submission of bid along with empanelment letter of Indian Bank & Allahabad Bank will be accepted only.


2- Every Tender shall be accompanied by Earnest Money Deposit of Rs. 30000.00 to be submitted in the form of a DD in favour of Indian Bank, payable at Meerut. The Tender not accompanied by such Earnest Money are liable to be rejected straight away. (E.M.D in any other form is not accepted).

3- Payment will be released on satisfactory completion on job and submission of bills (only one running payment will be made). Retention money @10% (including EMD) will be deducted from the bill and to be released after six months from the virtual completion provided no defects is observed during the period.

4- Approved Bank colour schemes for counter/ partition/ paneling of Branches.

5- Liquidated damage at the rate of 1% per week subject to maximum of 10% on Contract value applicable for the work completed after Contractual delivery date.

6- List of approved makes / manufacturers shall be taken into consideration while quoting the price as per Annexure- A only.



RECOMMENDED MAKE TO BE USED FOR ZONAL OFFICE, INDIAN BANK, MEERUT

S.NO	DESCRIPTION	MAKE/BRANDS
1	PLYWOOD – BWP (Boiling Water Resistant, Termite Resistant & Borer Resistant) – CONFIRMING TO IS: 303.	CENTURY/GREEN/ DURO
2	BLOCK BOARD – CONFIRMING TO IS :11255 - 2003.	CENTURY/GREEN/ DURO
3	FLUSH DOOR – CONFIRMING TO IS : 2202 (Part – 1) – 1991.	CENTURY/GREEN/ DURO
4	LAMINATE – CONFIRMING TO IS : 2046-1995.	CENTURY303, 191/ Formica F1 1224 & F1 1517 (SF)/ Sunmica E 224/1224, Sunmica terracotta G448/ 1448
5	Lipping & Moulding	First Class Teak Wood
6	Gypsum ceiling	Gypsum India/ Saint - Gobain Gyproc india
7	Grid Ceiling	Armstrong, Dexune
8	GI Support system for False Ceiling	GYPSTEEL ULTRA
9	Adhesive	Fevicol SH.
10	Locks/Handles & all other hardware	Godrej/ Dorset/ Harison
11	Glass	Modi/Asahi(Tata)/ Saint Gobain
12	Aluminium	Jindal/Hindal/Indal
13	Door Closer	OZONE/Dorma/ doorset
14	FLOOR SPRING	OZONE/GODREJ/ dooet
15	Vertical Blinds	Vista/ Mac/ Hunter duglas
16	Paint	Nerolac / Asian Paints
17	Wood Preservative	Bison by British Paints / Termiseal by ICI
18	Cement	ACC/ Ultra tech /Birla Plus
19	Preservative	Solignum/Black Japan / Termiseal
20	Sanitary Fittings	Kohler / Hindware
21	CP fittings	Jaguar
22	GI pipe	Jindal/Bhushan
23	Floor & Wall tiles	Somany/Kajaria
24	Overhead Water tank	Sintex

NOTE-

- 1- All other materials shall be best quality heavy section ISI mentioned in the drawings as well as in bill of quantities and also approved by bank/Consultant.
- 2- The contractor is strictly advised to use the makes specified/approved by the Bank/Architect, unspecified items will not be paid until they are changed with the specified ones.
- 3- The Plywood used for the work shall be BWR (Boiling water proof range) confirming to IS 303 as per brand specify.

Place:

Date:

Signature of contractor with seal



Project- Electrical Works for Zonal office, Indian Bank, Mall Road, Meerut

BOQ & Estimate- Electrical Works

S. No.	Description of Items	Unit	Qty	Rate	Amount
1	SITC of light RAW power MCB distribution board of TPN DB including all internal wiring etc complete including 40 amps TP MCB- 1 No outgoing 10/16 amps SP MCB-12 Nos.	No.	1		
2	<u>Power Wiring</u> Supply and wiring 2 runs of 2.5 sqmm and run of 1.0 sq.mm PVC Insulated flexible multi strand copper wire in 20mm Dia 2mm thick universal make PVC conduit/ casing capping as required for lighting circuit. RAW power and wall Fan points.	Rmt.	229		
3	<u>Electric point wiring complete</u> Supply and wiring 2 Runs of 1.5 Sq.mm. & 1 Run 1.0 Sq.mm. PVC Insulated flexible multi strand copper wire in 20mm dia 2 mm thick universal make conduit/ casing capping above false ceiling inside wall & floor as required from switch box to individual points switches shall be use. a) Single light point controlled by 6 amps switch (Modular)	Points	150		
4	<u>Sub Main Wiring</u> Supply and wiring 2 Runs of 10.00 Sq.mm. & 1 Run 4.0 Sq.mm. PVC insulated flexible multi strand copper wire in 20mm dia 2 mm thick universal make conduit/ casing capping above false ceiling inside wall & floor as required.	Mtr	75		
5	S/I of UPS points using 3 Nos. 5/15 amps sockets controlled by 15 amps switch including all accessories modular	Nos.	30		
6	S/I of Power points using 1 Nos. 15 amps sockets controlled by 15 amps switch including all accessories modular	Nos.	15		
7	S/I of AC points using 1 Nos. 25 amps industrial sockets & plug controlling by 32 amps switch including all accessories modular	Nos.	15		
8	S/I of fitting fixture including all accessories for fixing the fitting shall be Philips/ Lighting Technologies/ Wipro Make. 600 x 600 mm recess type LED Light fitting 36 Watt.	Nos.	20		
9	1 x 12 Watt LED down Light panel with acrylic cover make- Philips/Bajaj/ Havells	Nos.	40		
10	Wall mounted fan Crompton/ Hevalls/ Usha	Nos.	26		
11	1x 20 Watt services type LED battens fitting Philips/Bajaj/ Havells	Nos.	5		
12	1x 9 Watt LED bulb with holder all complete with make Lighting Philips/Bajaj/ Havells	Nos.	3		
13	<u>Telephone Points:-</u> Supply & fixing of GI/ PVC box suitable for fixing of Telephone Jack of 2 pin telephone socket as required with 2 pair of 0.63 mm die annealed tinned copper conductor in PVC pipe for each telephone complete in all respect as per drawing and specification given by Architect.	Nos.	15		
14	Point wiring with 2x4 Sq.mm. and 1x2.5 Sq.mm. PVC insulated single core copper wire in PVC conduit/ Casing for power/ Room AC point (Av. Run 10 Mts.)	Nos.	10		
15	Supplying and fixing 300 mm sweep Louverd fresher fan of Commercial/ Industrial quality Make- Havells/ Khaitan/ Usha	Nos.	3		
16	Supplying and fixing call bell with bell push.	Nos.	4		
17	Supplying and fixing 1x 2.5 Sq.mm. single core PVC insulated copper circuit wiring with 2x 2.5 + 1x 2.5 Sq.mm. PVC insulated flexible conduit at 15A & 5A point.	Mtr.	150		
18	Supply and wiring 2 Runs of 2.5 Sq.mm. & 1 Run 1.5 Sq.mm. PVC insulated flexible multi strand copper wire in 20 mm Dia 2mm thick universal make PVC conduit / casing capping as required for UPS points.	Mtr	130		
19	Supply and wiring 2 Runs of 4.0 Sq.mm. & 1 Run 1.5 Sq.mm. PVC insulated flexible multi strand copper wire in 20 mm Dia 2mm thick universal make PVC conduit / casing capping as required for AC & Power	Mtr	125		



20	DATA CABLING				
	Supplying and laying of 25 mm dia conduit.	Mtr	100		
1	Supplying and laying of CAT-6e UTP cable.	Mtr	490		
2	Providing CAT-6e mounting cord(1mt)- factory crimped.	Nos	20		
3	Supplying and laying of CAT-6, 1/0 + SMB (single port)	Nos	32		
	TOTAL				
	GST paid extra as Applicable				

Terms & Conditions:-


1- Submission of bid along with empanelment letter of Indian Bank/ Allahabad Bank will be accepted only.

2- Every Tender shall be accompanied by Earnest Money Deposit of Rs. 8000.00 to be submitted In the form of a DD in favour of Indian Bank, payable at Meerut. The Tender not accompanied by such Earnest Money are liable to be rejected straight away. (E.M.D in any other form is not accepted).

3- Payment will be released on satisfactory completion on Job and submission of bills (only one running payment will be made). Retention money @10% (including EMD) will be deducted from the bill and to be released after six months from the virtual completion provided no defects is observed during the period.

4- Liquidated damage at the rate of 1% per week subject to maximum of 10% on Contract value applicable for the work completed after Contractual delivery date.

5- List of approved makes / manufacturers shall be taken into consideration while quoting the price as per Annexure- A only.



Annexure-A

RECOMMENDED MAKE TO BE USED FOR ZONAL OFFICE, INDIAN BANK, MEERUT

S.N.	Description	Approved Makes
1	PVC Conduit	AKG/ Plaza/Sapia 2mm th.
2	Ceiling Junction Boxes	Amar/Home lite/ANCHOR
3	Wires & cables	Havells/R.R./Polycab
4	Modular Switches, Sockets etc	Legrand/Havells/ Anchor
5	Lighting Fixtures	Philips/Bajaj/ Havells
6	M.C.B./RCCB/RCBO etc	Havells/L&T
7	Distribution Boards	Same As Above
8	MCCB	Havells/L&T
9	Change Over Switches	H.P.L./A.B.B./Standard/ L. & T.
10	End Termination accessories	Dowells/Usha/Brecco/Cosmos
11	Telephone Cables & accessories	Havells, Krone, Finolex,
12	Fans/Exhaust fans	Khaitan/ Bajaj/ Philips
13	Music Speakers	Philips/Bosch/Ahuja
14	Amplifiers	Philips/Bosch/Ahuja
15	DVR	Samsung, Honeywell, HIKVISION
16	Rg11, CAT5/CAT6 cables/Telephone wires	Legrand, Molex, D'Link, AMP
17	CCTV Dome Camera	Honywell, HIKVision
18	Hard Disk drive	Seagate, HIKVISION
19	Smoke/Heat/Optical Fire Detectors	Edward, Siemens, Appolo Or other I.S.I. Equivalent.
20	Response Indicators, Hooters	Edward, Siemens OR other ISI Approved.
21	Telephone Tag Block	Krone

Place:

Date:

Signature of contractor with seal



Project- AC Works for Zonal office, Indian Bank, Mall Road, Meerut

BOQ & Estimate- AC Works

S. No.	Particulars/ Details	Unit	Qty	Rate	Amount
A	A.C. Works:-				
1	Air cooled HI Wall split AC units Comprising of:				
i	Nominal Capacity- 1.5 TR (Make- Voltas/ Daikin) 3 star rating copper condenssor 2019 Make.	Nos.	9		
ii	Nominal Capacity- 1.0 TR (Make- Voltas/Daikin) 3 star rating copper condenssor 2019 Make.	Nos.	6		
iii	Nominal Capacity- 2.0 TR (Make- Daikin) 3 star rating copper condenssor 2019 Make.	Nos.	1		
2	Installation testing comisloning of HI - Wall Split AC				
i	1.5 TR. Capacity unit	Nos.	9		
ii	1.0 TR. Capacity unit	Nos.	6		
iii	2.0 TR. Capacity unit	Nos.	1		
3	Installation testing comisloning of Voltage stabllizer of approved Make				
i	4 KVA voltage stabilizers in copper for above capacity Air-Condltioners. (Make: V Guard/ Luminus) Note- All voltage stabilizer is sufficient for AC should have tme delay facility	Nos	15		
ii	5 KVA voltage stabilizers in copper for above capacity Air-Conditioners. (Make: V Guard/ Luminus)	No.	1		
4	Copper Refrigerant Piping with electrcal cable:-				
	Installation & commissioning of soft copper piping with complete fitting & installation.	Rft	300		
i	1.5 TR. & 1.0 TR.	Rft	35		
ii	2.0 TR.				
5	Drain Piping				
	Hard PVC insulated drain water piping wrk of size 25 mm dia with complete fitting etc.	Rft.	450		
6	Civil Works for cutting chisling plastering of walls to conseal copper pipe drain pipe & Electrical wire plaster finish	Rft.	300		
7	Removing old split AC, window AC any TR stage as per Bank officers instructions complete as per bank satisfaction.	Nos.	16		
	TOTAL				
	GST paid extra as Applicable				

Terms & Conditions:-

- 1- Submission of bid along with empanelment letter of IndianBank/ Allahabad Bank will be accepted only.
- 2- Every Tender shall be accompanied by Earnest Money Deposit of Rs. 13000.00 to be submitted in the form of a DDin favour of Indian Bank, payable at Meerut. The Tender not accompanied by such Earnest Money are liable to be rejected straight away. (E.M.D in any other form is not accepted).
- 3- Payment will be released on satisfactory completion on job and submission of bills (only one running payment will be made). Retention money @10% (including EMD) will be deducted from the bill and to be released after six months from the virtual completion provided no defects is observed during the period.
- 4- List of approved makes / manufacturers shall be taken into consideration while quoting the price only.
- 5- Liquidated damage at the rate of 1% per week subject to maximum of 10% on Contract value applicable for the work completed after Contractual delivery date.

Note :

- i- AC units of Voltas/ Daikin only; AC's with COPPER Condenser & Evaporator coils are only to be supplied.
- ii- Only one of these Makes to be quoted.
- iii- Pl. enclose Tech. Brocher of the quoted Cassette/ Split A.C.
- iv- A.C.'s having Service centre In/Near the City should be preferred.

Place:

Signature of contractor with seal

Date:

