

Zonal Office:Gonda

NOTICE INVITING TENDER

Sub: COMPETITIVE QUOTATION FOR INTERIOR FURNISHING OF WAZIRGANJ BRANCH UNDER GONDA ZONE

Competitive sealed quotations are invited in the prescribed format from the contractors who are already empanelled with bank executed interior furnishing of nationalized Banks in last three years.

Formats of Quotations document is enclosed for submission of interior furnishing work of Wazirganj branch Distt-Gonda. Full details and tender document are available in Bank's website www.indianbank.in or can be obtained from Zonal Office Gonda. Duly filled tenders should be submitted as per following schedule:

1	Issue of Tender Document	From 29.05.2021 to 10.06.2021
2	Submission of Tender	On or before 10.06.2021 up to 5:00PM
3	Opening of Tender	On 11.06.2021 at 01:00 PM
4	Date of Commencement	7 Days from the date of issue of letter awarding the job
5	Time of Completion	20 days
6	Defect Liability Period	12 Months
7	Earnest Money	Rs.5000/- in form of DD/IOI in favour of Indian Bank payable at Gonda
8	Liquidated Damages for delay	Rs.2000/- per day subject to Max. of 10 % of accepted contract amount. (If the work is not completed to the satisfaction of the Employer within the stipulated period the contractor shall be bound to pay to the employer a sum equivalent to Rs. 2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.
9	Payment Terms	Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period.
10	Document to be attached with the Bill	Manager completion Certificate, Manufacture Certification Bills & 4-5 photographs showing completion atatus of work.
11	Retention Money	10% (Including Earnest money)

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tender without assigning any reason whatsoever. Late/delayed tender shall not be accepted after due date and time of submission of tender.

Zonal Manager

CLIENT

INDIAN BANK

**ZONAL OFFICE Gonda- Premises Department
Bahraich Road, Near Roadways Bus stop Gonda
Uttar Pradesh-227001**

WORK /PROJECT

**PROPOSED INTERIOR FURNISHING WORKS AT
INDIAN BANK ,WAZIRGANJ BRANCH,DISTT- GONDA**

**COMPETITIVE QUOTATION
FOR INTERIOR FURNISHING WORKS AT ABOVE PROJECT**

Tender Issued to

M/S

Address.....

.....

Contact No

Tender Issued on :.....

Last Date of Submission :

Signature of the Contractor

seal

Zonal Office:Gonda

NOTICE INVITING TENDER

**Sub: COMPETITIVE QUOTATION FOR INTERIOR FURNISHING
OF WAZIRGANJ BRANCH UNDER GONDA ZONE**

General terms & Conditions:-

- 1) Sealed quotation should be addressed to The Zonal Manager, Indian Bank, Zonal Office Gonda and super scribed name of Work Furnishing Work of Wazirganj Branch, at Wazirganj , Distt- Gonda and should reach before 5:00 p.m. on 10.06.2021 at Zonal Office Gonda.

Mailing Address:

The Zonal Manager,
INDIAN BANK
Zonal Office Gonda
Bahraich Road,Near Roadways Bus Stop, Gonda-271001(U.P)

- 2) No quotation will be accepted after 5:00 pm on 10.06.2021 and quotations will be opened on 11.06.2021 at 1:00 pm unless otherwise informed.
- 3) The quotations will remain valid for a period of 3 months from the date of opening.
- 4) Bank reserves the right to accept or reject any or all the quotations accept part of any tender, entrust the entire work to any contractor or divide the work to more than one contractor (item wise) without assigning any reason to do so or giving any explanation. The rates quoted by the contractors will help well for bifurcation and no compensation will be paid on this account.
- 5) At the time of submission every quotation must be accompanied by IOI/ Demand Draft for an amount of Rs.5000/- in favour of INDIAN BANK payable at Gonda towards EMD. Any quotation which is not accompanied by EMD will be summarily rejected.
- 6) Contract should quote rates in figures as well as in words.
- 7) All erasures and alterations made must be attested with the initials of tenderers. No overwriting is permitted.
- 8) The EMD of the unsuccessful bidders will be returned within 45 days from the date of opening the tender.
- 9) Joint tenders shall not be considered. Conditional tenders quoted by the contractor are liable to be rejected.
- 10) No escalation in the rates will be allowed under any circumstances.
- 11) On receipt of the intimation from the bank of the acceptance of his quotation, the contractor should submit his acceptance within 3 days If the successful contractor/ tenderer fail to undertake the work within 7 days after work allotment, the MMD will be forfeited and acceptance of his tender may be withdrawn.
- 12) The rate quoted in the tenders shall be inclusive of all materials as required and shall be inclusive of all charges of scaffoldings, lifting, tools and plants, freights/ transportation, labour conditions and fluctuations in rates of excise duty, octroi, GST, VAT, Excise Duty, service tax and any other taxes or expenditure of carrying out the works.
- 13) The Agency is advised to inspect and examine the sites and satisfy himself as to the condition prevailing at sites and its surrounding extent of work, scope and conditions under which the work is to be executed. The contractor shall also satisfy himself about the accessibility to the premises.

- 14) The agency shall submit the offer which satisfies each and every condition laid down in this notice, failing which the tender will be liable to be rejected. Conditional bids shall not be considered and will be out rightly rejected in the very first instance.
- 15) Work will be completed within the period of 20 days from the date of issue of tender or work order whichever is earlier. If the work be not completed to the satisfaction of employer within the stipulated period, the contractor will be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of Max 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains uncommenced or unfinished after expiry of the completion date. The contract may be rescind by giving one week notice incase work is not executed as per specification and as per time schedule given in tender document.
- 16) The liquidated damages as mentioned in the Notice inviting tender may not be enforced if the contractor applies for extension of time mentioning the genuine reasons for extension. If an extension of time of completion of the work is sought on the grounds of having unavoidable hindrances in his execution or any other ground, the contractor shall apply in writing to the Zonal Manager, Zonal Office Gonda with full details of the circumstances which is causing such an extension. Extension of time in days will be granted by the bank if it is proved that the contractor is not at fault for extending the work beyond stipulated date of completion. At the decision in this regard taken by the Bank shall be binding to the contractor.
- 17) The successful contractor is bound to carry item of work necessary for completion of job even though the same are not included in the schedule of quantity. Rates of extra item will be derived from quotation. In case the rates do not exist in quotation and extra item is not similar to the quoted item, then the rates will be worked out on actual cost of material and labour, any other expenditure for completing that work plus 15% towards contractors profit and overheads.
- 18) The work shall be carried out in such a way that, there is least disturbance to the staff of Bank. Contractors are required to organize the work in such a way that workings of staff and officers/executives of Office are not affected. Contractor is required to take adequate Care during progress of work to protect belongings. In case any damage, contractors at their own cost shall make the same good.
- 19) The contractor must co-operate with other contractors appointed by the bank so that entire work shall proceed smoothly and to the complete satisfaction of the Bank.
- 20) Contractor will arrange necessary tools and plants for completing own work at their cast. In case of any accident the total responsibility will be on the contractor. Contractors are required to submit time schedule of work. After completion of work, cleaning of floors, walls etc are to be done on daily basis to the satisfaction of Branch Head / engineer-in-charge. After completion of jobs, the site shall be cleared of all rubbish malba /debris etc in all respect and handover the site in proper manner on completion of the work.
- 21) No advance will be paid. Payment will be released on satisfactory completion of job and submission of bills. Retention Money @10% will be deducted from the bill and to be released after twelve months from the data of virtual completion provided no defects is observed during the period.
- 22) in case of non-completion or delay in completion of work or removal of defects in time, the bank shall be free to appoint another agency to get the job done at contractors risk and cost.
- 23) The contractor will attend to all the defects noticed during defect liability period. If the contractor fails to attend the defects these defects will be got rectified by the bank and the expenditure incurred on this account will be recovered from security deposit / retention money.
- 24) The work shall be got approved by the Architect / engineer and the contractor shall rectify any bad workmanship pointed out at any stage and remove from the site all the rejected materials immediately at his own cost.
- 25) The contractor shall acquaint himself with the site conditions making his own arrangements for storing of materials at site, lift, cartage etc. at his own risk and safety.
- 26) The Contractor shall make adequate arrangement for watch and ward of material and shall ensure the safety, breakage and any theft of material fixed or unfixed by him or the other sub contractors. The bank shall not be liable for any sort of loss incurred.
- 27) The contractor shall be responsible for application of labour laws, compensation for injury and accident to person, whether employed by him or his sub-contractor.

- 28) The contractor shall ensure that the workmen employed by him for the execution of work are suitably covered against Workmen Compensation Act and that all liabilities arising out of Workmen's .
- 29) compensation Act, ESIS and other legislative enactment applicable to such works and workmen shall be to the contactor's account and responsibility.
- 30) Civil, Interior Furnishing and Electrical Works will be carried out as per Bank's standard drawing / specifications and to the entire satisfaction of the bank.
- 31) The contractor shall inform the bank, well in time, to check measurements of anywork, which is likely to be hidden before covering.
- 32) Income tax at me prevailing rates will be deducted at source from contractor's bill and will be deposited with I.T.O. as per rules.
- 33) Any extra work or item can only be started by contractor after obtaining written approval from the Zonal Office. Item executed without prior approval from the Zonal Office will not be considered for payment.
- 34) The quantities mentioned in the schedule of quantities are approximate. Payment will be made on the actual work done by the contractors. However the contractor should not deviate the quantity without Banks permission.
- 35) The Bank has the right to alter the nature of work and to add or omit any items of work or to have the option of the same carried out departmentally or otherwise and such alterations or variations shall be carried out without prejudices to the contract.
- 36) The Bank has the right to terminate the contact if the contractor abandons the work or fails to commence the work in time, or fails to abide by the terms & conditions of the contract.

I have read and understood all the instructions/conditions given above and I have taken into account the above instructions/conditions while quoting the rates.

Date:

(Signature of the Contractor)

Place:

Seal

Bharat and Associates.
**Architects, Engineers, Interiors &
 Landscape Designers,**
 Shop no-1,First Floor,Jeevan Plaza
 Viram Khand-5 ,Gomti Nagar,Lucknow-226010
E-Mail: bharatandassociateslko@gmail.com

PROJECT - FURNISHING WORKS

BANK - INDIAN BANK

BRANCH -WAZIRGANJ

ZONAL OFFICE- GONDA

***ALL ITEM TO EXCLUSIVE OF TAXES. Taxes to Mention By the Contractor.**

***ALL WORKS TO BE DONE AS PER TENDER CONDITIONS**

Laminate use only-Century,Green,Archid,Sunmica Aica (Other Laminate is not Acceptable)

	FURNISHING WORKS	QTY	UNIT	RATE	AMOUNT (Rs.)
1	<u>FULL HEIGHT GLAZED & UNGLAZED PARTITION (HT -8'-6")</u>	65.00	Sq.Ft		
	Glazed Partition(upto false ceiling height only considered and above necessary ceiling supports to be provided) with Anodized Aluminium frame work, heavy sections (2mm thickness) of 2"x1.5" section, spacing of 2'0"x2'0" on bothsides and covered with 9mm thick BWR plywood (Green & Century finished with 1mm thick laminate of skirting & borders on both sides.Above 1'0"/2'6"/3'0" height partition,fixed with 8.0 mm bevelled glass with 3m sticker works door and teak wood beading with duco paint. Clear glass shall be finished with frosted film sticking over the glass of approved pattern and design. Rate to include providing cutouts and provisions to run electrical conduits, switches, etc.. Cost include wastages, transports, loading, unloading charges, labours, materials, tools, lead, lift and etc.Complete as per drawings and instructions of the Architect.				
	The job shall also include for provision of laying conduits, switch boxes etc. The erection of partition shall include for expansion bolts cleats, clamps bolts, nuts, screws, rivets and other accessories, all complete up to the satisfaction of the Architect.				
	All door opening shall have rebated teak wood framework (size - 75mm x 50mm, as per profile) on vertical (2 Nos.) and horizontal (1 No.) sides, with melamine finish and rebate of 40mm x 12mm, all complete up to the satisfaction of the Architect.				
	the partition and doors shall have hinges floor springs/sliding arrangement/hydraulic door closer, mortise locks (Godrej make all), etc. The rate shall include cost of all materials, labour, T&P, wastages, etc. required for proper completion of work, all complete to thesatisfaction of the Architect.				
	For unglazed partitions, no glazing to be given in partition/doors & other specifications as above				
2	<u>UPS Partition with Bisom board ht. 4'-6" rest specification as per as above partition.</u>	80.00	Sq.Ft		
3	<u>Low Height Partition. Glass to be etched</u>	48.00	Sq.Ft		
	Same specification as in 1 but P/F half height partition of height 4'-6" with wooden laminate till 3'-0" and 1'-6" height 12 mm thick glass secured with D brackets including all hardware necessary with the same specs. as above.				

4	<u>Cash Cabin Partition</u>	245.00	Sq.Ft		
	Providing and fixing in position 7'-7" high partly glazed partition for Cash Cabins as per drawing nos. (2-A, 2-B, 2-C, 2-D & 2-E) including door drawing no.(12) in frame work at 2' x 2' grid (horizontally and vertically) comprising of 2" x 1.5" TW/ HW. Section and/ or as per frame work shown in the drawings with 6mm plywood on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawing. Item to include 8 mm thick Glass with etching and frosting as per design and 2"x 2" T W/ HW. member for door sides and glass sides and TW. door frame to take 8 mm thick glass with etching and frosting.				
	The door will be provided with TW/HW. louvers finished in melamine polish of matching laminate colour. The doors are also to be provided with Godrej Night Latch. Two wooden trays are also to be provided as per drawing. Necessary cutouts are to be provided in the glass and the edges of the glass cutouts are to be finished in mirror polish. All exposed TW. surfaces to be finished in melamine polish of matching laminate colour as directed including all Necessary Stainless Steel finish fittings/ hardware, door closers, Godrej locks and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/ Bank complete in all respects.				
5	<u>Aluminium Jali on Cash Cabin Top</u>	75.00	Sq.Ft		
	Providing and fixing of aluminium grill with square size 75mm x 75mm - 8mm, on top of the cash cabins etc. The grill shall be tightly stretched and nailed to a wooden frame work, made out of 50mm x 40mm teak/hard wood (with anti-termite) members at 750mm c/c approx. both ways or as per site conditions. The erection of framework shall include for expansion bolts cleats, clamps bolts, nuts, screws, rivets and other accessories. All teak wood surfaces shall be painted with two coats of synthetic enamel over one coat of primer. The rate shall include cost of all materials, labour, T&P, wastages, etc. required for proper completion of work, all complete to the satisfaction of the Bank.				
6	<u>Glass Barrier</u>	15.00	Sq.Ft		
	Providing & fixing 12 m.m. glass in front of cash cabin and front counters with brass clamps including cut out for passing currency as/details. The edges of the glass to be machine polished.				
7	<u>Front office counter :-</u>	20.00	Rg.Ft		
	Providing and fixing in position front office counter 2'-6" wide as per drawing no. (1-A,1-B,1-C,1-D & 15) comprising of the following complete in all respect :-				
	i) Working top made with 19 mm thick plywood/ commercial board finished with 1 mm thick laminate. Outside Edge of the working top shall be provided with 1 1/4" X 1" Teak wood moulding finished with melamine polish. Inside edge will be provided with 1/2" X 1" T.W. beading patti with melamine finish.				
	ii) Vertical facia (Apron) made with 18 mm thick plywood/ commercial board finished with 1 mm thick laminate with 1 mm thick Groove at the joint of laminates of two different shades				
	iii) Vertical drop (horizontal band) shall be provided on the facia below the working top made with 18 mm thick plywood/ commercial board finished with 1 mm thick laminate with provision for concealed light, 1 mm thick groove shall be provided at the joint of two different shades of laminate.				

	iv) Glazed partition above working top to be provided with 12 mm thick clear glass cut to the standard shape fixed to partition as per fixing detail and to boxing with concealed S.S finished 'D' brackets as shown in the drawing. The exposed edges of the glass shall be finished in mirror polish.				
	v) 3'-10" high boxing (10" x 10") made with 18 mm thick plywood/ commercial board finished with 1 mm thick laminate including Providing and fixing 6 mm thick square frosted glass at a height 3' -2" above finished floor level				
	vi) Glazed partition having height 1'-0" above the transaction top (in facia) shall be provided with 12mm thick glass (clear) with cut out 8" X 4" as per drawing. The edge of cut out and the top edge of glass are to be mirror polished and to be fixed to partition as per fixing details and to boxing with concealed S.S. finished 'D' brackets as shown in glass (Clear) above the slit to be fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing. The exposed edges shall be finished in mirror polish				
	vii) Vertical supports made with 18 mm thick plywood/ commercial board finished with white enamel paint.				
	viii) 7' -7" high Boxing (10" X 10") made with 18 mm thick plywood/ commercial board as per drawing with 1' -6" horizontal extension at the top including providing & fixing 6mm thick square frosted glass at the height of 5' -11" above Finished Floor Level.				
	ix) 1'-9" high boxing (5" x 5") made with 12 mm thick plywood finished with 1 mm thick laminate.				
	x) Telescopic CPU stand/ readymade keyboard tray shall be provided of approved model and make.				
	xi) Footrest made with T.W members of size 4" X 1.5" finished with french polish.				
	xii) Drawer unit as per drawing shall be provided with multipurpose godrej locks in Each Drawer. Facia of drawer unit shall be finished with 1 mm thick laminate and all other sides shall be finished with white enamel paint. The drawer shall be provided with handles (Stainless Steel finish) and Channels as per approval of the project Consultant/ bank.				
	xi) Boxing as per drawing made with 12 mm thick plywood finished with Synthetic enamel paint shall be provided below the table top for electrical conduiting and at the bottom for the Lan Cabling /telephone wire Conduiting.				
	The item to include all necessary hardware and fitting in stainless steel finish, lipping to all edges and making provision only for electrical fitting behind the front. Vertical drop and also in the 10" X 10" boxing as shown in the drawing. Necessary beadings with melamine polish for fixing the glass are to be provided.				
8	<u>Cash Counters</u>	10.00	Rg.Ft		
	Providing and fixing in position cash counter 2' -9" wide as per drawing no. (2-A , 2-B , 2-C , 2 -D, 2 -E, 2 - F) comprising of the following:				
	i) Working top made with 19 mm thick plywood/ commercial board with 19mm black grenite finished and other portion 1 mm thick laminate. Outside Edge of the working top shall be provided with 1 1/4" X 1" Teak wood moulding finished with melamine polish.inside edge will be provided with 1/2" X1" T.W. beading patti with melamine polish.				

	iii) Vertical drop (horizontal band) shall be provided of facia below the working top made with 19 mm thick plywood/ commercial board finished with 1 mm thick laminate with provision for concealed light, 1 mm thick groove shall be provided at the joint of two different shades of laminate.				
	iv) Glazed partition of 1' -4" height above working top provided with 12 mm thick toughened and frosted glass beside non-transparent film from inside fixed to partition as per fixing details and to boxing with concealed S.S finished in mirror polish.				
	v) Transaction top shall be provided with 12mm thick toughened glass (partly glazed partly frosted) fixed horizontally with concealed stainless steel D bracket. Both exposed edge (inside and outside) shall be moulded and finished in mirror polish.				
	vi) Glazed partition having height 1'.0" above the transaction top (in facia) shall be provided with 12mm thick glass (clear) with cut out 8" X 4" as per drawing .the edge of cut out and the top edge of glass are to be mirrior polished and to be fixed to partition as per fixing details and to boxing with concealed S.S finished ' D' brackets as shown in glass (Clear) above the slit to be fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing.The exposed edges shall be finished in mirror polish.				
	viii) 7'-7" high Boxing (1 0"x 1 0") made with 18mm thick plywood/ commercial board as per drawing with 1-6" horizontal extension at the top including providing' and fixing 6 mm thick square frosted glass at a height of 5" - 11" above Finished Floor level.				
	ix) 1'-9" high boxing (5"x 5") made with 12 mm thick plywood finished with 1 mm thick laminate are to be provided.				
	x)Telescopic CPU Stand/ readymade Keyboard tray shall be provided of approved model and make.				
	xi) Footrest made with T.W. member of size 4"X1 1/2 "finished with french polish.				
	xii) Drawer units as per drawing shall be provided and each drawer should have vertical partitions for keeping the currency notes and multipurpose Godrej locks. Facia of drawer unit shall be finished with 1 mm thick laminate and all other sides shall be finished with white enamel paint The drawers will be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant / Bank.				
	xi) Boxing as per drawing made with 12mm thick plywood finished with Synthetic enamel paint shall be provided below the table top for electrical conduiting and at the bottom for the LAN Cabling/ Telephone wire conduiting. The item to include all necessary hardware and fittings in Stainless Steel finish, lipping to all edges and making provision only for electrical fitting behind the Vertical drop and also in the 1 0"x1 0" boxing as shown in the drawing. Necessary beadings with matching melamine polish for fixing the glass are to be provided as per drawing/ as directed.				
9	Supplying and fixing in position 32 mm thick solid core hot pressed phenol formaldehyde bonded flush door fininshed with 1.0 mm thick laminate of approved shade and quality on both sides of the door shutter & beading on edges including cost of hardware fitting e.g.-Godrej night latch/ mortise lock, hinges, door closure, handles etc. of approved make and quality & making provision of peep hole of suaitable size with glass & beading all- round all as directed .(Cash/Store/Other doors)	21.00	Sq.Ft		

10	Supplying and fixing in position 32 mm thick solid core hot pressed phenol formaldehyde bonded partly glazed flush door shutter of approved make finished up to 900 mm from floor level with 1.00 mm thick laminate of approved quality on both sides of the door shutter & beading on edge .The upper portion of the Shutter is to be Provided with 12 mm thick clear float glass fixed with white or steam beach wood glazing beads of approved design, complete as per drawing. Rate to include cost of hardware fittings e.g.-mortise lock, hinges, handles, door closer etc. of approved make and quality.(Manager cabin door)	21.00	Sq.Ft		
11	FLAP DOOR- Providing and fixing Door of min. size: 3'(B)X 2'-6"(H) Made of block board with approved lamination on both side, required size with hinges/tower bolts/stopper/handles etc complete	20.00	Sq.Ft		
12	ENTRANCE DOOR(WITH ETCHING, HT.-8' & GLASS - 12mm THICK) Providing fabricating & fixing in position twin - style door at Main Entrance made of anodized/powder coated Aluminium sections of size 100 mm height X 50 mm thick aluminium bottom rail, 100mm X 50mm thick vertical and top rail 100 mm X 50mm thick lock rail floor spring of ISI make, clip sections and 12mm thick glass(Modi/Saint Gobain make) including fixing the frame to brick wall/RCC/wooden surfaces with necessary fasteners to have proper fixity including all incidentals etc complete . Glass to be fixed in the grooves of the aluminium section with necessary materials/beading etc. The job also includes cost of providing & fixing heavy duty double action hydraulic floor spring(ISI mark) in the floor, fixing the door on it, including necessary fixing materials on the lintel/bottom, bolts, locks & satin finish stainless steel decorative tubular handles(approx.300mm log) on both faces complete as per drawing and instructions. All members to be 16 gauge. The vertical shutter rail to house wool packing to act as a sealant for a gap between shutter and frame fixed glazing. The rate should also include cost for decorative etching on the glass.	90.00	Sq.Ft		
13	Tables				
A	Chief Manager's Table with Side credenza(Side Table) include the 12 mm thick glass	1	Nos.		
	Providing and placing in position tables with top,vertical sides/dividers,skirting and modesty panel made out of 19 mm thick Premium Board (Green/Century) with 1mm thick laminate (as/shade approved by the Architect) on all exposed surfaces.It shall also have 75 mmx40 mm teak wood runners below the top and for footrest below. Every table shall be provided with a side unit(size-W-500mm,H-750mm,D-500mm approx.),consisting of 150 mm deep drawer at top and a cabinet with open able/hinged shutter below.				
	The job shall include for 6mm x 6mm grooves in between sides and open able drawers and hinged shutters. All the exposed edges of Premium Board (Green /Century) and ply shall be provided with 6mm thick teak wood/hard wood lipping. All teak wood surfaces shall be melamine polished and other internal surfaces shall be painted with two coats of synthetic enamel over one coat of primer, all complete to the satisfaction of the Architect. Every table top shall be provided with 10 mm thick float glass (as per profile) with polished and beveled (25mm wide) edges all complete to the satisfaction of the Architect				
B	Officer Table size 5'-6"x 3'-0"x 2'-6" With Side Table & 12 mm Thick Glass				
	SPECIFICATION AS PER MANAGER TABLE(PART -A)				

14	Writing Table & Brochure Holder	1	Nos.		
	Providing and fixing in position (with rear wall) slip and customer writing desk (as per design) of overall size-1200 mm x 450 mm x 300 mm. The fixing shall include for expansion bolts, cleats, clamps, bolts, nuts, screws, rivets and other anodized accessories, all complete up to the satisfaction of the Architect.				
	The writing top and facia/sides shall be made out of 19mm thick Premium Board (Green /Century) with 1mm thick laminate (as per shade approved by the architect), on all sides and . It shall be laid over the base of 19mm thick Premium Board (Green /Century) (already considered in various items.) and fixed with araldite. It shall include for beveling and polishing at all the exposed edges. The rate shall include cost of all materials, labour, scaffolding, wastages, polishing and T& P etc. It shall be made out of 12mm thick Premium Board (Green /Century) plywood (two surfaces of 6mm thickness, fixed together, where required) on rear and both sides.				
	The front shall be made out of 12mm thick glass (as per profile). It shall be fixed in the grooves, made in side members, in an inclined manner (as per profile in drawing enclosed) with a gap of 75mm (max.) in between. The space shall be further divided in four equal parts with help of 12mm thick Premium Board (Green /Century). All edges of the glass shall be polished. All the exposed edges of water proof board and plywood shall be provided with 6mm thick teak wood/hard wood lipping. All teak wood surfaces shall be melamine polished and other internal surfaces shall be painted with two coats of synthetic enamel over one coat of primer, all complete to the satisfaction of the Architect				
15	Complaint & Suggestion Box & Cheque Drop Box	2	Nos.		
	Providing and fixing in position complaints/suggestion box (as per design) with hinged shutter of size - 450mm x 600mm x 150mm made out of 19mm thick water proof board with 1mm thick laminate (as per shade approved by the architect) on all exposed surfaces. It shall have 6mm thick water proof plywood on the back.				
	The hinged shutter shall be made out of teakwood (section - 25mm x 50mm) framework, with 4mm thick float glass, fixed with teakwood (size - 12mm x 12mm) beading. The unit shall have cam locks, handles, spring hinges, magnetic catchers etc. of approved make. All the exposed edges of water proof board or ply shall be provided with 6mm thick teak wood/hard wood lipping. All teak wood surfaces shall be melamine polished and other internal surfaces shall be painted with two coats of synthetic enamel over one coat of primer, all complete to the satisfaction of the Architect.				
16	Notice Board	2	Nos.		
	Providing and fixing in position notice board (as per design) of size-900 mm x 600 mm x 150 mm. The sides shall be made out of 19 mm thick Premium Board (Green/Century) with 1 mm thick laminate (as per shade approved by the architect) on all exposed surfaces. It shall have 12 mm thick teak The front shall have 6 mm thick float glass sliding shutter in two parts.				

	<p>It shall also have 19mm wide two track aluminium channel for sliding arrangement, all around, along with locking arrangement. board (Make – Cellotex or equivalent) wrapped with stretched blazer cloth (Make- Raymonds), of Rs. 200.00 per Mt. (approx.) in colour and pattern approved by the Architect. It shall be fixed with help of kail/partal wood (sect. 19mm x 25mm) frame work. It shall be covered with 6mm thick Premium ply (Green /Century), on the back. All the exposed edges of water proof board and ply shall be provided with 6mm thick teak wood/hard wood lipping. All teak wood surfaces shall be melamine polished and other internal surfaces shall be painted with two coats of synthetic enamel over one coat of primer, all complete to the satisfaction of the Architect</p>				
	Total				
	GST Extra				