

Tender Document for Air Conditioning work of Panaji Branch, Indian Bank

	<b>SUMMARY</b>	<b>AMOUNT</b>
D	AC WORK	
	TOTAL D	
	GST AS APPLICABLE	

## Tender Document for Air Conditioning work of Panaji Branch, Indian Bank

Sr.no.	Items	Units	Qty.	Rate	Amount
1	Supply and installation of split A.C. Voltas make Supplying and erecting split type room Air conditioning unit (tonnage as mentioned below ) ton capacity suitable to operate on 250 volts, 50 cycles, A.C. Supply having 1 nos. of air handling units high wall mounting type having cooling capacity as per mentioned below and the condensing unit connected with 12/9mm copper piping upto 5 mtr duly insulated and 3 core copper flexible cord of required length etc. and stand for condensing unit with testing etc.complete and marking Sr no. and date of erection and remote. complete. with voltage stabiliser.				
	2T SPLIT AC ( IN BRANCH )	NO	2		
	1T SPLIT AC (IN ATM – 2 nos., manager cabin - 1 nos, mezz floor 1 nos.)	NO	4		
	TIMER	NO	1		
	PART A: SUPPLY OF MACHINERY TOTAL COST				
	PART B : INSTALLTION WORK				
2	ADDITIONAL COPPER PIPING	Per m	35		
	Copper piping between indoor and outdoor unit. Suction line to be insulated with elastomeric nitrile rubber tubular insulation of 9mm thickness and join sealed with black moonsoon tape, with electrical wiring complete				
3	Drain pipe	Per m	25		
	Drain piping of 25mm dia PVC pipe for drainage of condensate. (Prince /supreme make )				
4	Stands	Nos	6		
	MS stand / (for unit along with level adjustment .				
5	INSTALLATION CHARGES	nos	6		
6	Piping Concealing work , Making cashes in the wall filling with P.O.P making good the surface ,	Per m	-		
	PART B : TOTAL INSTALLATION WORK				
	PART A :				
	PART B:				
	TOTAL COST ( AIR CONDITIONING )				