

B.O.Q OF INTERIOR WORK FOR INDIAN BANK AT BERHAMPUR BRANCH.

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
A	PARTITION WORK.				
1.0	FULLY HEIGHT Partition (Semi Glazed)				
	<p>Providing and fixing in position partly glazed full Partition work as per drawing ,in frame work at 2'x2' grind (horizontally and vertically) comprising of 2"x1 ½" hevy gazed almunium section and/or as per frame work shown in the drawings with 9 mm plywood (conforming IS 710) on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 8 mm thick glass as per design and fitted with 3-1/4" thick beach wood beading and 2"x2" T.W. member for door sides . All exposed T.W / beading surfaces to be finished in melamine polish as directed including all necessary Stainless Steel finish fittings/hardware and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects.</p> <p>(Note : In case of false ceiling, the vertical members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only)</p>	Sft.	540.00		
2.0	LOW HT. HEIGHT Partition (Semi Glazed)				
	<p>Providing and fixing in position partly glazed 4'-0" HT. Partition work as per drawing ,in frame work at 2'x2' grind (horizontally and vertically) comprising of 2"x1 ½" hevy gazed almunium section and/or as per frame work shown in the drawings with 9 mm plywood (confermin IS710) on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 12 mm thick glass as per design and fitted with 3-1/4" thick beach wood beading at glass sides All exposed wood. surfaces to be finished in melamine polish of as directed including all necessary Stainless Steel finish fittings/hardware and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects.</p>	Sft.	130.00		
3.0	Full glazed Partition				
	<p>Providing , fitting & fixing 12mm thick flot glass partition with chemically eaching as per design.the partiton will be supported with S.S patch panel fittings as per drawing and design. The exposed edge of the glass partition should be polished to super quality. The work should be completed as per direction of architect including cost of all labour & material .</p>	Sft.	65.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
4.0	Pine wood beading Providing , fitting & fixing Pine wood beading in low height partition,cash counter front & low height cash counter front fascia with All pine wood beading surfaces to be finished in PU clear polish as directed . The work should be completed as per direction of architect including cost of all labour & material .				
	i)75mmx18 mm (as per design)	Rft	250.00		
B	DOOR WORK.				
1.0	Doors – semi glazed Providing and fixing partly glazed doors of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make (conforming IS 710) and finished with 1mm thick approved laminate on both sides. The edges finished with teak wood lipping. The shutter will have part glazed 8mm thk float glass with body itching of and necessary TW wood beading etc mat polished with melamine polish of asian / ici , complete to match the aligned partition elevations designs, the rates are inclusive of cost of necessary hinges, motise lock (7-lever- 8" lock of Godrej / Doorset make) , aldrops etc., all labour, materials, taxes, leads & lift to the place of work executed	Sft.	114.25		
2.0	Doors – glazed Providing and fixing Entrance Door (glazed) as per drawing in Black Anodised aluminium door single groove section of size 125mmx25mm (Jindal make) in top and bottom & sides glazed with 10 mm thick glass of approved make . Item to include all necessary hardware of Stainless Steel finish and chemical eaching with bank's logo as approved by the Project Consultant/Bank complete in all respects.				
	a) Open able portion (it include SS finished H type 1'-6" long door handle)	Sft	24.50		
	b) Fixed portion	Sft	40.00		
3.0	Wicket gate (up to 1.5M. ht) Specification same as B1 , but fully solid	Sft.	12.00		
4.0	Door closer Providing and fixing Godrej / Doorset / Dorma make over head door closers in door with necessary fixtures and fittings etc.	Nos	5.00		
5.0	Floor spring Providing and fixing Godrej/ Hardween/ Dorma make heavy duty floor spring in entrance door with necessary fixtures and fittings etc.	Nos	1.00		

SL.No.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
6.0	Night latch lock Providing and fixing Knightlatch lock of Godrej make to cash counter door with necessary fixture and fittings etc as per direction of architect.	Nos	1.00		
C	FURNITURE WORK.				
1.0	Officer's table Providing executive type front officer table top of size 4'-6"x2'-9"x2'-6", a front drawer unit consisting 3 Nos of drawer units slides on telescopic slider made up of 19mm th.ply (conforming IS 710) with locking arrangement. It also include readymade keyboard of engineering plastic (KD 575 PMT/INNOFIT SYSTEMS OR Equivalent of).The keyboard is a pullout type, fixed to channels and screwed to below table top . The CPU stand is made up with 19 mm ply with laminate finish as per design.The exposed edge surfaces are to be finished with 1.0mm th.laminates as per design of approved shadea and the inner surface is finished with 0.7 mm th inner laminate.The side credenza will have two drawer unit slides on telescopic slider and two cupboard unit. It also include 8mm clear glass table top with edge polished .The work should be completed including all labour and material.	Nos	5.00		
	Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in dupli'cate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers etc. of approved qualityThe work should be mpleted including all labour and material. It also include 8mm th clear table top glass with all edge mechince polished. The 3" front facia of the table to be made with 19 mm ply and a glazed glass pics of size1'0"x1'-0" with bank logo colour eached edge polished fixed with 1/2" SS stord vertically on the front side of the counter as per instruction . The work should				

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
2.0	Cash Counter				
	Providing and fixing of counter table of size 5'-6"x2'-9"x2'-6" with 25mm th. ply table top (conforming IS 710) the front facia is raised up to ht of 3'-6" with a horizontal 15" wide counter top and a vertical member to separate the D-tel unit (supplied by the bank) as per drawing and instruction made up of 19mm th.ply (conforming IS 710) with locking arrangement. It also include readymade keyboard of engineering plastic (KD 575 PMT/INNOFIT SYSTEMS OR Equivalent).The keyboard is a pullout type, fixed to channels and screwed to below table top . The CPU stand is made up with 19 mm ply with laminate finish as per design The exposed edge surfaces are to be finished with 1.0mm th.laminates as per design of approved shade and the inner surface is finished with 0.7 mm th inner laminate	Nos	1.00		
	Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in dupli'cate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers etc. of approved qualityThe work should be mpleted including all labour and material. The 3" front facia of the table to be made with 19 mm ply and a glazed glass pics of size1'0"x1'-0" with bank logo colour eachd edge polished fixed with 1/2" SS stord vertically on the front side of the counter as per instruction . The work should be completed including all labour and material				

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
3.0	<p>Manager's table</p> <p>Providing executive type manager table top of size 6'-0"x2'9"x2'-6", a side credenza of size 3'-6"x1'-6"x2'-6" and a front drawer unit consisting 3 Nos of drawer units,slides on telescopic slider made up of 19mm th.ply (conforming IS 710) with locking arrangement. It also include readymade keyboard of engineering plastic (KD 575 PMT/INNOFITT SYSTEMS OR Equivalent of).The keyboard is a pullout type, fixed to channels and screwed to below table top . The CPU stand is made up with 19 mm ply with laminate finish as per design. The exposed edge surfaces are to be finished with 1.0mm th.laminates as per design of approved shade and the inner surface is finished with 0.7 mm th inner laminate.The side credenza will have two drawer unit slides on telescopic slider and two cupboard unit. Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in dupli'cate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers etc. of approved qualityThe work should be mpleted including all labour and material.It also include 8mm glass top on table with edge polished. All the work should be done as per drawing and</p>	Nos	1.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
4.0	Running table Providing and fixing in positioin Running /utility table of size 2' wide as per drawing by using 25 mm thick ply wood for top and 18 mm thick plywood for all other horizontal and vertical members .Footrest made with T.W. member of size 4"x1 ½" finished with French polish shall be provided. External surface shall be finished with 1mm thick laminates as shown in the drawing and all other sides shall be finished with 0.7 mm th inner laminate.	Rft.	12.00		
5.0	Storage Cabinete. Providing and fixing of low/ full height storage cabinete having 450mm. depth of made out of 19mm th. block board having one horizontal intermediate shalves. The storage unit should have locking arrangement with front shutter .The exposed surface is to finished with 1.0mm th.laminates as per design of approved shade and the inner surface is finished with 0.7 mm th inner laminate. The work also include intermediate shaves with laminate finished as per design .The work should be completed according to drawing and design including all labour and materials	Sft	80.00		
6.0	Daftri Table Providing and fixing in positioin daftri table of size 5'-0" x 2'-0" x 2'-6" as per drawing by using 25 mm thick ply wood for top and 18 mm thick plywood for all other horizontal and vertical members .Footrest made with T.W. member of size 4"x1 ½" finished with French polish shall be provided. External surface shall be finished with 1mm thick laminates as shown in the drawing and all other sides shall be finished with 0.7 mm th inner laminate.	Nos	1.00		
D	OTHER WORK				
1.0	Panelling Providing and fixing panelling on wall /column/partition . Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 25 mm @ 600mm c/c Both ways horizontally and vertically on the wall.This framing would be covered by 9mm thk. BWP Ply finished in approved 1.0 mm. Thk. Laminate . It also include Wooden moulding, lipping with melamine polished as per design. as directed by Bank / architect shall be provided wherever required. as per Architect's drawing/ direction. The cost includes all the materials, labour, trasportation taxes etc., complete for the	Sft.	100.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
2.0	<p>Suggestion box & Cheque drop box</p> <p>Supplying and erecting free-standing suggestions box of overall size , 450 mm long x 300 mm deep x450 mm high made of 19 mm thick BWP block board, all as in drawing, complete. with hardware. fittings and fixtures of approved make and quality.Top and all exposed surfaces of block board are to be finished with 1mm thick laminate sheet of approved shade and quality. (the suggestion box to be finished with red colour mica) Inner faces of block board surfaces are to be finished with 0.7 mm th inner laminate of approved shads and quality . The shutter should have a glzed portion of size 6"x6" with 8mm. th. clear glass. The work should be done as per design including all labour , material hardware etc</p>	Nos	2.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
3.0	Writing platform for customers & application form set Providing , fitting , fixing writing plat form at a height of 4' above floor level fixed to the wall made out of 19 mm BWP block board with lamination 1 mm tk on top & hard wood beading ducco painted . At least 10 nos vertical slip in chalan shelves attached to wall over writing platform made out of min 4 mm tk acrylic sheets with 6 mm tk ply back up. Each chalan shelf will be of size 6'' height , 6'' wide .The entire unit will be complete in all respect including materials ,labor etc to the satisfaction of consultant .	Rft	3.00		
4.0	Notice Board Providing soft board covered with approved fabric with wooden frame work and decorative beading for display drawings and documents,with locking arrangementof the sliding shutter made up of 8mm th. flot glass. The work should be done including all labour and material.	Sft	12.00		
5.0	False ceiling (Gypsum board.) False Ceiling (Gypsum Board)Providing & fixing in position false ceiling in Gypboard 12 mm thick for horizontals & Verticals fixed over G.I. frame work as specified by India Gupsm Co. Ltd. including trap doors for A.C. Unit in 18 mm thick M. R. Grade Plywood with Stainless Steel hinges & locks with moulding 1'' x 1'' for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects.(Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.)	Sft.	650.00		
6.0	False ceiling (Armstrong) Providing & fixing in position false ceiling in Armstrong 600 x 600 mm x 15/16 mm Dune Supreme RH 99 Prima tile with Tegular edge framework as specified by Armstrong Co. with suspenders wherever required. Making necessary framework for A. C. ducting, if any, and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level, including making grooves and trap doors for A. C. unit in 18 mm thick M. R. Grade Plywood with Stainless Steel hinges & locks with moulding 1'' x 1'' for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects.(Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.)	Sft	344.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
7.0	Façade of front entrance door.				
	Providing and fixing in position Aluminium composite panel boxing with PVDF coating & LDPE core laminated Eurobond / Altobond/ Alukbond Exterior Grade 4 mm thick with composite of (0.5 mm – 3 mm – 0.5 mm) including fabrication for the same with aluminium sections, required hardware, silicon sealant (Dow corning 789) masking tape, necessary scaffolding etc. as detailed in drawing complete in all respects.	Sft	90.00		
8.0	Electrical panel board cover				
	Providing and fixing of electrical panel board cover made up of 19mm ply with two shutter at the front having T.W livers as per drawing and design, it allso have furnished with locking arrangement. The exposed surface is finished with 1mm. Th. Laminates and inner surface is finished with two cote of plastic emulsion paint over one coate of primer . The work should be completed including all hardware, material and labour.	Sft	28.00		
9.0	Vertical blinds				
	Supplying, fitting & fixing in position coloured 0.33mm thickness acrylic coated cleanable/ washable vertical blinds (Marvel or its equivalent, as approved) inclusive of all recommended accessories colour pattern etc., as per Architect's approval. The cost includes all the materials, labour, trasportation taxes etc., complete for the work.	Sft	25.00		
TOTAL				Rs:-	

Total Amount In Words:-