

Schedule of Quantities for laying of **cement concrete interlocking paver block** in the Bank's premises at 55 The Mall Meerut cantt

| Sl. | Description of Item | Unit | Qty. | Rate* | Amount |
|-------|--|------|------|-------|--------|
| No. | | | | (Rs.) | (Rs.) |
| 1 | Providing and laying 60mm thick faciory made cement concrete interlocking paver block | sqm | 3000 | | |
| | of M -30 grade made by block making machine with strong vibratory compaction, of | | | | |
| | approved size, design & shape, laid in required colour and pattern over and including | | | | |
| | 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all | | | | |
| | complete as per the direction of Engineer-in-charge. | | | | |
| 2 | Brick edging laid lengthwise with half brick depth including excavation, refilling and | m | 600 | | |
| | disposal of surplus earth lead upto 50 metres: With common burnt clay F.P.S. (non | | | | |
| | modular) bricks of class designation 7.5 | | | | |
| 3 | Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand | sqm | 200 | | |
| | (zone-III) derived from natural sources: 6 graded stone aggregate 20 mm nominal size | | | | |
| | derived from natural sources) over 75mm thick bed of dry brick ballast 40 mm nominal | | | | |
| | size, well rammed and consolidated and grouted with fine sand, including necessary | | | | |
| | excavation, levelling & dressing & finishing the top smooth | | | | |
| TOTAL | | | | | |

Signature of Contactor with seal