

Schedule of Quantities for laying of cement concrete interlocking paver block in the Bank's premises
at 55 The Mall Meerut cantt

Sl. No.	Description of Item	Unit	Qty.	Rate* (Rs.)	Amount (Rs.)
1	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	sqm	3000		
2	Providing and laying cement concrete 1:2:4 (cement:coarse sand:graded stone aggregate 20mm or below for filling the external border.	Cum	7		
2	Brick edging laid lengthwise with half brick depth including excavation, refilling and disposal of surplus earth lead upto 50 metres : With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	m	600		
3	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth	sqm	200		
TOTAL					
Add GST					
Grand total					