



INDIAN BANK

RFQ FOR INTERIOR FURNISHING AND MODULAR TABLES / CABINETS WORK FOR THE PROPOSED SPACE FOR DIGITALIZATION DEPARTMENT, AT SEVENTH FLOOR, NO:66, RAJAJI SALAI, CHENNAI 600001.

Ref:No: CO:EST:HO:TEN:SKR:006:2022-23
Date : 09.12.2022
Bid : Price Bid

Issued to:

.....
.....
.....

This Tender document contains 4 pages

Signature & Seal of the Bidder

Price Bid

Schedule of Quantities					
“Interior furnishing and modular tables / cabinets work for the proposed space for digitalization department, at seventh floor, no:66, Rajaji Salai, Chennai 600001”.					
S.No		Qty	Rate	Unit	Amount
1	FURNISHING WORK				
	Linear Workstation - Sharing Size: 1350x600x750/1200ht				
	<p>Linear Running Counter - Sharing Size: 1200x600x750ht. Supplying and installation of Linear Working Table of Size 1350mm x 600mm x 750 mm, 25 mm thick pre laminated particle board table top with under structure, Race way, Soft closing access flap etc. Privacy Divider (by Glass & Magnetic Fabric Board) Metal Key board, CPU trolley as per specifications below: Under Structure: Under structure made of straight leg which should be fabricated with cross connector by CO2 welding MS ERW Box of size 50.8mm x 50.8mm x 1.5 mm thk with the base of MS tube fitted with Glide Plate Over 50mm X50mm PU leveller. The leg shall be supported by the cross connector which shall be MS ERW RHS 40mm X 30mm (RHS) X 1.5 mm thick members at upper level. The rate inclusive of 300mm X 1.2 mm thick CRCA sheet as a perforated stiffener (Laser cutting as per design) by suitable welding wire management suitable MS race way shall be provided for vertical & horizontal wire management in the middle of the under structure including race ways shall be finished within min 50 micro thickness of epoxy polyester powder coating. Table Top: The table top shall be 25mm thick twin side Pre Laminated particle board confirming to IS:3087 laminated with laminate of thickness 0.8mm confirming to IS: 2046 and glued with PVAC. 2mm PVC lipping to be done which is glued with Hot rent EVA glue and to be fitted under structure by MS supporter, the rate including providing soft closing access flap having 450/500 x120 mm in the table. The rate including accessories: Metal CPU trolley (Safe load 20Kgs). Key board tray should have 1.2mm thick CRCA sheet with slides Tray size should be 540mm 197 mm fixed on the table top (bottom side). Privacy Divider: Front side partition for the entire length of linear table, the panel partition shall be 15/30 mm thick powder coated suitable aluminium extrusion vertical trim and horizontal trim. The panel shall be 2nos x 3mm thick painted glass and fabric magnetic tiles, fabric upholstered metal tiles in 0.6mm thick G.I grade ‘O’ as per IS:277. The fabrics should be upholstered with adhesives back to back, or Equivalent approved. (Deviation: privacy Divider - 675mm length x 450mm height White board with magnetic board quoted). The suitable fixing arrangement to be made for firm fixation on the under structure. The rate including of installing (Size 450mm x 600mm) 10mm thk toughened intermediate</p>	28		Nos.	

	<p>glass divider (corners bevelled) with necessary fittings and hardware as per approved design above table top. The cost of include the supporting system to privacy divider and under structure such as brackets / fasteners / joining posts / race ways 2 nos / wire management cleats / runners etc. (Basis Cost of Fabric Rs. 300 / per running meter.)</p>				
2	Mobile Pedestal: 400 (W) x 450 (D) x 650 (H) mm				
	<p>Providing and installing drawer boxes (Box File)of size 650 mm ht., 400mm width and 450 mm deep made out of 18mm thk pre laminated particle board Grade II & Type-II (IS12823: 1990; Reaffirmed 2005) finished with 0.8mm thk laminate twin side, front and sides made of 18 mm thk pre laminated particle board Grade II & Type-II (IS 12823: 1990; Reaffirmed 2005) finished in 0.8mm thk laminate and back, drawer bottom to shall be metal box ,2 nos. minimum 120mm high drawer & 1 minimum 275mm high filing drawer. Handles to be provided. Central locking to be given for each pedestal Soft closing and Anti slam mechanism for pedestal. M8 Leveling stud for free standing pedestal. The anti-tipping mechanism should have fitted in the roller arrangement mounted below file drawer to avoid toppling of unit when file drawer is pulled out.</p>	30		Nos	
3	BACK STORAGE - As per site needed L (approx. 900 mm each) X 450DX 750/1200HT				
	<p>Providing & Installing Back Storage as per site need having size L (approx. 900 mm each) X 450DX 750/1200HT - Free standing side credenza of above mentioned size with openable shutters in 19mm thk pre laminated mdf board , 19mm thk prelam mdf board for verticals & bottom, back of 9mm thk prelam particle board, with back to be inserted in the groves provided in the verticals top and bottom, with pvc edge banding on all exposed edges, 25mm thk top edge banded on facing edge and other three sides edge banded, adjustable shelves at app 16" c/c. with 19 mm. with pre laminated particle board & all necessary fittings like 4" long ss brushed finish handles, tower bolts, self-closing hafele make hinges, godrej make/hafele make locks & any miscellaneous items. the bottom facing skirting to be in same laminate finished as per scope drawings</p>	200		Sqft.	
4	VERTICAL BLINDS Deep cleaning of existing vertical blinds, rate shall include removal of blinds, re-fixing the same after deep cleaning, replacing damaged beaded chains, track, beading etc, labour and to-and-fro transportation etc., at site for proper completion of job.	600		Sqft.	
5	Half Height partition (5'0" height) - Partition shall be made with Anodized Aluminum frame work, heavy sections (2mm thickness) of 2"x2" section, spacing of 2'0"x2'0" c/c. 8mm thick calcium silicate to be fixed on the both sides and finished with two coat of enamel paint of approved shade and colour. where ever required 12mm thick plain glass to be fixed with teak wood beading and duco paint / polish of	160		Sqft	

	approved shade and colour. Clear glass to be finished with frosting design of approved pattern and design. Rate to include providing cutouts and provisions to run electrical conduits, switches, etc. Cost include removal of the existing partitions, wastages, transports, loading, unloading charges, labours, materials, tools, lead, lift and etc. Complete as per instructions of the Bank.				
6	Internal Wall painting: Scraping and cleaning the existing surface and Providing and applying two coats of approved Plastic Emulsion paint finish with necessary primer putty and primer to all internal wall surfaces including scraping the walls, scaffolding etc. complete as per manufacturers specification and as instructed by Bank.	1000		Sqft.	
7	Providing and applying two coats of approved colour enamel paint finish over Grill, Ply finish, Door with necessary primer putty including rubbing with sand paper, scaffolding, etc. complete as per manufacturers specification and as directed and instructed by Bank.	1300		Sqft.	
8	Dismantling of existing wooden raised platform and etc from site, stacking of serviceable materials as directed by Bank at site and carting away the debris from site to contractors dumping yard. Cost include transports, loading, unloading charges, labours, materials, tools, lead, lift and etc.	120		Sqft.	
Total amount (excluding GST)					
GST @ %					
Gross Total					

Total Amount in words: Rupees only

Place:
Date:

Signature & Seal of the Bidder