

**Shed on Terrace of CBS Project Office on Plot No. 9 & 10, Sector 19A, Vashi, Navi Mumbai
for Indian Bank**

S.N.	Description	Quantity		Rate	Amount
G. S. SHEET ROOF					
1	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), including the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.80 mm thick with zinc coating not less than 275 gm/m ² etc. complete as directed by Architect/ Bank.	6000	Sq.ft.		
GRAND TOTAL					
Add SGST					
ADD CGST					
TOTAL AMOUNT					
<p>Note: 1. The contractor shall quote rate of whole item in BOQ considering the provided basic rate of material by bank. However, if bank approves the basic rate of material below the provided rate in the respective item, than the difference of amount for that item will be deducted accordingly or rate will be reduced accordingly.</p> <p>2.All the pages shall be signed and stamped by the contractor.</p> <p>3.Price Bid shall be filled only in type form. The price bid which are handwritten will be summarily rejected.</p>					
<p>NOTE : The above quantities are approximately taken for estimation purpose they may increase or decrease. Contractor will be paid for actual work executes against each item. Brief specifications are given for each item. Minor verification in design and specification for each item are likely for which no extra payment will be given. Any of these items may be cancelled.</p>					
<p>NOTE :- Cost inclusive of all taxes other than GST. The Contractor estimate shall also include MMC / Local Authorities Permission for smooth functioning the work.</p>					