

**BILLS OF QUANTITIES FOR FURNISHING WORK OF INDIAN BANK FOR MAIN BRANCH, AHMEDABAD**

Sr. No.	Description	Quantity	Rate	Unit	Amount
---------	-------------	----------	------	------	--------

**[A] FURNISHING WORK**

1 CASH COUNTER 0 RFT  
 Supplying, fixing and keeping in position single window counter complete as per design, and drawing made out of 18mm thick commercial plywood of approved make, complete with 3/4" th. C.P. Teak wood lipping on all edges wherever required.

The cost shall be inclusive of S & F of a drawer and shelf unit with 18mm thick commercial plywood and with Godrej/ equivalent lock in drawer and shelf unit. The cost shall also be inclusive of the following.

[a] size :

Description:	L	B	Ht.
Writing Top	5'-0"	2'-9"	2'-6"
Transaction Top	5'-0"	1'-0"	3'-9"

**3 Drawers with**

region hole	2'-0"	1'-3"	2'-0"
-------------	-------	-------	-------

Computer key Board

Supplying and fixing metal key Board of Ebco Earl Bihari or equivalent make in counter as per design and instructions.

Providing 18 mm thick plywood with T.W beading self for CPU stand below counter

[b] Working top shall be finished with laminated sheet 1.0 mm thick of approved make, natural Teak wood Texture/ choice shade laid with grains parallel to the length of the counter.

[c] **Transaction top and vertical (above writing top) shall be made from 12 mm thick glass with frosted and polished edges shall be fixed with necessary S.S brush finish brackets supports on wooden partition as directed. All edges of glass shall be diamond cut polished edges. as per drawing**

[d] Front pannel and front projection shall be finished with laminated sheet 1.0 mm thick of choice shade approved by Architects/Bank and fixed on 18mm thick commercial plywood with horizontal and vertical grooves as per design.

[e] Skirting : 6" high Laminated sheet 1.0mm thick for skirting shall be glued on to pannel of [in front and rear] 18 mm thick commercial plywood of approved make ht.

[f] The projecting portion shall have 9" deep with vertical supports as required made of 18mm thick commercial plywood of approved make.

[g] Foot rest of 3" x 1.5" in C.P. Teak wood.

[h] All wood work shall be wax/spirit polished over a coat of linseed oil to a smooth and uniform finish of choice colour and shade.

Sr. No.	Description	Quantity	Rate	Unit	Amount
[i]	All fittings like brass knobs/ S.S Godrej multipurpose locks to each drawer and cabinet doors, piano hinges, ball catcher stopper etc.				
1[A]	<p>SINGLE WINDOW COUNTER</p> <p>- Do - as in item No. 1 but with transaction top.</p> <p>Description:      L            B            Ht.</p> <p>Writing Top      5'-0"      2'-6"      2'-6"</p> <p>Transaction Top 5'-0"      0'-9"      3'-0"</p> <p><b>3 Drawers with</b></p> <p>pegion hole      2'-0"      1'-3"      2'-0"</p> <p>Computer key Board</p> <p>Supplying and fixing metal key Board of Ebco Earl Bihari or equivalent make in counter as per design and instructions.</p>	0		RFT	
1[B]	<p>LOW HEIGHT COUNTER FOR OFFICER</p> <p>- Do - as in item No. 1 but with transaction top.</p> <p>Description:      L            B            Ht.</p> <p>Writing Top      5'-0"      2'-6"      2'-6"</p> <p>Transaction Top 5'-0"      2'-6"      2'-6"</p> <p><b>2 Drawer &amp; 1 shutter storage cabinete</b> (As per design and instructions)</p> <p>Computer key Board</p> <p>Supplying and fixing metal key Board of Ebco Earl Bihari or equivalent make in counter as per design and instructions.</p>	0		RFT	
1.1	<p><b>Removing, refixing and realignment of existng Furnitures</b></p> <p>Removing, Refixing and re-alignment of Tables, Side Tables, cup board, Misc. other furnitures to be used from existing premises including polishing and minor repairs.</p> <p>Shifting and re-laying table, side table, cup board as per new lay out. Rate also includes removal of electric/ data/telephone connection as per site requirements.</p> <p>Necessary cutting, modification and repairing if required.</p> <p>Repaing of drawers and shutter and painting /polishing complete as directed.</p> <p>Rate includes transportation cost from existing premises to new premises.</p>				
1[A]	CASH CABIN COUNTER 5'-0" Length with front side glass Partition	1		NO	
1[B]	OFFICER COUNTER 5'-0" Length	6		NO	
1[C]	BM TABLE Approx. Size 5'-9" x 2'-9"	1		NO	
1[D]	OFFICER TABLE Approx Size 4'-6" /4'-0"x 2'-6"	2		NO	
1[E]	OFFICER TABLE Approx Size 5'-0" x 2'-6" Rate including necessary Modification Drawer unitr change from Right side to Left side	2		NO	

Sr. No.	Description	Quantity	Rate	Unit	Amount
1[F]	OFFICER TABLE Approx Size 4'-0" x 2'-6"	1		NO	
1[G]	SIDE TABLE With Drawers	4		NO	
1[H]	SIDE TABLE Without Drawers	4		NO	
1[I]	Removing and refixing of existing storage cup board with necessary cutting and modification including painting/ polishing etc complete	27		SFT	
1[J]	Refixing of existing storage cup board Shutter with necessary cutting and modification & painting/ polishing etc complete	125		SFT	
1[K]	Refixing of Existing flush door shutter at New location Including necessary repairing/alternation if required complete as directed.	42		SFT	
1[L]	Refixing of Existing Cash cabin & SW Partition with flush door shutter at New location Including necessary repairing/alternation if required complete as directed.	25		SFT	
1[M]	Providing and fixing 1.0 mm thick laminate on any existing laminate surfaces of Tables, Side Tables, , cupboards, panelling by removing existing laminate by Hot Iron. Rate includes applying lacquer polishing on all existing exposed wooden members. Only laminate finished surface area shall be measured for payment	425		SFT	
2	Providing & fixing Full height <b>partition with door shutter</b> For Manager and other area Providing and fixing both sides laminated full height partition <b>using 50mmx25mm x1.20 mm thick Aluminium members</b> in a grid of 2'-0" x 2'-0" fixing 6mm th commercial plywood and 1.0mm laminate on both sides of Aluminium skeleton, providing 5.0/8.0 mm th float glass as directed in the partition. Providing door shutter using 5" x 1 1/2" th steam beach member for Styles and rails and fixing 8mm th glass in between as per design 4" Long 3 Nos stainless steel hinges shall be provided 8.0 mm th glass shall be provided in door shutter as directed. Godrej Mortice lock shall be provided in door shutter steam beach Beading glass. All visible members if not laminated shall have melamine polished as directed. <b>Note :Rate shall be same for solid partition</b>	110		SFT	

Sr. No.	Description	Quantity	Rate	Unit	Amount
2[a]	<b>Providing and Fixing Partition For Server Room/UPS Room with door shutter</b> Same as above item no 2 but Providing both side 8 mm thick Hilux board over aluminium framing with 1.0mm thick laminate & other side plastic paint of approved make & specifications etc complete as directed.	90		SFT	
3	Providing and fixing low height partition For Cash /S.W Cabin and other partition Providing and Fixing low height partition using <b>50mmx25mmx1.20mm thick Aluminium member</b> in grid of 2'-0" x 2'-0" fixing 6 mm thick commercial plywood of approved brand on both side of Aluminium skeleton fixing 1.0 mm thick laminate of approved shed on both sides and. Fixing steam beach member of 2 1/2" x 3/4" T.W. members in a shape as directed shall be fixed on all exposed edges. Fixing 12 mm th free glass as directed steam beach beading glass.Applying melamine polish on exposed steam beach members as directed complete., Providing 12mm th glass with polish edges shall be provided as directed. including door shutter as per design and instruction	15		SFT	
3[a]	Providing and fixing Isolated flush door shutter Using 4" x 2" Steam beach members and 30mm th flush shutter with 5mm th glass as per design and instruction. Providing Steam beach member on periphery for fixing 4" long hinges 3 Nos. Fixing 1.0mm th laminate on both sides. Providing S.S Handles, Godrej Mortice Lock, stoppers, doorstop & polishing to exposed edges directed complete.	42		SFT	
3[b]	Providing and fixing Wicket Gate door in Cash cabin Same as item no 3[a] but P/F 30 / 32 mm thick flush shutter with both side laminate including SS hinges with countersunk SS screws, Approved make Night latch Lock, S.S Handles,Door stoppers, doorstop etc complete as directed.	12		SFT	
4	Providing and laying pannelling on walls & pillars at main entrance door and 18mm thick plywood box for entrance door and AC pipe covering Providing and laying pannelling on pillars and walls having 6mm th commercial plywood and 1.0mm th laminate fixed on wall & pillars <b>with Aluminium. framing of 25mm x25mmx1.20 mm thick at 2'-0" c/c</b> bothways or 18mm thick commercial plywood with laminate paneling on wall & pillar etc. complete as directed. Creating Box for above glass door/ glass partition 12/18 mm thick commercial plywood with 1.0 mm thick laminate shall be used with framing of Aluminium as requirement etc complete as directed.	150		SFT	

Sr. No.	Description	Quantity	Rate	Unit	Amount
5	<p>Providing and fixing Glass partition on Cash counter/ SW Counter / Low Height counter front side top as follows.</p> <p>12mm th glass shall be fixed with necessary S.S Brush finish brackets support on wooden partition as directed. Making necessary cut outs in glass, all edges of the glass touching to the adjoining componants shall be diamond polished,the top open edge shall have pencil round moulding as directed complete.</p>	10		SFT	
6	<p>Suppling and providing BM Table as per the following description Size 6'-0" x 2'-9". Table top shall be made for 18mm thick commercial ply wood with 1.0mm th laminate with necessary intermediates support. Table top shall be supported by 18mm thick commercial ply wood with wooden framing 1.0mm thick laminate. Storage cabinate of 1'-3" x 1'-6" x 2'-0" shall be provided using 18mm thick commercial ply wood having <b>2 Nos drawers and one shutter</b> as directed with slidding channel of Ebco makele ,Godrej lock / S.S. Handle. Computer Key board of metal of ebco Earl Bihari make shall be provided. Exposed surfaces of the cabinate shall have 1.0mm th lamiante. Foot rest of 1 1/2" x 3" T.W members shall be provided. All the surface without lamination shall be polished. Apron made from lamiantion shall be provided in a pattern as directed. Table shall have stand for keeping CPU and cable Manager shall be provided in table top.</p>	0		NO	
6[a]	<p>'-DO- as above but S/P Officer Table Approx Size 5'-0" x 2'-6". With 2 Nos Drawer+ 1 Shutter unit for Officer</p>	0		NO	
6[b]	<p>-DO- as above but S/P Officer Table Approx size <b>4'-6" x 2'-6" without Drawer storage unit in table</b></p>	0		NO	
7	<p>Supplying and providing side cabinate for keeping computer and printer size 3'-3" Length 1'-4" Width and 2'-6" height. <b>Having openable shutters</b> as directed. Cabinate shall be made from 18mm thick commercial ply wood with 1.0mm thick laminate back shall be made from 6mm th commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with 1.0mm th laminate and "Godrej" lock. Drawer shall slid on slidding channel, all the surfaces of the cabinate without laminate shall have polish/paint as directed. Rate includes all necessary provisions for installing computers. for AGM</p>	0		NO	
7[a]	<p>- Do - as in above but size shall be <b>3'-0"x 1'-4"x 2'-6" ht With Openable Shutter unit</b></p>	0		NO	

Sr. No.	Description	Quantity	Rate	Unit	Amount
7[b]	- Do - as in above but size shall be <b>3'-0"x 1'-4"x 2'-6" ht With Partly Drawer and Openable Shutter unit for Officer Table</b>	0		NO	
8	Supplying and providing side storage cabinet as per following description.[ <b>Low Height and Full Size</b> : Depth 1'-4" ht. 2'-6" /4'-0"/7'-0"having openable shutter as directed. Cabinet shall be made from 18mm thick commercial plywood for vertical, shelves, shutters and 6mm commercial plywood for backing with 1.0 mm thick laminate on all exposed surface and polishing/painting for internal surface with vertical (at 3'-0" c/c) shelves at 1'-3" c/c shutters openable in 18mm thick commercial plywood with all S.S hinges, towers bolts, powder coated handle, ball catches, S.S godrej multi purpose lock complete. Edges to be finished with teak wood lipping etc. including all incidental etc. complete. [Filling storage Cup Board]	0		SFT	
8[a]	Providing and fixing Electric cup board using 18mm thick commercial ply wood with 1.0 mm thick laminate on outer side polishing/painting on internal surface with Godrej lock handle, ball catches and providing and fixing SS jali in shutter etc. complete as directed depth of cup board 1'-4". <b>Height of shutter will be maximum 7'-0". Only Front elevation shall be measured for payment purpose. Rate also including using of existing shutter</b>	0		SFT	
9	<b>Reinstallation of existing soft board for pin up using 6mm thick commercial plywood on back side and 12mm th soft board on front. Fixing cloth of selected design of Basic rate of Rs. 150 per mt. T.W member shall have polish as directed complete.</b>	8		SFT	
10	Reinstallation of Existing CUSTOMER WRITING DESK 'Size 2'-0" x 1'-0" x 6" ht. Sides and bottom shall be made from 18mm thick commercial ply wood with 1.0mm thick laminate at inner & outer surface. Top shall be made from 12mm th glass with bevelled and polished edges making diff divisions by 8mm th glass for slips or forms as directed complete.	1		NO	
10[a]	Reinstallation of Existing of letter box cum suggestion box of size 1' 3"x1'-0" x 3'-6" ht. Box shall be made from 18mm thick commercial plywood with 1.0mm th laminate, back shall be 6mm th commercial plywood shutter shall be made from 18mm thick commercial plywood with 1.0mm th laminate and Godrej lock, The top shall have a slit for dropping letter, all the surface of the box without laminate shall have polish as directed.	1		NO	

Sr. No.	Description	Quantity	Rate	Unit	Amount
11	Providing and fixing "EG/Godrej" or equivalent make door closure.	2		NO	
12	<b>Supplying and fixing Roller Blind of Approved made like Neon/ Trans or Equivalent make with selected fabric of approved design and shed.</b>	0		SFT	
13	Supply office stool 1'-0" x1'-0" 1'-4" ht to be made of Teak Wood frame 2" x 2" with Square Tapered legs to be Provided with 19 mm thick Commercial Ply wood with laminated top. Including polish/paint complete as directed.	0		NO	
	ALUMINIUM WORK				
14	MAIN ENTRANCE DOOR Providing & Fixing fully glazed main door at the main entrance The Item includes fixing of <b>12 mm th. Toughned glass</b> with the help of <b>top patch &amp; bottom patch fittings</b> . The door will have patch lock, pti pivot, floor spring & 600 mm long handles , fixed with the glass by making necessary cutouts & holes. The glass edges shall be polish on all sides. The entire door shall be erected in complete line & level. The door will have S.S brush finish Signage for pull & push.The entire door, complete in all respect should be installed in positions as req.				
[a]	OPENABLE PORTION Glass Door with Patch Fitting	0		SFT	
[b]	Fixed Portion partition With Patch Fitting	0		SFT	
[c]	Providing and fixing 12mm thick Glass Partition on front side Building	0		SFT	
[d]	Refixing of Existing Aluninum door shutter Including necessary repairing/alternation if required complete as directed.	25		SFT	
[e]	Refixing of Existing Aluninum with glass partition Including necessary repairing/alternation if required complete as directed.	25		SFT	
15	<b>ALUMINUM COMPOSITE PANEL FOR FRONT SIDE ELEVATION</b>	280		SFT	

Sr. No.	Description	Quantity	Rate	Unit	Amount
	Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond with 0.25 mm foil with 2" x 1" x 1.60 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building This item will be carried out as per manufacturer specifications.				
16	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section <b>(Gypframe)</b> supporting system in lline and level. Finishing the surface and applying 3 coats of flat paint as directed complete entire work to be done asper standard specifications of Indian Gypsum.	310		SFT	
	<b>Note : (1) Rate includes making necessary cutouts for lighting fixtures (2) Pattas of Less than 1'-0" shall be measured in Sqft and not in Rft and paid in Sqft. (3) Only finished surface area shall be measured for payment.</b>				
17	<b>Providing and fixing of Armstrong Mineral Fibre Acoustical Suspended Ceiling System with 16 mm thick FINE FISSURED (MICRO LOOK) EDGE TILES WITH ARMSTRONG SELECT (Black Reveal) 15 mm EXPOSED GRID.</b> Using Select Grid with Fine Fissured microlook. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for lighting fixture and Diffusers will not be deducted from area for payment purpose. Rate includes transportation cost from existing premises to new premises.	650		SFT	
<b>TOTAL TENDER COST "A"</b>				<b>RS.</b>	<u>                    </u> <u>                    </u>

**+ GST AS PER APPLICABLE**

**(SEAL AND SIGNATURE OF CONTRACTOR)**