

PROJECT: INDIAN BANK AT SECTOR-06 DWARKA BRANCH.

SUB:- AC WORK

ARCHITECT :- BURMAN ET.AL.

S.NO	ITEMS	UNIT	QTY	RATE	AMOUNT
1	Supply of Air cooled Hi Wall Split AC type Units Comprising Of: (3 STAR)				
a	3-Star rated Hi-wall split airconditioner of 2.0 TR capacity	Each	0		
b	3-Star rated Hi-wall split airconditioner of 1.5 TR capacity	Each	0		
c	3-Star rated Hi-wall split airconditioner of 1.0 TR capacity	Each	0		
2	Uninstalling existing Split AC from the existing Branch and reinstalling the same in new Branch with proper servicing, Gas Charging and any other relater work to make the Acs fully functional/operational, complete to the satisfaction of the architect.	Each	0		
3	Copper Pipes				
a	Charges for providing additional copper pipes (one circuit) for the above split units with necessary insulation and with adequate pvc insulated copper wire from indoor to outdoor units concealed and taken through beyond the standard 5 mtr length.	Rmt	70		
4	DRAIN PIPING				
a	Charges for providing additional 25mm dia heavy duty PVC drain piping with all necessary fittings duly insulated with 9mm thick nitrile rubber pipe insulation drain pipe concealed / surface mounted and taken through wall / partition beyond the standard 5m length for the above split units.	Rmt	70		
5	STABILIZERS				
a	Supply, installation, testing and commissioning of wall mounting 4KVA stabilizers for 1.5Tr & 1.0Tr Hi-Wall Split Air Conditioning units with input voltage range of 170-270 Volts and output 220 +/- 10% as required.	Each	0		
b	Supply, installation, testing and commissioning of wall mounting 5KVA stabilizers for 2.0Tr Hi-Wall Split / Cassette type Air Conditioning units with input voltage range of 170-270 Volts and output 220 +/- 10% as required.	Each	0		
6	Electrical Cable :-				
a	Providing & fixing of 2.5 Sqmm wiring interconnected electrical indoor & outdoor unit as req. complete as per design & wiring between specification of manufacturer.	Rmt	80		
7	Providing and fixing standard powder coated support brackets & including grille gauge with locking arrangemnet for the above split / cassette units including fasteners and other accessories as required.				
A	For split air conditioner	Each	5		

8	Civil Work For cutting Chisling Plastering of walls to conseal copper pipe, Drain pipe & Electrical wire with plaster finish.	LS	1		
	TOTAL				