



INDIAN BANK

BRANCH: NEW COLONY HARIDWAR,RANIPUR

DATA CABLING WORKS (Branch & ATM)

BILL OF QUANTITIES (BOQ) AND SPECIFICATIONS

S.NO.	ITEM DESCRIPTION	QTY	UNIT	RATE	AMOUNT (Rs.)
A:-	DATA CABLING WORKS:				
1.0	Providing & Laying UTP Cat6 cable from server panel to each destinations. The cable make shall be of D-LINK. The item is incl. of all material, labours, tools & palnts etc.	350.00	RMT		
2.0	Providing & Fixing in positions 16 port/10/100mbps Swtch. The item make shall be of " Dlink ".	1.00	Nos.		
3.0	Providing & Fixing in position 24 port jack panel . The item make shall be " Dlink ".	1.00	Nos.		
4.0	Providing & Fixing in positions 19" Rack -9u with glass door . The item is incl. complete with locking arrangement etc.	1.00	Nos.		
5.0	Providing & Fixing in positions information outlet dual plate with face plate and back box with complete arrangements etc.	20.00	Nos.		
6.0	Providing & Fixing in positions the Mounting Port 7' . The item make shall be of Dlink .	10.00	Nos.		
7.0	Providing & Fixing in positions the Mounting Port 3' . The item make shall be of Dlink .	10.00	Nos.		
8.0	Providing & Laying in positions 25mm dia PVC Conduit for UTP cables.	150.00	RMT		
	TOTAL FOR UPS & DATA CABLING			Rs.	

S.NO.	ITEM DESCRIPTION	QTY	UNIT	RATE	AMOUNT (Rs.)
ABSTRACT COST SUMMARY					
	TOTAL FOR DATA CABLING WORKS:			Rs.	
	TOTAL BEFORE GST			Rs.	
	ADD: GST 18%			Rs.	
	TOTAL AFTER GST			Rs.	
	SAY			Rs.	
Amount in words: Rupees					
<p style="text-align: center;">contractor's Under taking: 1- I/my representaive have inspected the said Branch premissess personally. 2- I have read and understand all the specifications and terms & conditions properly.</p>					
	Contractor's Sign and Stamp			APPROVED BY ZO: INDIAN BANK, DEHRADUN	