THARANGAMPADI BRANCH & ATM - INTERIOR, FURNISHING, ELECTRICAL, DATA CABLING AND AIR CONDITIONING WORKS FOR INDIAN BANK (NAGAPATTINAM ZONE)

А	MAIN WORKS	Amount(Rs.)
1	INTERIOR WORK	
2	FIXTURES WORK	
3	BRANCH ELECTRICAL WORK	
4	BRANCH & ATM DATA CABLING WORK	
5	BRANCH AIR CONDITIONING WORK	
6	ATM INTERIOR WORK	
7	ATM ELECTRICAL WORK	
7	ATM AIR CONDITIONING WORK	
	TOTAL	

ALL RATES ARE INCLUSIVE OF 18% GST

THARANGAMBADI BRANCH - INTERIOR, FURNISHING WORKS FOR INDIAN BANK (NAGAPATTINAM ZONE) **BILL OF QUANTITIES-INTERIOR** S NO **PARTICULARS UNIT** RATE(Rs) **AMOUNT (Rs)** QTY **PARTITIONS** а **Full & Half Blocked Partition** Providing full height double skin fully blocked 326.00 Sft partitions upto RCC ceiling ht using aluminium plain rectangular sections of 2 1/2"x 1 1/2" size spaced at 2'0" c/c maximum for the frame work, fixed with 6mm plywood on both sides and lined with 1mm tk. laminate (Bank approved colors) with necessary grooves of 1mm thick. The rate shall include the cost of providing 100mm wide skirting with 1mm tk. laminate (Indian Bank Blue) at base and a 100mm wide border (Indian Bank Blue) at the top including making necessary slots for cable conduits to pass through and all incidental materials etc., complete.(Record, dining, strong room, ups room) b Partly Glazed Partition Manager & Server Cabin: Providing full height double skin partly glazed 214.00 Sft partitions using aluminium sections of 2 1/2"x11/2" size spaced at 2'0" c/c maximum for the frame work, fixed with 6mm plywood on both sides and lined with 1mm tk. laminate with necessary grooves of 1mm thick. The rate shall include the cost of providing 100mm wide skirting with 1mm tk. laminate (Indian Bank Blue) at base and a 100mm wide border (Indian Bank Blue) at the top and shall include the cost of providing 8mm tk. plain float glass with etching Designe to suitable sizes, including making necessary slots for cable conduits to pass through and all incidental materials etc., complete. **Low Height Partition** С

	Providing low height double skin partitions along with Counter Divider partition wicket gate of the same type using aluminium sections of 2 1/2" x 1 1/2" size spaced at 2'0" c/c maximum for the frame work, fixed with 6mm plywood on both sides and lined with 1mm tk. laminate (bank approved laminates only) with necessary grooves of	90.00	Sft	
	1mm thick. The rate shall include the cost of providing 100mm wide skirting with 1mm tk. laminate (Indian Bank Blue) at base& including making necessary slots for cable conduits to pass through and all incidental materials etc., complete.			
d	Providing full height upto 7' 3" from floor level, semi grilled plywood partition for cash cabin, using aluminium sections of 2 1/2" x 1 1/2" size spaced at 2'0" c/c maximum for the frame work, fixed with 6mm plywood on both sides and lined with 1mm tk. laminate (bank approved laminates only) with necessary grooves of 1mm thick, The rate shall include the cost of providing 100mm wide skirting with 1mm tk. laminate (Indian Bank Blue) at base and a 100mm wide border (Indian Bank Blue) shade at the top and shall include the cost of providing ornamental aluminium grille to suitable sizes, including making necessary slots for cable conduits to pass through and all incidental materials etc., complete.	91.00	Sft	
е	CASH CABIN TOP ALUMINIUM GRIL			
	Providing and fixing in position readymade anodized alumium grill of approved design and quality fixed with continuous steam beech / teak wood beads of approved shape (finished 35 x 25 mm) all round polished (in cash cabin)	50.00	Sft	
2	FRONT COUNTER 12MM GLASS			
	Providing front glazing for cash cabin above counter from 3'9" to 7'0" height, and inbetween banking counters using 12mm thick plain glass including edge polishing & etching.	55.50	Sft	
3	DOORS			
a)	ENTRANCE DOOR			

				T
	To be made out of 12mm thk glass with etching as	42.00	Sft	1
	per design. The glass with etching has to be fixed			
	with top & sides rails of 2½"x4" and bottom rails of			
	size 2½" x 6". The rails to be made out of beech			
	wood The door shall have 18" long s/s handle (as			
	shown in the drawing) and also double action floor			
	spring of specified make. The door frame to be mde			
	out of 5"x 2½" best quality beech wood. The etching			
	in glass pattern to be done strictly following			
	instructions of the Architect or following the drawing			
	attached. The exposed wood of frames, rails to be			
	polished as per instructions of the architect. NB: The			
	·			
	size of the door may slightly vary as per site			
	conditions for matching the elevation on the fixed			
	glazing. All exposed edges of the glass to be machine			
	polished. The rails are to be made as per the design			
	of the architect. Bank Entrance door (6'0" X 7'0")			
b)	FLUSH DOORS			
i)	Door (3'0" x 7'0")	2.00	No	
ii)	ups - (2'6" x 5'0")	1.00	No	
c)	SEMIGLAZED DOORS			
c) i)	SEMIGLAZED DOORS Manager (3'0" x 7'0")	1.00	No	
		1.00	No No	
i)	Manager (3'0" x 7'0")			
i) ii)	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0")			
i) ii) d)	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR	3.00	No	
i) ii) d) i)	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0") Cheque drop box/ Complaint	3.00	No	
i) ii) d) i)	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0")	1.00	No No	
i) ii) d) i)	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0") Cheque drop box/ Complaint Providing cheque drop box / Complaint /Suggestion	1.00	No No	
i) ii) d) i)	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0") Cheque drop box/ Complaint Providing cheque drop box / Complaint /Suggestion 1'6" length, 0'9" wide and 1'6" height with 19mm tk. Plywood and lined with 1mm tk. Laminate(Fusion	1.00	No No	
i) ii) d) i)	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0") Cheque drop box/ Complaint Providing cheque drop box / Complaint /Suggestion 1'6" length, 0'9" wide and 1'6" height with 19mm tk. Plywood and lined with 1mm tk. Laminate(Fusion Maple - Wood finish) for top & exposed sides.	1.00	No No	
i) ii) d) i)	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0") Cheque drop box/ Complaint Providing cheque drop box / Complaint /Suggestion 1'6" length, 0'9" wide and 1'6" height with 19mm tk. Plywood and lined with 1mm tk. Laminate(Fusion Maple - Wood finish) for top & exposed sides. Exposed edges of plywood shall be fixed with teak	1.00	No No	
i) ii) d) i)	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0") Cheque drop box/ Complaint Providing cheque drop box / Complaint /Suggestion 1'6" length, 0'9" wide and 1'6" height with 19mm tk. Plywood and lined with 1mm tk. Laminate(Fusion Maple - Wood finish) for top & exposed sides. Exposed edges of plywood shall be fixed with teak wood beading suitably polished and the back side	1.00	No No	
i) ii) d) i)	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0") Cheque drop box/ Complaint Providing cheque drop box / Complaint /Suggestion 1'6" length, 0'9" wide and 1'6" height with 19mm tk. Plywood and lined with 1mm tk. Laminate(Fusion Maple - Wood finish) for top & exposed sides. Exposed edges of plywood shall be fixed with teak wood beading suitably polished and the back side shall be covered with 6mm tk. plywood. The inner	1.00	No No	
i) ii) d) i)	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0") Cheque drop box/ Complaint Providing cheque drop box / Complaint /Suggestion 1'6" length, 0'9" wide and 1'6" height with 19mm tk. Plywood and lined with 1mm tk. Laminate(Fusion Maple - Wood finish) for top & exposed sides. Exposed edges of plywood shall be fixed with teak wood beading suitably polished and the back side shall be covered with 6mm tk. plywood. The inner sides shall be painted with two coats of enamel	1.00	No No	
i) ii) d) i)	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0") Cheque drop box/ Complaint Providing cheque drop box / Complaint /Suggestion 1'6" length, 0'9" wide and 1'6" height with 19mm tk. Plywood and lined with 1mm tk. Laminate(Fusion Maple - Wood finish) for top & exposed sides. Exposed edges of plywood shall be fixed with teak wood beading suitably polished and the back side shall be covered with 6mm tk. plywood. The inner sides shall be painted with two coats of enamel paint	1.00	No No	
i) ii) d) i)	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0") Cheque drop box/ Complaint Providing cheque drop box / Complaint /Suggestion 1'6" length, 0'9" wide and 1'6" height with 19mm tk. Plywood and lined with 1mm tk. Laminate(Fusion Maple - Wood finish) for top & exposed sides. Exposed edges of plywood shall be fixed with teak wood beading suitably polished and the back side shall be covered with 6mm tk. plywood. The inner sides shall be painted with two coats of enamel paint over acoat of primer & two coats of putty.	1.00	No No	
i) ii) d) i) 5	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0") Cheque drop box/ Complaint Providing cheque drop box / Complaint /Suggestion 1'6" length, 0'9" wide and 1'6" height with 19mm tk. Plywood and lined with 1mm tk. Laminate(Fusion Maple - Wood finish) for top & exposed sides. Exposed edges of plywood shall be fixed with teak wood beading suitably polished and the back side shall be covered with 6mm tk. plywood. The inner sides shall be painted with two coats of enamel paint over acoat of primer & two coats of putty. Vertical Blinds:	1.00	No No	
i) ii) d) i) 5	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0") Cheque drop box/ Complaint Providing cheque drop box / Complaint /Suggestion 1'6" length, 0'9" wide and 1'6" height with 19mm tk. Plywood and lined with 1mm tk. Laminate(Fusion Maple - Wood finish) for top & exposed sides. Exposed edges of plywood shall be fixed with teak wood beading suitably polished and the back side shall be covered with 6mm tk. plywood. The inner sides shall be painted with two coats of enamel paint over acoat of primer & two coats of putty. Vertical Blinds: Providing and fixing 100mm wide Vista Make or	1.00	No No	
i) ii) d) i) 5	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0") Cheque drop box/ Complaint Providing cheque drop box / Complaint /Suggestion 1'6" length, 0'9" wide and 1'6" height with 19mm tk. Plywood and lined with 1mm tk. Laminate(Fusion Maple - Wood finish) for top & exposed sides. Exposed edges of plywood shall be fixed with teak wood beading suitably polished and the back side shall be covered with 6mm tk. plywood. The inner sides shall be painted with two coats of enamel paint over acoat of primer & two coats of putty. Vertical Blinds: Providing and fixing 100mm wide Vista Make or equavalent vertical blinds of approved make quality	1.00	No No	
i) ii) d) i) 5	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0") Cheque drop box/ Complaint Providing cheque drop box / Complaint /Suggestion 1'6" length, 0'9" wide and 1'6" height with 19mm tk. Plywood and lined with 1mm tk. Laminate(Fusion Maple - Wood finish) for top & exposed sides. Exposed edges of plywood shall be fixed with teak wood beading suitably polished and the back side shall be covered with 6mm tk. plywood. The inner sides shall be painted with two coats of enamel paint over acoat of primer & two coats of putty. Vertical Blinds: Providing and fixing 100mm wide Vista Make or equavalent vertical blinds of approved make quality and colour shade and pattern. Rate shall include	1.00	No No	
i) ii) d) i) 5	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0") Cheque drop box/ Complaint Providing cheque drop box / Complaint /Suggestion 1'6" length, 0'9" wide and 1'6" height with 19mm tk. Plywood and lined with 1mm tk. Laminate(Fusion Maple - Wood finish) for top & exposed sides. Exposed edges of plywood shall be fixed with teak wood beading suitably polished and the back side shall be covered with 6mm tk. plywood. The inner sides shall be painted with two coats of enamel paint over acoat of primer & two coats of putty. Vertical Blinds: Providing and fixing 100mm wide Vista Make or equavalent vertical blinds of approved make quality and colour shade and pattern. Rate shall include necessary scotch guard treatment on both side. The	1.00	No No	
i) ii) d) i) 5	Manager (3'0" x 7'0") Manager, SWO & B.cash (2'6"x 7'0") WICKET DOOR Wicket Door (3'0"x3'0") Cheque drop box/ Complaint Providing cheque drop box / Complaint /Suggestion 1'6" length, 0'9" wide and 1'6" height with 19mm tk. Plywood and lined with 1mm tk. Laminate(Fusion Maple - Wood finish) for top & exposed sides. Exposed edges of plywood shall be fixed with teak wood beading suitably polished and the back side shall be covered with 6mm tk. plywood. The inner sides shall be painted with two coats of enamel paint over acoat of primer & two coats of putty. Vertical Blinds: Providing and fixing 100mm wide Vista Make or equavalent vertical blinds of approved make quality and colour shade and pattern. Rate shall include	1.00	No No	

7	FALSE CEILING (GYPBOARD)			
-	Providing & fixing suspended gypboard false ceiling,	1000.00	Sft	
	which includes Providing & fixing G.I perimeter			
	channels of size 27mm, 0.5mm thk having one flange			
	of 20mm & another flange of 20mm along with			
	perimeter of the ceiling, screws fixed to brick			
	wall/partitions with the help of rawl plugs & Screws.			
	Then suspending G.I intermediate channels of size			
	45mm, 0.9mm thk with two flanges of 15mm each			
	from the soffit at 1200mm centres with stell G.I			
	hanger of width 25mm,0.5mm thk fixed to soffit			
	with G.I. cleat & steel expansion fasteners. Ceiling			
	section of 0.5mm thickness having knurled wedge of			
	51.5mm and two flanges of 26mm each with leafs of			
	10.5mm are then fixed to the intermediate channel			
	with the help of connecting clips and in direction			
	perpendicular to the intermediate channel at			
	450mm centres. 12.5mm tapered edge gypboard is			
	then screwed fixed to ceiling section with 25mm dry			
	wall screws at 230mm centres Screw fixing will be			
	done mechanically either with screw driver or			
	drilling machine with suitable attachment. Finally			
	the tapered and squared edges of the boards are			
	jointed at finished to give a flushed finish			
	with requiste jointing compound, paper tapes,			
	finisher and premier suitable for Gypsum plaster			
	boards. The entire work shall be finished as per			
	instructions of the Architect. And also finished with			
	two or more coats of acrylic emulsion paint of			
	approved shade and make. No extra cost shall be			
	entertained in completing the entire work in all			
	respect.			
1	Total Interior Works			

THARANGAMBADI BRANCH - INTERIOR & FIXTURES WORKS FOR INDIAN BANK (NAGAPATTINAM ZONE) **BILL OF QUANTITIES-FIXTURES** S NO UNIT RATE(Rs) **PARTICULARS** QTY AMOUNT (Rs) 1 **TABLE** Manager table as per drawing done with structure made of 18mm plywood with drawer unit comprising of 1 drawer, 1 filing shelf fixed with pull out door (box type hinges), locks, D type handles and all accessories to be provided. All drawers, corners, doors to be finished with beach wood lipping/beading, melamine polished., push in type keyboard, all drawers and key board on telescopic channels. All exposed edges Teak/beach wood beadings is finished with melamine polished and inside laminated with 0.8mm laminate. The table to be topped with 12mm float glass with beveling on all four sides. The side unit is provided with two drawers and filing shelf with two pull out doors, finished in same manner.CPU platform with foot rest to be provided. wall to table gap to closed with plywood. Branch Manager 6'0"x2'6" 1.00 a) No 2 FRONT COUNTER AND BULK CASH COUNTER Providing and assembling banking counter and Cash, single window counter unit as shown in drawing of size not less than 5'0" x 2'6" x 2'6" or as per site requirements, with regular drawer - 1 No. and shelves on one side, a keyboard drawer at centre and a platform for CPU onto other side for each counter as shown in drawing using 19mm thick commerical plywood lined with 1.0mm thick laminate(Bank approved colors) Cash and single window with 12mm thick glass (to be strictly followed) in front side for all the exposed surfaces, including providing skirting 4" wide with 1.0mm thk laminate (Indian Bank Blue) on both sides to match with the adjoining partition and 4" wide border at top with 1.0mm thk laminate (Indian Bank Blue). The customer top at 3'9"ht of 1'3" width & working counter top of 2'6" width to be fixed with 19mm Granite top (approved) with double nosing @ front side as shown in the drawing

	All the plywood edges shall have teak wood lipping and			
	all inner surfaces shall be painted with two coats of			
	enamel paint over a coat of primer & two coats of			
	putty. The rate shall include providing, fixing & painting			
	a foot rest using first class seasoned country frame of			
	size 3" x 1 1/2".Necessary hardware fittings like draw			
	sliders, hinges, multipurpose locks with set keys,			
	handles shall be provided.			
	·			
i)	Bulk cash	5.00	Rft	
ii)	Working counters	32.00	Rft	
2	STORAGE	0=100		
	Providing and fixing filing cabinet in manager cabin for			
	a height of 2'6" & 7' ht. made of 18mm plywood			
	structure comprising of suitable intermediate			
	horizontal racks with open type doors, finished with			
	1mm laminate and teak wood beadings neatly			
	melamine polished and inside finished with 0.8mm			
	laminate with locks, handles and all accessories			
	idifficate with locks, fiduales and all accessories			
i)	Manager Sc	10.00	Sft	
ii)	Cash Sc	20.00	Sft	
iii)	Record Sc	57.75	Sft	
iv)	Hall Sc	63.00	Sft	
v)	Hall - Side Credenza	175.00	Sft	
3	WRITING LEDGE WITH 12mm GLASS TOP	175.00	310	
	Made out 18 mm ply as per design and exposed	1.00	No	
	external surfaces to be laminated and internal surface	1.00	140	
	to be painted with top provided 12 mm thk etched			
	glass with machine polished edges. The entire work			
	has to be done to the satisfaction of the architect. The			
	design given has to be strictly followed			
	design given has to be strictly followed			
	NOTICE BOARD			
4	NOTICE BOARD Drawiding and fiving of the soft heard on the sustamer	12.00	Ct+	
	Providing and fixing of the soft board on the customer	12.00	Sft	
	lobby made of jolly board with a fabric of B / R @ 200 /			
	- per meter .The design and the entire work has to be			
	done as per the instructions of the architect a the time			
	of execution			
5	ROLLING SHUTTER COVER BOX			
	Supplying & fixing of rolling shutter box using 19mm	45.00	sft	
	thk plywood with adequate support at the ends and	.3.00	3.0	
	finished with lamination of approved make and colour			
	etc., complete			
	•			
1	Total Interior Works			

THARANGAMBADI BRANCH - ELECTRICAL WORKS FOR INDIAN BANK (NAGAPATTINAM ZONE)

BILL OF QUANTITIES-ELECTRICAL

SI.No	Description Of Work	Unit	Qty	Rate	Amount
Α	Supply&Installation&Commisioing of the following				
1	MAIN DB (8WAY VTPN DB)				
	Three Phase, Vertical Distribution board				
	with nuetral bar,earth bar,cables ties,top and				
	bottom removable gland plate and with necessary				
	adopter boxes if any. The DB should be IP 42 metallic				
	double door with provisioin of MCB etc as				
	required including cuting of wall and plastering the				
	same with neat finish.It comprising as flolows:-				
	Incomer :				
	100A TPN MCCB -1Nos				
	Outgoings:				
	63A TP MCB -4Nos				
	32/25/20A SP MCBs- 5Nos	Set	1		
В	Supply&Installation&Commisioing of the following				
1	LIGHTING DB(4WAY TPN DB)				
	Three Phase, Phase Segrigated Distribution board				
	with nuetral bar,earth bar,cables ties,top and				
	bottom removable gland plate and with necessary				
	adopter boxes if any.The DB should be IP 42 metallic				
	double door with provisioin of MCB,RCBO etc as				
	required including cuting of wall and plastering the				
	same with neat finish.It comprising as flolows:-				
	Incomer : 40A TPN RCBO & ELCB				
	Outgoings:				
	10/6A SP MCBs- 12Nos	Set	1		
2	POWER DB(4WAY TPN DB)				
	Three Phase, Phase Segrigated Distribution board				
	with nuetral bar,earth bar,cables ties,top and				
	bottom removable gland plate and with necessary				
	adopter boxes if any.The DB should be IP 42 metallic				
	double door with provisioin of MCB&ELCB etc as				
	required including cuting of wall and plastering the				
	same with neat finish.It comprising as flolows:-				
	Incomer : 63A TPN RCBO				
	Outgoings:				
	32/25/20A SP MCBs- 12Nos	Set	1		
3	COMPUTER DB(8WAY SPN DB)				

	Language on the state of the st				
	12 Way SPN Distribution board				
	with nuetral bar,earth bar,cables ties,top and				
	bottom removable gland plate and with necessary				
	adopter boxes if any.The DB should be IP 42 metallic				
	double door with provisioin of MCB&ELCB etc as				
	required including cuting of wall and plastering the				
	same with neat finish.It comprising as flolows:-				
	Incomer : 40ADP MCB				
	Outgoings:				
	10A SP MCBs- 6Nos	Set	2		
4	Supply&Installation of the following with the necessary				
	enclosure and adopter boxes if necessary,				
	a)63A TPN MCB	Set	2		
	b)63A DP MCB	Set	5		
5	Supply&Installation of 32A Metal Clad Socket with				1
	top in a specified company manufactured box with				
	suitable rating MCB for AIR CONDITIONS	set	7		
	Suitable fating Web for Air CONDITIONS	300	,		
6	Supply&Installation of 63A 4Pole Change over switch	set	1		
- 0	Supply&llistaliation of 65A 4Pole Change over switch	Set			
	Cumply and Fiving for 62A Phase Calastor switch with				
7	Supply and Fixing for 63A Phase Selector switch with		_		
	enclosure and adopter boxes if necessary,	set	2		
<u> </u>					
С	LT CABLES				
1	Supply&Laying of the following cables in built up				
}	trenches, on wall, or in the ground as per the case may be,				
	with proper clamping with necessary fixing materials etc.				
	Installing testing&commisioing of 1100V grede UG				
	cable as per IS 7098/1554 (Finolex/ Universal)				
	3.5Corex50Sqmm Aluminium Armored cable Main DB	Mtr	38		
	3.5Corex35Sqmm Aluminium Armored cable power DB	Mtr	28		
	3.5Corex16Sqmm Aluminium Armored cable LDB Main	Mtr	34		
2	End Termination of the above cables with proper Glands				
	and Lugs				
	3.5Corex50Sqmm Aluminium Armored cable Main DB	Set	2		
	3.5Corex35Sqmm Aluminium Armored cable power DB	Set	2		
	3.5Corex16Sqmm Aluminium Armored cable LDB Main	Set	4		
D	WIRING				
1	Light/Fan point wiring with 3 of 1.5 sqmm PVC				
	insulated copper conductor to be laid in 2mm suitable				
	PVC conduit with Bend, Couplings, etc And fixing with				
	clamps screws etc.All conduits to be laid above the				
	false ceiling/partition/concealed in the wall				
	etc. Wiring to be connected with supply&Fixing of				
				1	

	Ica aa 11	I	ı	1	F	
	6A Modular type switch(MK/ROMA) with suitable					
	Modular plate and metal Box					
	a) One light Controlled by One Switch	Pts	24			
	b) Two light Controlled by One Switch	pts	18			
	c) 6A Switch box Sockets in the switch board itself	Pts	15			
	d) Ceiling fan with regulator	Pts	4			
	e) wall bracket fan point (6A socket with 6A switch)	pts	12			
	f) Calling bell point with Calling bell instrument	Pts	1			
	g)Exhaust fan point	pts	3			
2	Supply&Wiring with Flame Retardant					
	insulated PVc wire as per grade IS 994					
	for Circuits,Computer point,Power points within 2mm thk					
	PVc conduits with necessary accessories and with					
	proper clamps and to be concealed below the false					
	ceiling It comprises as follows:-					
	a) 3Runs of 2.5Sqmmcopper wire in PVC conduit for					
	lighting circuit mains	Mtr	180			
	b) 3Runs of 2.5Sqmmcopper wire in PVC conduit for					
	Power points	Mtr	210			
	C) 3Runs of 2.5Sqmm copper wire in PVC conduit for					
	computer points	Mtr	220			
	d) 2Runs of 4Sqmm copper wire+1.5Sqmm copper					
	wire in PVC conduit A/C Wiring	Mtr	220			
	e) 2Runs of 6Sqmm copper wire+2.5Sqmm copper					
	wire in PVC conduit	Mtr	33			
	f) 4Runs of 6Sqmm copper wire+2.5Sqmm copper					
	wire in PVC conduit	Mtr	28			
	POWER POINT OUTLETS					
1	Supply&Installation of 3 Nos of 6A Sockets controlled by					
	2of 5A Switches with front plate with enclosure and	_				
	other accessories etc(MK /ROMA)	Set	12			
2	Supply&Installation of 1Nos of 6A Socket controlled by					
	1No 6A Switch with front plate with enclosure and other					
	accessories etc(MK /ROMA)	Set	10			
3	Supply&Installation of 1Nos of 16A Socket controlled by					
	1No 16A Switch with front plate with enclosure and other					
	accessories etc(MK /ROMA)	set	4			
F	LIGHTING FIXTURES					
1	Supply, Fixing & Commissioning of Recess mounting type					
	compact vertical Flat Panel 34W LED fitting in Down Rods with					
	white finish and other fixing accessories.(Crompton,					
	Wipro,Philips)	set	18			

	la 1 = 1	1		ı		
2	Supply, Fixing & Commissioning of Recess mounting type					
	compact vertical round shaped 1x15W LED downlighter fitting					
	with white finish and other fixing accessories.,(Crompton,					
	Wipro,Philips)	set	4			
3	Supply&Fixing of Patti Type LED 20Watts Fiitings (Crompton,					
	Wipro,Philips)	Set	11			
4	Supply&Fixing exhaust fan (Crompton, Almonard)	set	3			
5	Supply&Fixing & Commisioning of wall mounting fan					
	with necessary Down Rods and with all					
	fixing accessories.,(Crompton / Havells)	Set	12			
6	Supply&Fixing & Commisioning of 48" ceiling fan					
	with necessary Down Rods and with all					
	fixing accessories.,(Crompton / Havells)	Set	2			
G	EARTHING		İ		1	
1	Providing dedicated earthing with 600x600x3.15				1	
	mm copper plate along with 50mm dia.10feet				1	
	long G.I pipe with other accessories in the earth				1	
	filled with necessary salt, charcoal, etc. It should					
	be covered with G.I Manhole cover with necessary					
	civil works.etc	Set	1			
	CIVII WOLKS.CCC	Jet				
2	Supply & Laying of 10 Sqmm PVC Insulated Multi					
	strand copper conductor laid in 25mm dia PVC pipe for					
	Dedicated earth leads from the earth electrodes to					
	the UPSsystem	Mtr	38			
	the or saystem	IVILI	30			
3	Providing general earthing with 50mm dia.10feet					
	long G.I pipe with other accessories in the earth					
	filled with necessary salt, charcoal, etc. It should					
	be covered with G.I Manhole cover with necessary					
	civil works.etc	Set	1			
	CIVII WOIKS.Etc	Set	1			
	Cumply Playing of OCMC compartuits	N /1+10	Γ0			
4	Supply&Laying of 8SWG copper wire	Mtr	50		+	
<u> </u>	TELECONANALINICATION!				1	
F	TELECOMMUNICATION				1	
1	Supply&Laying of 2 Pair Telephone Cable within PVC	N 4+	100		1	
	Conduit and its necessary accessories etc	Mtr	180		1	
_	Complete Landing of 200-in Table have Call 1981 1982		-		1	
2	Supply&Laying of 20Pair Telephone Cable within PVC	2.0	20		1	
	Conduit and its necessary accessories etc	Mtr	30		1	
	Complete Design of State of the control of State				1	
3	Supply&Installation of RJ II Jack with necessary Face	6 1			1	
	plate and Box for connecting telephone points	Set	10			
4	Supply & fixing of 10 pair KRONE Box with lock and key	Set	1		1	
	TOTAL					

THARANGAMBADI BRANCH & ATM - DATA CABLING WORKS FOR INDIAN BANK (NAGAPATTINAM ZONE) **BILL OF QUANTITIES-DATA CABLING** S.No Unit **Description Of Work** Qty Rate Amount **DATA CABLING** Supply&Laying of CAT 6 Data Communication cable in 2mm thk heavy duty 20mm dia PVC conduit and makinng holes in the aluminium partitions/wall all accessories as required (DLink) Mtr 320 Supply&Installation,Testing&Commission of Modular type 1Nos of RJ45 Female Jack housed in GI anodised metal box with suitable Faceplate fixing the same in the wall/partitions with all accessories etc. as required. Set 11 Supply and fixing of 1M Mounting Cord Set 11 Supply and fixing of 2M Mounting Cord Set 11 Supply&Installation of 24por cat6 SWITCH Set Supply and installation of 24port cat 6 jack panel 6 Set 1 Supply and installation of 9u wall mounting rack Set **TOTAL**

THARANGAMBADI BRANCH - AIR CONDITIONING WORKS FOR INDIAN BANK (NAGAPATTINAM ZONE)

	BILL OF QUANTITIES-BRANCH AC WORKS						
Sl.No	Description Of Work	Unit					
1	Supply, Testing and commissioning of						
	indoor and outdoor split air conditioner with remote						
	control, with 3 star rating units and necessary civil						
	works etc., The rate of units is including the supply						
	and laying of 3 mtr of copper pipes with insulations,						
	rubbers, white cements etc., (Brand: Voltas)						
а	1.0 TR - Manager & Server&Hall	2	No				
b	2 TR - Banking hall and manager	5	No				
2	Supply and laying of copper pipes with rubber						
	insulations, rubbers, white cements etc.,	60	Mtr				
3	Supply and installation of Stabilizer for following						
	units						
а	1.5 TR - 4 KVA	2	No				
b	2 TR - 5 KVA	5	No				
	Installation Charges for 1.5 Tr,2 Tr Split Air Conditioner						
b		7	No				
4	Supply and Installation of Outdoor Stand with						
	necessary civil works	7	No				
5	Supply and laying of PVC Blue pipes for water						
	drain from the indoor units.	56	Mtr				
	Civil works like cutting AC hole,packing,drain pipe cutting						
6	and packing with mortar etc.	1	Ls				
7	Supply and fixing Timer controlled for server Unit	1	No.				
	Airconditioning works Total:	_					

THARANGAMPADI - ATM INTERIOR WORKS FOR INDIAN BANK (NAGAPATTINAM ZONE)

BOQ - ATM INTERIOR

S.No	ITEMS AND DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	FULLY GLAZED ALUMINIUM PARTITION & DOOR				
a b	FULLY GLAZED ALUMINIUM PARTITION & DOOR FRONT BOTH SIDE FIXED PARTITION: Providing and fixing Fully glazed partition in ATM Entrance, made of aluminium MRF vapocured twin style frame work of size:-58 x38mm, 20 micron of IB-Black colour finished with 10 mm thk float glass with derk silicon (SAINT GOBAIN or MODIGUARD) up to the false ceiling level. Support to be done to the rcc ceiling, but measurements would be taken below the false ceiling level only. ENTRANCE DOOR (Size: 3'6"x7'0"): Providing and fixing of Fully glazed door for ATM entrance, made of	25	Sft		
	aluminium MRF vapocured twin style frame of size:-100 x 50 mm, 20 micron of approved colour finished with 10 mm edge polished glass with silicon (SAINT GOBAIN or MODIGUARD) up to the 7'0" height, door to be provided with dorma make 12" SS handle, lock and door closure(approved make) & stopper				
2	ACP WALL PANELLING	274	C.C.		
	Providing and fixing Wall Panelling using 3mm thk Aluminium Composite Panels of Alstrong or equivalant make over necessary frame work. The joints formed by the junction of two panels shall be filled with silicon sealent. The Wall Panelling / Boxing shall be erected 75 mm above the Highest False Ceiling Level. However, only exposed portions below the Highest False Ceiling Level shall be considered for payment. Pattern of wall panelling to be got colour approved from the Bank.		Sft		
3	GYPBOARD FALSE CEILING				
	Supply and erection of gypboard false ceiling for Manager cabin area at single level with framework of G.I. Section of spacing 4'0" x 2'0" above with 12mm gypboard fixing. Recessed ceiling is to be done as per architects instruction to have provision for indirect lighting rate is included for cutouts for lights, smoke detectors and AC grills. The ceiling is putty finished and sanded to form clean and homogeneous surface. Rate is included for two coats of acrylic emulsion painting.		sft		

				1	
4	ATM SOCKETS COVER BOX (1'0"X1'0"x6" - 1no)				
	All ATM Sockets, IO Box to be covered using 12mm	2	nos		
	plywood structure with 1mm thk lamination finish				
	(matching ACP color colour), Shutter type door (up &				
	down) with lock, handle and necessary wire manager				
	groove (at bottom) to be provided.				
5	PIN-UP NOTICE BOARD				
	Providing & fixing Pin-up Board of approx size of 600mm	1	no		
	x 800mm made of textile wrapped on 12 mm thick soft				
	board with 6 mm com ply backing and a frame work of				
	50mm wide with 24 mm thk com ply, finished with 1				
	mm thk Laminate. The Pin-up Board shall be set into the				
	wall panelling with necessary fittings as directed by the				
	Bank.				
6	WRITING DESK				
	Writing desk to be done as per plan with 12mm glass	1	no		
	topped with pigeon holes made with 18mm plywood				
	structure with additional boxing as per design,				
7	CHEQUE DROP BOX/ COMPLAINT				
	Providing cheque drop box/Complaint/Suggestion 1'6"	1	no		
	length, 0'9" wideand 1'6" height with 19mmtk. Plywood				
	and lined with 1mmtk. Laminate (Fusion Maple Wood				
	finish) for top & exposed sides. Exposed edges of				
	plywood shall be fixed with teak wood be ading suitably				
	polished and the back sides hall be covered with 6mmtk.				
	plywood. The innersides shall be painted with two coats				
	of enamel paint over a coat of primer & two coats of				
	putty.				
L					
8	ROLLING SHUTTER COVER BOX				
	Supplying & fixing of shutter box using 19 mm plywood,	28	sft		
	boxing with above entrance partiton and rolling shutter				
	and finished with 1mm lamination.				
	TOTAL				
	IUIAL				

	THARANGAMBADI ATM - ELECTRICAL WORKS FOR INDIAN BANK (NAGAPATTINAM ZONE)						
BOQ-ATM ELECTRICAL							
SI.	Description	Qty	Unit	Rate	Amount		
Α	MAINS & DISTRIBUTION BOARDS						
1	Supply, erection, testing and commissioning of three						
	phase 4 WAY, TPN MCB DB double door vertical type,						
	IP 42 powder coated with						
	40A TPN MCB – 1No as INCOMER						
	32A DP MCB-1No For UPS						
	10/25/32A – 4No.s as OUTGOING						
	Including all interconnections & accessories etc	1	No				
В	POWER CABLES & CONDUIT WIRING						
1	Supplying, laying, testing & commissioning of PVC /						
	LT insulated 1.1KV grade aluminium armoured						
	conductor cables of the following sizes, laid in trenches						
	below ground level/ clamped on to the walls as per site						
	condition.						
а	3.5C x 25Sqmm aluminium armoured PVC cable	17	mtr				
С	Supplying and terminating the end of cables of the						
	following sizes using Siemens type single compression						
	cable glands, crimping type aluminium / copper						
	sockets of required size, gland earthing clips etc.,						
	complete.						
a	3.5C x 25Sqmm aluminium armoured PVC cable	2	Set				
D	AIR CONDITIONING WIRING & ACCESSORIES						
1	Supply&Installation of 32A Metal Clad Socket with						
	top in a specified company manufactured box with						
	suitable rating MCB for AIR CONDITIONS	2	No				
2	Wiring in position 2 runs of 4.0 sq.mm. cable and 1 run						
	of 2.5 sq.mm cable for earth from Main D.B. to 2 Nos						
	split air – conditioners in P.V.C. conduit pipes including						
	chasing in walls / floor wherever necessary.	22	Mtr				
Ε	UPS WIRING & ACCESSORIES						
1	Supply, erection, testing and commissioning of single						
	phase 6 WAY, SPN MCBDB double door type, IP 42						
	powder coated for UPS and Emergency Lighting with						
	40A DP MCB – 1No as INCOMER						
	10A SP MCB – 4Nos. as OUTGOING						
	Including all interconnections & accessories etc.,						
	complete.	1	Set				
2	Wiring in position 2 runs of 6.0 sq.mm. cable and 1 run						
	of 4.0 sq.mm cable for earth from Main D.B. to UPS and						
	UPS to UPS DB.	11	Mtr				

				Ι	
3	Wiring in nocition 2 runs of 2 E sq. mm cable for circuits from				
	Wiring in position 3 runs of 2.5.sq.mm cable for circuits from UPS.Lighting, Raw power required places in P.V.C. Conduit				
	1 .	22	N/1+10		
	pipes including chasing in walls / floor wherever necessary	32	Mtr		
4	Supply, fixing, testing & commissioning of 2No. 16A				
	multi pin socket outlet in UPS circuit controlled with				
	1No. 16A one way switch in a steel sheet enclosure with				
	8 module top plate including dummies and incidental	_	NI-		
	materials etc.,	2	No		
F	LIGHTING WIRING				
	Supply, fixing, testing & commissioning of the following				
	switch controls in steel sheet enclosure including 3 runs				
	of 1.5sqmm, steel sheet enclosure & modular top plate				
	and all incidental materials etc., complete.	4		ļ	
1	One light Controlled by One Switch	1	No	<u> </u>	
2	1 No. 6A socket controlled by single switch	2	No		
G	LIGHTING & FIXTURES				
1	SFTC for the following light fittings with required				
	hardwares such as suspension wires from ceiling, false				
	ceiling, anchor fasteners, chains, bolts, nuts etc.,				
	complete.				
a	36 watts LED light fitting with 2'X2'	2	No		
b	15 watts LED round fitting with LED as	4	No		
С	20watts LED Patty fitting	1	No		
Н	DATA POINT				
1	Supply&Laying of CAT 6 Data Communication cable in 2mm				
	thk heavy duty 20mm dia PVC conduit	40	mtr		
2	Supply&Installation,Testing&Commissiong of Modular type				
	1Nos of RJ45 Female Jack housed in GI anodised metal box				
	with suitable Faceplate fixing the same in the wall/partitions				
	with all accessories etc. as required.	2	No		
I	EARTHING				
1	Providing earthing two numbers , One for ATM and				
	another for AIR-CONDITIONERS including excavating				
	the P.C.C. floor/ earth to 6'0" depth and providing				
	earthing with 50mm dia. G.I. pipe with perforations				
	connected through copper wire including copper flat				
	including copper plate of size 300mm x 300mm, G.I.				
	bolts and filled up with layers of charcoal, salt and				
	earth. (Earth provided for computers shall not be used				
	for any other purpose)	1	No		
2	Supplying and laying of 6 Sqmm multi stranded copper				
	wire for UPS earth in suitable PVC conduit with all				
	incidental materials etc., complete.	18	Mtr		
	Total				

THARANGAMBADI ATM - AIR CONDITIONING WORKS FOR INDIAN BANK (NAGAPATTINAM ZONE) **BILL OF QUANTITIES - ATM AC** SI.No **Description Of Work** Unit Qty Rate Amount 1 Supply, Testing and commissioning of indoor and outdoor split air conditioner with remote control, with 3 star rating units and necessary civil works etc., The rate of units is including the supply and laying of 3 mtr of copper pipes with insulations, rubbers, white cements etc., (Brand: Voltas) 1 TR - Manager & Server No 2 Supply and laying of copper pipes with rubber insulations, rubbers, white cements etc., 20 Mtr Supply and installation of Stabilizer for following 3 units 1.5 TR - 3 KVA 2 No а b Installation Charges for 1 Tr Split Air Conditioner 2 No Supply and Installation of Outdoor Stand with 4 necessary civil works 2 No Supply and laying of PVC Blue pipes for water drain from the indoor units. 15 Mtr 6 Civil works like cutting AC hole, packing, drain pipe cutting and packing with mortar etc. 1 Ls 7 1 Supply and fixing for Timer for A/C Controlled No

Airconditioning works Total: