

**Indian Bank**  
**ZONAL OFFICE KOLKATA CENTRAL**

**NOTICE INVITING TENDER FROM BANK'S EMPANELLED CONTRACTORS**

Indian Bank, Zonal Office Kolkata Central invites sealed tenders in the prescribed format on item rate basis (financial) **from the Bank's empanelled contractors** for proposed Interior Works in the existing Premises of Tollygunge Branch, at 76, Golf Club Road Kolkata - 700033.

**Full details and Tender documents may be downloaded from Banks web site [www.indianbank.co.in](http://www.indianbank.co.in) or may be obtained from Premises & Expenditure Department, Zonal Office Kolkata Central, 3<sup>rd</sup> Floor, 14, India Exchange Place, Kolkata-700001, West Bengal, as per following programme.**

1	Name of work	FURNISHING and CIVIL Work in the existing Premises of Tollygunge Branch, KOLKATA.
3	Period of completion	30 days to be reckoned from 5 <sup>TH</sup> day from the date of issue of the Work Order or handing over of site whichever is later.
4	Validity of Tender/ Quotation	90 Days from the date of opening
5	Defects Liability Period	12 Months from the date of virtual completion of work
6	<b>Application Fee</b>	<b>Rs.1000/-</b>
7	Initial Security Deposit (ISD)	After acceptance of Work Order, Contractor shall submit ISD of 2% of the Bid / Contract Amount in the form of DD.
8	Retention Money (RM)	8% of the Bill Amount excluding Taxes
9	Total Security Deposit (TSD) = ISD + RM	10% of the Bid Amount (ISD - 2% & RM - 8%) ISD Amount will be refunded to Contractor within 14 days from the issue of Work Completion Certificate by the Architect and the Retention Money will be refunded after the completion of defect liability period.
10	Interim / Adhoc Payment	No Interim / Adhoc Payment will be paid
11	Payment terms	Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 8% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period.
12	Documents to be attached with the Bill	Managers Completion Certificate, Manufacture Certification, Bills & Photographs showing completion status of work.
13	Liquidated Damages	1% per week of the Contract Value subject to maximum total of 10% of final Contract value
14	Eligibility	<b>BANK'S EMPANELLED CONTRACTORS</b>
15	Tender Documents	Tender documents can be obtained from Indian Bank, Zonal Office, Kolkata Central, Premises Department, 3 <sup>rd</sup> Floor, 14,

*Handwritten signature*

		India Exchange Place, Kolkata-700001, from 16/11/2024 to 30/11/2024 upto 5 pm on all working days during office hours and / or can be downloaded from the Bank's website ( <a href="http://www.indianbank.in">www.indianbank.in</a> ) under Tenders column.
16	Last date of submission of tenders / quotation	30/11/2024 upto 5 pm at Indian Bank, Zonal Office, Premises Department, Zonal Office Kolkata Central, 3 <sup>rd</sup> Floor, 14, India Exchange Place, Kolkata-700001.
17	Date of opening Tender	02/12/2024 at 11 am at Indian Bank, Zonal Office, Premises Department, Zonal Office Kolkata Central, 3 <sup>rd</sup> Floor, 14, India Exchange Place, Kolkata-700001.
18	Terms and conditions	As per Technical Bid part - B

**Note:**

1. The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tender without assigning any reason whatsoever. Late / delayed tender shall not be accepted after due date and time of submission of tender.
2. The rates quoted by the tender shall be based only on the specifications and conditions of the tender documents.
3. Bank is not liable to make any payment to tenders for preparation to submit the tender/bid/quotation.

<p><b>Tenders Documents: -</b>  <b>A) Technical Part-A + Part B + Application Fee</b>  <b>B) Financial bid: Schedule of Quantity</b></p>
--------------------------------------------------------------------------------------------------------------------------------------------------

The duly filled in offer completed in all respect in sealed cover marked "Financial Bid" and superscribing "FURNISHING & CIVIL" Works etc. at Existing premises of Tollygunge Branch on top and name, address, contact no. & e-mail id of the vendor at bottom left corner should be addressed to

**The Zonal Manager**  
**Indian Bank, Zonal Office: Kolkata Central,**  
**3rd Floor, 14, India Exchange Place, Kolkata-700001, West Bengal**

Date: 16.11.2024  
Place: Kolkata

  
(DY. ZONAL MANAGER)  


इंडियन बैंक



Indian Bank

इलाहाबाद

ALLAHABAD

**PREMISES DEPARTMENT  
ZONAL OFFICE KOLKATA CENTRAL**

*TENDER DOCUMENT FOR BANK'S EMPANELLED CONTRACTORS FOR  
INTERIOR FURNISHING & CIVIL WORKS IN THE EXISTING PREMISES  
OF INDIAN BANK, TOLLYGUNGE BRANCH, KOLKATA*

Ref:No: ZOKOLCentral: PRM: TENDER:2024-25: 01

Date : 16.11.2024

Issued to:

M/S. ....  
ADDRESS .....  
CONTACT.....  
E-MAIL: .....

Last date of submission of Tender	16.11.2024 upto 17:00 HRS at Indian Bank, Zonal Office, Kolkata Central, Premises Department, 3 <sup>rd</sup> Floor, 14, India Exchange Place, Kolkata-700001.
Date of opening Tender	02.12.2024 at 11:00 HRS at Indian Bank, Zonal Office, Kolkata Central, Premises Department, 3 <sup>rd</sup> Floor, 14, India Exchange Place, Kolkata-700001.
Cost Of Tender	Rs.1000/-.

**CONSULTANT:**

**M/s. BURMAN ET.AL**

Architecture .Interior. Engineering. QAQC

Villa No:- 05, Basement, Block-2, Eros Garden, Charmwood Village, Surajkund Road, Faridabad, Haryana-121009, Tel : 0129-4876589, (M) : 9811210589, 8800147589. Email:-

burmanetal2008@gmail.com, jburmanroy@gmail.com, burmanetal2008@gmail

इंडियन बैंक



Indian Bank

इलाहाबाद

ALLAHABAD

FORM OF TENDER

Technical part - A

Indian Bank  
Zonal Office Kolkata Central  
Premises Department  
3<sup>rd</sup> Floor, 14, India Exchange Place,  
Kolkata-700001,

Dear Sir,

**SUB: Invitation of Tender for INTERIOR FURNISHING AND CIVIL Work  
in the existing Premises of Tollygunge Branch, Kolkata**

I /we being empanelled contractors of the Bank and having examined the drawings, specifications, conditions and schedule of quantities prepared by you, and satisfying ourselves as to the location of the site and working conditions, I/We hereby offer to execute the above works at the respective rates which I/We have quoted for the items in the Schedule of Quantities.

I/We herewith deposit **Rs.1000 /- (Rupees One Thousand Only)** by crossed demand draft payable at KOLKATA and drawn in favour of "Indian Bank" as Application Money for the Tender / due execution of the works at my/our tendered, together with any variations should the work be awarded to me/us.

In the event of this tender being accepted, I/We agree to enter into and execute the necessary contract required by you. I/We do hereby bind myself/ourselves to Deposit 2% of the work order as ISD (initial security deposit), if selected. The amount will be forfeited in the event of our refusal or delay in signing the Contract Agreement. I/We further agree to complete the work within the stipulated time specified in the Appendix to General Conditions of Contract.

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tender without assigning any reason whatsoever.

I/We agree to keep our tender open for **90 (Ninety) days** from the date of opening of Envelope No.1.

I/We enclose the completed tender documents duly signed under sealed envelopes and the Application Money of Rs.1,000/- (Rupees One Thousand only) by Bank Draft No. .... dated ..... Issued by .....

Thanking you,

Yours faithfully,

Place:

Date :

[To be signed by the Authorized Representative of  
Tenderer who has the Power to do so]

## FORM OF TENDER

Technical Part - B

### Interior Furnishing and Civil Works at the existing premises of Tollygunge Branch at 76, Golf Club Road, Kolkata - 700033.

#### TERMS AND CONDITIONS

1. The Contractor is advised to inspect and examine the sites and satisfy himself as to the condition prevailing at sites and its surrounding extert of work, scope and conditions under which the work is to be executed. The contractor shall also satisfy himself about the accessibility to the premises.
2. **The rate quoted in the tenders shall be inclusive of all materials as required.**
3. **Work will be completed within the period of 30 days from the work order whichever is earlier. If the work be not completed to the satisfaction of employer within the stipulated period, the contractor will be bound to pay to Indian Bank a sum equivalent to Rs. 2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un commenced or unfinished after expiry of the completion date.**
4. Contractors are required to submit time schedule of work. After completion of work, cleaning of floors, walls and the site shall be cleared of all rubbish in all respect. All holes shall be filled up and finished as per existing finishes.
5. The tenderer must obtain for himself on his own responsibility and at his own expenses all the informations which may be necessary for the purpose of filling this tender and for entering into a contract for the execution of the same and must examine the drawings and inspect the site of the work and acquaint himself with local conditions and matters pertaining thereto, nature and requirements of the work facilities of transport condition, access and storage of material. The tenderer shall provide in their tender the cost of carriage, freight and other charges as also for any special difficulties and including police restriction for transport etc. for proper execution of the work as indicated in the drawings. The successful tenderer will not be entitled to any claim of compensation for difficulties faced or losses incurred on account of any site condition which existed before the commencement of the work or which in the opinion of the architects might have deemed to have reasonably been inferred to be so existing before commencement of work.
6. Each of the tender documents is required to be signed by the person or persons submitting the tender in token of his having acquainted himself with all the conditions/ specifications as may be laid down. Any tender with any such document / paper not signed or with details marked as applied for shall be out rightly rejected. It will be obligatory on the part of tenderers to sign on all the pages of the tender. Conditional tenders shall be rejected. If any of the documents are missing or unsigned the tender shall be considered as invalid also rates not filled up in any item or marked as actual plus percentages shall make the tender as invalid and shall be rejected.
7. The tender form must be typed/written in ink and not by the pencil. The tenderer shall not make any correction/alteration on these documents. Over writing of figures is not permitted. Failure to comply with either of these conditions will render the tender void. No advice or any change in rates or conditions after submission of the tender will be entertained.
8. **Security deposit equivalent to 10% from each running bill shall be deducted and shall be returned after expiry of defect liability period of 12 months from the date of virtual completion as certified by the architect, provided to the satisfaction to the Bank.**

9. All compensation or other sums of money payable by the contractor to Indian Bank under the terms of this contract may be deducted from the security deposit or from any other sum that may be or may become due to the contractor on any account whatsoever and in the event of the security deposit being reduced by reason of such deductions the contractor shall within 7 days of being asked to do so make good in cash or cheque any sum or sums which may have been deducted from his security deposit.
10. In case where the same item of work is mentioned at more than one place in the schedule of quantities the lowest of the rates quoted by the contractor shall be taken into account for payment of the item.
11. The rates quoted shall be firm and shall include all costs, charges, freight, allowances, taxes, levies, taxes, royalties etc. as applicable. **GST should be mentioned separately. Taxes like TDS etc. shall be deducted from the bill(s) of the contractor as per prevailing rates.** In case of any exemption claimed in this regard the contractor shall submit requisite certificates from the respective departments to Indian Bank in advance.
12. Any damage done to the property of Indian Bank during execution of work shall be the responsibility of the contractor and it shall be made good by him at his cost to the entire satisfaction of consulting architect/ Indian Bank. The architect & engineer shall have full powers to get the material or workmanship etc. inspected and tested by an independent agency for its soundness and adequacy at the cost of contractor. Prior approval of brand and material of ISI make as per the general material specifications is sole discretion of engineer in-charge binding upon the contractor.
13. **The quantities contained in the schedule are approximate only.**
14. No advance shall be released to the contractors at the start of work. Only one running payment shall be made to the contractor as per the work progress after verification of running bill by the architect/ Bank. Tender shall be valid for a period of 3 months from the due date of its submission. **However, Indian Bank is not bound to accept the lowest or any tender and reserves the right to accept or reject any or all tenders either in whole or in part, without assigning any reason for the same. Conditional tenders are not acceptable and shall be summarily rejected. Further, no communication in this regard will be entertained.**
15. All items of work mentioned in the schedule of quantities are to be deemed and paid as completed works in all respects and details including preparatory and finishing works involved directly, related to and reasonably detectable from the drawings, specifications and schedule of quantities and no further extra charge will be allowed in this connection. In the case of lump sum charges in the tender in respect of any item of works, the payment of such items of work will be made for actual work done on the basis of lump sum charges as will be assessed to be payable by Indian Bank/ Architect.
16. The tenderer should note that the tender is strictly on item rate basis and their attention is drawn on the fact that the rates for each and every item should be correct, workable and self-supporting and based on the specification schedule submitted herewith. Financial bids marked as percentages above or below the PWD BSR / CPWD BSR or any such other instrument would be summarily rejected. If called upon by Bank/ Architects detailed analysis of any or all the rates will have to be submitted. The Architects / Bank is not bound to recognize the contractor's analysis.
17. All designated material samples will be tested and inspected at contractor's expense if desired by the Bank at designated laboratories.
18. The contractor shall conform to the provision of all local byelaws and acts relating to the work and to the regulations etc. of the government and local authorities and of any company with whose system the building is supposed to be constructed. The contractor shall give all the notices required by the said act, rules and regulation and byelaws etc. and pay all charges/ fees payable to such authorities for execution of the work involved. The cost if any shall be deemed to have been included in his quoted rates, taking into account all liabilities for licenses, fees for footpath encroachment, restoration etc. and shall indemnify the employer against such liabilities and shall defend all actions arising from such claims of liabilities.

19. For any further drawings/ details/ clarifications please have an advice through the Bank.
- 20. Bank reserves the right to cancel all or any of the tenders and can change / drop/ reduce the quantities/ items mentioned in the schedule at any time, before placing of the order or even during execution. The decision of the Zonal Manager in all matters pertaining to the work execution shall be final and binding.**
21. Prior approval to be obtained in writing from project architect/ bank if any change made in the design/ execution of works.
22. Final bill will not be processed until rectification of defects pointed out by the project architect/ bank is carried out by the contractor.
23. All taxes and duties including sales Tax, E.S.I. charges etc. as applicable, Central or Octroi, Royalties, Interstate transportation etc. on works and materials required for use in this project shall be entirely borne & payable by the contractor. The Employer will not entertain any claim whatsoever in this respect. The rates shall be firm and shall not be subject to cost escalation of labour and material and exchange variations, labour conditions and other conditions whatsoever.
- 24. Certified photocopies of – GSTIN, PAN Card, (exemption if any) shall need to be submitted along with all bills for issue of payment.**
25. After opening the envelope containing the offer on the standardized conditions and opening of the priced tender, no correspondence will be entertained.
- 26. Incomplete tenders shall be rejected and no further communication in this regard will be entertained.**
27. **Indian Bank has the right to accept / reject any or all tenders without assigning any reasons whatsoever.**
28. The tenders shall remain open for acceptance by the bank for a period of 90 days from the date of opening of the second cover containing the priced tender.
29. The tenderer must use only the Tender forms / documents issued by the bank. If given space falls short for furnishing the information's, separate sheets may be added duly signed by the contractors.
- 30. Each page of the tender document must be signed by the contractor.**
31. The Tender submitted on behalf of a Firm shall be signed by all the Partners of the Firm or by a Partner who has the necessary authority on behalf of the Firm to enter into the proposed contract otherwise the Tender may be rejected by the Owners.
32. The Contractor shall not assign the contract. He shall not sublet any portion of the Contract except with the written consent of the bank. In case of breach of these conditions, the bank may cause the Architect to serve a notice in writing on the Contractor rescinding the Contract where upon the Security Deposit shall stand forfeited to the bank, without prejudice to his other remedies against the Contractor.
33. The Contractor shall carry out all the work strictly in accordance with Drawings, details and instructions of the Architect/Bank. If changes have to be made in the design. The same will be done with the prior approval in writing of the bank/ Architect. Contractor shall carry out the same without any extra charge. The Bank's decision in such cases shall be final and shall not be open to arbitration.

34. A Schedule of Probable Quantities in respect of each work and specifications accompany these special conditions. The schedule of Probable Quantities is liable to alteration by omissions, deductions or additions at the discretion of the Architect. Each Tender should contain not only the rates but also the value of each item of work entered in a separate column and all the items should be totalled in order to show the aggregate value of the entire Tender.
35. The Tenderer must obtain for himself on his own and at his own expenses all the information which may be necessary for the purpose of making a Tender and for entering into a Contract and must inspect the site of the work and acquaint himself with all local conditions, means of access to the work, nature of the work and all matters appertaining there to.
36. The successful tenderer should make his own arrangements to store all the materials required for the work. No advance against materials purchased and brought at site will be made. The contractor will have to keep the materials at site under their safe custody and at their risk and cost. The Bank/ Owners of premises are not responsible for damages and losses of such materials brought at site.
37. Contractors are requested to note that no extra item or deviated item of work to be executed without taking prior permission from Bank/Architects, if the extra item or deviated item of work is executed without taking prior permission, Bank shall not be held responsible for the payment of such works executed.
38. Work should be executed only at the site under the supervision of a competent supervisor with strict quality control & workmanship Bank/ Architects may inspect the work during its execution at site.
39. No deviation in the specification and make would be acceptable.
40. All furniture such as counters, tables, etc. shall be computer compatible and shall have key board tray, CPU stand, etc.
41. The names of partners of the contractor's firm to be mentioned below :  
(i) \_\_\_\_\_ (ii) \_\_\_\_\_ (iii) \_\_\_\_\_
42. Name of the partner of the firm authorized to sign Or Name of person having Power of Attorney to sign the Contract.  
(Certified true copy of the Power of attorney should be attached)
43. The contractors are advised to inspect the drawings available with the Bank before submitting the Tender.
44. I/We are the empanelled Bank's contractors / firms. (letter enclosed)
45. There must be submission of "Single Line Diagram" for electric works and "As built" drawings in original (3 sets) should be a mandatory criteria before releasing final payments to contractor.

I / We hereby declare that I / We have read and understood the above instructions for the guidance of Tenderers.

Date:  
Place:  
Contractor

Signature, Seal and address of



**BILL OF QUANTITIES FOR THE INTERIOR, ELECTRICAL WORK AT INDIAN BANK TOLLYGANGE BRANCH**

All concealed faces of Plywood and frame work shall be finished with one coat of wood preservative paint.  
 All exposed faces of beading are to be polished / stained to the satisfaction of the engineer in charge.  
 All Wood / Ply Wood used shall be Termite Resistant or shall be provided with Anti- Termite Treatment.  
 The inner side of the unit finished with 1 Coat of Wood Primer and 2 coats of Enamel Paint to the satisfaction of the engineer in charge.  
 All relevant hardware required for the fabrication of each item of work comprising of, but not limited to the hinges, locking arrangements, S.S  
 All positions of Partitions / Furniture shall be marked at site for Architect's approval. The work shall taken up only after receiving the clearance  
 All of material, colour, texture, shade and pattern shall be used in the project only after the approval of the samples by the Architects.  
 Wood sizes given in the schedule are the finished sizes after planing.  
 Any discrepancy in the drawings and specifications or any variation of the available measurements on site from that of the drawings shall be  
 The Full Height Partitions shall be erected 75 mm above the adjoining highest False Ceiling Level. However, only the exposed surface shall be  
 All level differences and provisions for coves shall be made as per the drawings. However, only vertical drops of 100 mm shall be measured for  
 All the Exposed Edges Glass shall be buffed and polished.  
 The lines and levels are of utmost importance and care shall be taken to match them appropriately.

Sl. No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
<b>A</b>	<b>PARTITIONS</b>				
<b>1</b>	<b>Entrance Partition (with Twin Style Frame)</b>	<b>Sq. Ft.</b>	<b>49.00</b>		
	Providing & fixing in position fully glazed entrance partition upto 7 feet height using 12 mm thick Toughened Glass of approved make, with 3-3/4" x 1-1/2" powder coated aluminium Twin Style door frame section at the top and bottom. Over and above 7 feet height, Non-Glazed Plywood Partition or Aluminium Composite Partition shall be made, as instructed (This shall be measured separately in relevant item elsewhere). The rates to be quoted inclusive of all the fittings and other accessories. Silicon Sealant shall be applied between the glass panel to make it absolutely water tight.				
<b>2</b>	<b>Non-Glazed/SOLID Plywood Partition</b>	<b>Sq. Ft</b>	<b>240.00</b>		
	Providing & fixing in position double skinned laminated partition between Banking Hall and Back Office. The partition is to be made with 6 mm plywood covered with 1 mm thick laminate, fixed on framework made of 18 mm thick 710 Grade (BWP) plywood frame (horizontal and vertical) of 50mm width. Spacing of verticals should not be more than 450mm (1'-6"). Necessary holes must be made in the frame sections to run the wires, computer cables wherever necessary. Similarly, necessary cuttings to be made in the plywood surface to fix switch boxes of electrical, telephone sockets, computer information outlets etc. Additional provisions for fixing Flush Doors (measured separately) shall be made where ever necessary.				
	(The partition shall be erected upto 3" above the False Ceiling Level and the supports shall be anchored firmly to the RCC roof. However, only the exposed area below the False Ceiling shall be considered for payment).				

<b>4</b>	<b>Composite Partition (one side plywood and one side gypsum)</b>	<b>Sq. Ft</b>	<b>0.00</b>		
	Providing & fixing composite partitions as per design with 1.0 mm thick G.I. sections of size 50 mm x 32, provided at not more than 600 mm c/c and covered on one side with 6 mm thick 710 Grade (BWP) Plywood and the other side with 12.5 mm thick gypsum board using self drilling screws between banking hall and back office area, etc. The partition should withstand its weight. The plywood surface shall be finished with 1mm thick laminate and the Joints between the Gypsum board shall be fixed with fiberglass joint mesh and finished with putty. Provision for flush doors shall be considered wherever required. Additional stiffeners using 18 mm thick 710 Grade (BWP) plywood shall be made for fixing flush shutters.				
	(The partition shall be erected upto 3" above the False Ceiling Level and the supports shall be anchored firmly to the RCC roof for support. However, only the exposed area below the False Ceiling shall be considered for payment. The portion above the False Ceiling Level shall be measured as Paneling with Gypsum board).				
<b>6</b>	<b>Manager Cabin Partition - Partially glazed / GLAZED</b>	<b>Sq. Ft</b>	<b>172.00</b>		
	Providing & fixing in position partly glazed, partly double skinned, laminated partition for Manager Cabin. The partition shall be made using a framework made of 18 mm thk 710 Grade (BWP) Plywood @ 450mm x 450 mm Grid, sandwiched by 6mm 710 grade (BWP) plywood & 1mm thick laminate of approved colour with wooden lippings for inserting glass. Between 1' and 7' plain glass of 8 mm thickness shall be used. (as specified in the 2D). The rate shall also include a Fully Glazed Flush Door with 8 mm thick plain glass of size 3'-0" x 7'-0" at the front and a Partly Glazed Flush Door with 5 mm thick plain glass of size 2'-6" x 7'-0" at the side / rear as per design, with necessary fittings such as hinges, handles, lock, door closer etc complete.				
	(The partition shall be erected upto 3" above the False Ceiling Level and the supports shall be anchored firmly to the RCC roof. However, only the exposed area below the False Ceiling shall be considered for payment. The exposed portion, if any, above the lowest False Ceiling Level shall be measured as Paneling with Laminated Plywood).				

7	<b>Cash Cabin Partition</b>	Sq. Ft.	158.00		
	Providing & fixing in position partly glazed, partly double skinned, laminated partition for Cash Cabin. The partition shall be made using a framework made of 18 mm thk 710 Grade (BWP) Plywood @ 450mm x 450 mm Grid, sandwiched by 6mm 710 grade plywood & 1mm thick laminate of approved colour with wooden lippings for inserting glass for at total height of 6'-9". At sides other than the front, 8 mm thick Clear Glass shall be provided from 3'-6" upto 6'-0" with a 2" wide voice gap at 4'-6" from FFL. A cheque passing tray shall be provided between cash officer & cash counter. The front side shall be provided with 10 mm thick Toughened Glass fixed to the partition using SS D-Brackets, with a 2" wide Voice Gap at 4'-6". The lower portion of the toughened glass shall have a Transaction Hole of 6" x 6". Skirting (4") in Cardinal Red shall be provided along the perimeter of the partitions (outside). The rate shall also include a Partly Glazed Flush Door with 5 mm thick plain glass of size 2'-6" x 7'-0" at the side / etween the Gypsum board shall be fixed with fiberglass joint mesh and finished with putty.dge polished and fixed to the surface using clear adhesive. wder coated aluminium deco grill on top. Cash transaction hole to be provided with movable shutter with sticker reading 'CLOSED'.				
	(Only the portion above the Top Ledge of the Cash Counter on the front face shall be measured in this item.)				
	Door size: 2'6"x6'6"				
8	<b>Low Height Partition</b>	Sq. Ft.	48.00		
	Providing & fixing in position double skinned laminated partition of 7'/4'-0" height. The partition is to be made with 6 mm plywood covered with 1 mm thick laminate is fixed on framework made of 18 mm thick 710 Grade (BWP) plywood frame (horizontal and vertical) of 50mm width. Spacing of framework shall not be more than 450mm (1'-6").				
B	<b>DOORS</b>				
9.a	<b>Entrance Door (Double Shuttered with Twin Style Frame)</b>	Sq. Ft.	0.00		
	Providing & fixing in position fully glazed entrance door with 12 mm thk Toughened Glass of approved make, with 3-3/4" x1-1/2" powder coated aluminium Twin Style door frame section at the top and bottom. The door is to be mounted on floor spring. Over and above 7'-0" height, Non-Glazed Plywood Partition or Aluminium Composite Partition shall be made as instructed (This shall be measured seperately in relevent item elsewhere). The door shall be double shuttered with shutters being 2 no:s x 2'-6" x 7'-0", as per design with necessary fittings and accesseries like SS Handle and Glass to Glass Lock, connector for Floor Spring, etc, but excluding floor spring. (Floor Spring shall be measured seperately).				
	Size - 2 no:s x 2'-6" x 7'-0"				

9.b	<b>Entrance Door (Single Shuttered with Twin Style Frame)</b>	Sq. Ft.	24.00		
	Providing & fixing in position fully glazed entrance door with 12 mm thk Toughened Glass of approved make, with 3-3/4" x1-1/2" powder coated aluminium Twin Style door frame section at the top and bottom. The door is to be mounted on floor spring. Over and above 7'-0" height, Non-Glazed Plywood Partition or Aluminium Composite Partition shall be made as instructed (This shall be measured seperately in relevent item elsewhere). The door shall be single shuttered with shutters being 3'-6" x 7'-0", as per design with necessary fittings and accesseries like SS Handle and Glass to Glass Lock, connector for Floor Spring, etc, but excluding floor spring. (Floor Spring shall be measured seperately).				
	Size - 3'-6" x 7'-0"				
10	<b>Flush Door in Partitions (Both Side Laminated)</b>				
	Providing and fixing 40mm thick Flush Door using frame work made of 18 mm thick 710 Grade (BWP) Plywood, sandwiched with 6 mm thick 710 Grade (BWP) Plywood and both sides finished with 1 mm thick Laminate of aproved colour and make. Vision Panel of 150 mm width shall be provided using 6 mm thick Plain Glass from 1'-0" upto 6'-0" of the door. The shutter shall be fixed to existing partition frame work using 4 no:s of 4" long heavy duty SS hinges. The rates to include mortise lock with SS handle, hinges, stopper, etc.				
a	Door Size : 75 cm x 210 cm	No:s			
b	Door Size : 85 cm x 210 cm	No:s	6.00		
11	<b>Flush Door in Partitions (One Side Laminated and One Side Painted)</b>				
	Providing and fixing 40mm thick Flush Door using frame work made of 18 mm thick 710 Grade (BWP) Plywood, sandwiched with 6 mm thick 710 Grade (BWP) Plywood. The side facing the Banking Hall shall be finished with 1 mm thick Laminate of aproved colour and make and the rear shall be finished with primer, putty and 2 coats of Enamel Paint. Vision Panel of 150 mm width shall be provided using 6 mmt thick Plain Glass from 1'-0" upto 6'-0" of the door. The shutter shall be fixed to existing partition frame work using 4 no:s of 4" long heavy duty SS hinges. The rates to include mortise lock with SS handle, hinges, stopper, etc.				
a	Door Size : 75 cm x 210 cm	No:s			
b	Door Size : 85 cm x 210 cm	No:s			

12	<b>Flush Door in Partitions (Both Sides Painted)</b>				
	Providing and fixing 40mm thick Flush Door using frame work made of 18 mm thick 710 Grade (BWP) Plywood, sandwiched with 6 mm thick 710 Grade (BWP) Plywood and finished with primer, putty and 2 coats of Enamel Paint. Vision Panel of 150 mm width shall be provided using 6 mm thick Plain Glass from 1'-0" upto 6'-0" of the door. The shutter shall be fixed to existing partition frame work using 4 no:s of 4" long heavy duty SS hinges. The rates to include mortise lock with SS handle, hinges, stopper, etc.				
a	Door Size : 75 cm x 210 cm	No:s			
b	Door Size : 85 cm x 210 cm	No:s			
13	<b>Aluminium Door in Locker Partition</b>	No:s			
	Providing and Fixing Aluminium Door with powder coated sections of 2-1/2"x1-1/2" on all sides and a horizontal section in the center with 8 mm 710 Grade (BWP) plywood finished with 1 mm thick laminate on both sides as top and bottom panel (To be provided in strong room partition). The rates to include hinges lock with powdercoated aluminium handle, stopper, etc.				
	Size - 3'-0"x7'-0"				
14	<b>Wicket Door</b>	Sq. Ft.	0.00		
	Providing and fixing wicket door with 18 mm 710 Grade (BWP) Plywood finished with 1mm laminate on both sides including all hardware..				
	Aprox. Size - 90 cm x 70 cm with one openable shutter as per design.				
	All edges to finished with edge banding. Door to be provided with SS Tower bolt.				
C	<b>PANELING AND BOXING</b>				
15	<b>Pillar and Wall Panelling</b>	Sq. Ft.	400.00		
	Column & Wall panelling with 2"x1" aluminum sections fixed to the surface at a maximum grid spacing of 2' x 2' and then covered with 6mm plywood and finished with 1mm thick laminate of approved make as per design. SS strips of 6 mm thicknes shall be provided horizontally on the laminate at every 2 feet. 4" skirting in Cardinal Red shall be provided along the perimeter of the pillars.				
	(The panelling shall be erected 3" above the False Ceiling Level. However, only exposed portions below the False Ceiling Level shall be considered for payment.)				
15.1	<b>SAME AS ABOVE BUT USE WITH ACP FOR ATM</b>	Sq. Ft.			

16	<b>Paneling with Gypsum Board</b>	Sq. Ft.			
	Providing & fixing gypsum board paneling over G.I. sections of size 50 mm x 32 mm or 710 Grade (BWP) plywood framework, as the case may be, provided at not more than 600 mm c/c, using self drilling screws for portion above false ceiling level upto the soffit of the slab (to close the gap) at back office area. The arrangement should withstand its weight. The Joints between the Gypsum board shall be fixed with fiberglass joint mesh and finished with putty.				
17.a	<b>Boxing for Rolling Shutter Drum (with plywood)</b>	Sq. Ft.	35.00		
	Providing and fixing enclosure to rolling shutter drum using 8 mm thick 710 Grade (BWP) plywood finished with 1 mm thick laminate over a framework using 2"x1" Aluminium sections at a grid spacing not exceeding 2'x2'. The box arrangement shall be anchored to the ceiling and walls in such a manner that the same can be removed for accessing the Rolling Shutter Drum. The rate to include all hardware and accessories, complete.				
17.b	<b>Boxing for Rolling Shutter Drum (with Aluminium Composite Panel)</b>	Sq. Ft.	0.00		
	Providing and fixing enclosure to rolling shutter drum using 4 mm thick Trafold Aluminium Composite Panel of approved make and colour over a framework using 2"x1" Aluminium sections at a grid spacing not exceeding 2'x4'. The box arrangement shall be anchored to the ceiling and walls in such a manner that the same can be removed for accessing the Rolling Shutter Drum. The rate to include all hardware, accessories and silicon sealent, complete.				

18	<b>Enclosure for Electrical Panels</b>	Sq. Ft.	38.00		
	Providing and fixing enclosure of 1'-6" depth, for covering electrical panel board, etc., with 16mm thick Cementitious Board. The edge of the enclosure shall be lined with 16 mm thick 710 Grade (BWP) plywood for a width of 4 ". Shutters of 16 mm thick 710 Grade (BWP) plywood shall be fixed to the plywood lining on the box using autoclosing hinges. The shutter shall be provided with aluminium powdercoated louvers of approved colour on 50% of its surface area. All external plywood surfaces shall be finished with 1mm thick laminate of approved shade and make and internal surface shall be painted with primer, putty and two coats of synthetic enamel paint. The surfaces of the cementitious board shall be painted using 2 coats of emulsion paint over primer. The rates to include autoclosing hinges, handles, ball catches, etc complete.				
	(Only the face area shall be measured for payment)				
D	<b>FURNITURE</b>				
19	<b>Manager Table</b>	No:s	1.00		
	Providing and fixing Manager table of 5'-6" length with 16 mm 710 grade (BWP) plywood finished with 1mm thick laminate with vertical groves at every 2'-0". The table top shall be at 2'-6" from the ground level & 3'-0" clear top width (or as per shape and size shown in drawing). An 8 mm thick black tinted glass shall be provided on table top as per shape. Table front to be fixed with 2 no:s of equally spaced SS divider strip (6 mm thick) horizontally. The front edge shall be finished with additional plywood (710 Grade) and laminate so as to form a combined thickness of 1.5", as per drawing. A sliding key board tray with mouse pad on sliders, three pullout drawer of width 40cm and a bottom rack for CPU shall be provided. Locks, SS handle, auto closing hinges & SS footrest (2" thick) shall be provided. All inside surface to be finished with Enamel Paint after priming and puttying. The table tops shall have provision for cable managers of approved shade. All edges should be edge profiled of approved colour.				
	Size : 6'-6"x3'-0"x2'-6"				

20	<b>Low Counter</b>	R.Ft.	18.00		
	<p>Providing and fixing Low Counter of 2'-6" width, to be done as per drawing with structure made of 16mm 710 Grade Plywood (BWP) finished with 1 mm thk Laminate approved colour &amp; design with vertical groves at every 2'-0". Table front to be fixed with 3 equally spaced SS divider strip (6 mm thick), horizontally as per the drawing. 4" skirting in Cardinal Red shall be provided along the perimeter of the counter (outside). A sliding key board tray on sliders, three pullout drawers of width 40cm on sliders and a bottom rack for CPU shall be provided. Locks, SS handle, auto closing hinges &amp; SS footrest (2" thick) shall be provided. All inside surface to be finished with Enamel Paint after priming and puttying. The table tops shall have provision for cable managers of approved shade. All edges should be edge profiled of aproved colour.</p>				
	Size - 4'-0"x2'-6"x2'-6"				
21	<b>High Counter</b>	R.Ft.	0.00		
	<p>Providing and fixing High Counter with 2'-6" wide staff working counter at 2'-6" height from FFL and 1'-0" wide customer ledge at 3'-6" height from FFL. The structure shall be made using 16mm 710 Grade Plywood (BWP) finished with 1 mm thk Laminate approved colour &amp; design with vertical groves at every 2'-0". Table front to be fixed with 3 equally spaced SS divider strip (6 mm thick), horizontaliy as per drawing. 4" skirting in Cardinal Red shall be provided along the perimeter of the counter (outside). A sliding key board tray on sliders, three pullout drawer of width 40cm and a bottom rack for CPU shall be provided. Locks, SS handle, auto closing hinges &amp; SS footrest (2" thick) shall be provided. All inside surface to be finished with Enamel Paint after priming and puttying. The table tops shall have provision for cable managers of approved shade. All edges should be edge profiled of aproved colour. The customer top @ 3'-6" ht (1' wide) shall be topped with 8mm thick tinted glass (black) with edge polisetween the Gypsum board shall be fixed with fiberg</p>				
	Size : 4'-0"x2'-6"x3'-6"				



22	Cash Counter	R/Ft	10.00		
	<p>Providing and fixing Cash Counter with 2'-6" wide staff working counter at 2'-6" height from FFL and 1'-6" wide customer ledge at 3'-6" height from FFL. The structure shall be made using 16mm 710 Grade Plywood (BWP) finished with 1 mm thk Laminate approved colour &amp; design with vertical groves at every 2'-0". Table front to be fixed with 3 equally spaced SS divider strip (6 mm thick), horizontally as per the drawing. 4" skirting in Cardinal Red shall be provided along the perimeter of the partitions (outside). A sliding key board tray on sliders, three pullout drawer on sliders of width 40cm and a bottom rack for CPU shall be provided. Locks, SS handle, auto closing hinges &amp; SS footrest (2" thick) shall be provided. All inside surface to be finished with Enamel Paint after priming and puttying. The table tops shall have provision for cable managers of approved shade. All edges should be edge profiled of approved colour. 4" skirting in Cardinal Red shall be provided along the bottom of counters. The custo between the Gypsum board shall be fixed with fiberglass joint mesh and finished with putty.dge polished and fixed to the surface using clear adhesive.</p>				
	Size : 5'-0"x2'-6"x3'-6"				

23	<b>Back Office Table</b>				
	Providing and fixing Back Office Table with 16 mm 710 grade (BWP) plywood finished with 1mm thick laminate with vertical groves at every 2'-0". The table top shall be at 2'-6" from the ground level & 2'-6" clear top width (or as per shape and size shown in drawing). Table front to be fixed with 3 nos SS divider strip (6 mm thick), horizontally, matching the lines of the running counter, as per the drawing. 4" skirting in Cardinal Red shall be provided along the perimeter of the counter (outside). The front edge shall be finished with additional plywood (710 Grade) and laminate so as to form a combined thickness of 1.5", as per drawing. A sliding key board tray with mouse pad on sliders, three pullout drawer of width 40cm and a bottom rack for CPU shall be provided. Locks, SS handle, auto closing hinges & SS footrest (2" thick) shall be provided. All inside surface to be finished with Enamel Paint after priming and puttying. The table tops shall have provision for cable managers of approved shade. All edgetween the Gypsum board shall be fixed with fi				
a	Size : 5'-0"x2'-6"x2'-6"	No:s			
b	Size : 4'-0"x2'-6"x2'-6"	No:s	1.00		
24	<b>Side Unit for Manager Table / Staff Counter</b>				
	Providing and fixing double shuttered Side Unit made of 16mm thick plywood 710 Grade (BWP) structure finished with 1mm laminate. The side unit shall consist of a pull out drawer of 250 mm height at the top and openable double shuttered storage unit with one rack inside at the bottom. All internal surfaces shall be finished with 2 coats of enamel paint after priming and puttying. The rate is to be inclusive of all harware like autoclosing hinges, SS handles, locks, complete.				
a	Size : 3'-6"x1'-6"x2'-6"	No:s	2.00		
b	Size : 3'-0"x1'-6"x2'-6"	No:s			
c	Size : 2'-6"x1'-6"x2'-6"	No:s			
25	<b>Low/FULL Height Storages</b>	SQFT	120.00		
	Providing and fixing Low Height Storage Unit for Manager Cabin and Banking Hall, of 1'-4" depth and 2'-6" height, made of 16mm thick plywood 710 Grade (BWP) structure finished with 1mm laminate. The side unit shall consist of a pull out drawer of 250 mm height at the top and sliding double shuttered storage unit with one rack inside at the bottom. All internal surfaces shall be finished with 2 coats of enamel paint after priming and puttying. The rate is to be inclusive of all harware like autoclosing hinges, SS handles, locks, complete.				
26.a	<b>Writing Ledge with Complaint / Suggestion Box (Mounted on Wall / Partition)</b>				
	Providing and fixing Writing Ledge of 1'-3" depth, 5'-0" / 3'-0" width and 1'-3" height mounted on wall, made of 16mm 710 Grade (BWP) plywood structure comprising of suitable intermediate vertical partitions to make compartments for placing leaflets. An 8mm thick tinted glass (black) with edge polished shall be fixed to the surface using clear adhesive. The back plywood panel shall continue further on the wall for a height of 4" beyond the glass top. Two sets of plywood boxes of size 0'-10"x0'-12"x0'-6" made of 16mm 710 Grade (BWP) plywoods shall be provided below the writing ledge on either sides for receiving complaints and suggestions. The Writing Ledge shall be fixed in such a way that the level of the Glass Top shall be at 4'-0" from FFL. All exterior surfaces shall be finished with 1mm thick laminate of approved shades and inside area finished with 2 coats of enamel paint after priming and puttying. The openable shutter on the front shall be provided with approved quality locks, handles etc. and slit (5"X1") on top for dropping complaints / suggestions.				
	Size : 5'-0"x2'-3"x1'3"	No:s	1.00		
	Size : 3'-6"x1'-3"x4'-0"	No:s			

26.b	<b>Writing Ledge with Cheque Drop Box / Complaint Box (Floor Standing)</b>	R.Ft.			
	Providing and fixing Writing Ledge of 1'-3" depth, 5'-0" / 3'-0" width and 4'-0" height mounted on floor, made of 16mm 710 Grade (BWP) plywood structure comprising of suitable intermediate vertical partitions to make compartments for placing leaflets. An 8mm thick tinted glass (black) with edge polished shall be fixed to the surface using clear adhesive. Two sets of plywood boxes of size 0'-10"x0'-12"x0'-6" made of 16mm 710 Grade (BWP) plywood shall be provided below the writing ledge on either sides for receiving complaints and suggestions. All exterior surfaces shall be finished with 1mm thick laminate of approved shades and inside area finished with 2 coats of enamel paint after priming and puttying. The openable shutter on the front shall be provided with approved quality locks, handles etc. and slit (5"X1") on top for dropping complaints / suggestions.				
	Size : 5'-0" x1'-3"x4'-0"	No:s			
	Size : 3'-6"x1'-3"x4'-0"	No:s			
26.c	<b>Writing Ledge (Mounted on Wall / Partition)</b>	R.Ft.	0.00		
	Providing and fixing Writing Ledge of 1'-3" depth, 5'-0" / 3'-0" width and 1'-3" height mounted on wall, made of 16mm 710 Grade (BWP) plywood structure comprising of suitable intermediate vertical partitions to make compartments for placing leaflets. An 8mm thick tinted glass (black) with edge polished shall be fixed to the surface using clear adhesive. The back plywood panel shall continue further on the wall for a height of 4" beyond the glass top. The Writing Ledge shall be fixed in such a way that the level of the Glass Top shall be at 4'-0" from FFL. All exterior surfaces shall be finished with 1mm thick laminate of approved shades and inside area finished with 2 coats of enamel paint after priming and puttying. The openable shutter on the front shall be provided with approved quality locks, handles etc. and slit (5"X1") on top for dropping complaints / suggestions.				
	Size : 5'-0" x1'-3"x4'-0"	No:s			
	Size : 3'-6"x1'-3"x4'-0"	No:s			
26.d	<b>Complaint Box / Cheque Drop Box</b>	No:s	1.00		
	Providing and fixing Complaint box with 16mm 710 grade (BWP) plywood .All exterior surfaces shall be finished with 1mm thick laminate of approved shades and inside area finished with 2 coats of enamel paint after priming and puttying. Provided with openable shutter on front with approved quality locks, handles etc. and slit (5"X1") on top for dropping complaints / suggestions.				
	Size- 10"x12"x6"				

27	Notice Board(pin up)	Sq. Ft.	30.00		
	Providing and fixing of notice board made of 12 mm thick Soft Board wrapped with red velvet coloured fabric, fixed on a backing of 6 mm thick 710 Grade (BWP) plywood. A frame of 6" width and 12 mm thickness in 710 Grade (BWP) plywood finished with 1 mm thick laminate shall be provided around the soft board at the perimeter, over the 6 mm thick plywood backing. The exposed thickness of the frame shall be provided with SS Strip of 19 mm width.				
	Rear surface of plywood to be applied with two coats of synthetic enamel paint. Size: 5'-0" x 4'-0"				
28	Dining Counter	R.Ft.			
	Providing and fixing dining counter with 16mm 710 grade plywood finished with 1mm thick laminte and fixed at wall/partition with necessary fittings.				
E	FALSE CEILING				
29	False ceiling (PAINT FINISH)	Sq. Ft.	840.00		
	Providing and fixing suspended false ceiling, which includes providing and fixing GI perimeter channels of size 0.55mm thick having one flange of 20mm and another flange of 30mm and a web of 27mm along the perimeter of ceiling, screw fixed to brick wall/partition with the help of nylon sleeves and screws at 610mm centers. The suspending GI intermediate channel of size 45mm, 0.9mm thick with two flanges of 15mm each from the soffit at 1220mm centers with ceiling angle of width 25mmx 10mmx 0.55mm thick fixed to soffit with GI cleat and steel expansion fastened. Ceiling section of 0.55mm thickness having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clips and in direction perpendicular to the intermediate channel at 457mm centers. 12.5mm tapered edge Gypboard (Conforming to IS- 2095-1982) is then screwed fixed to ceiling section with 25mm dry wall screw at 230mm centers. Screw fixing is done mechanically. The joints between the Gypsum board shall be fixed with fiberglass joint mesh and finished with putty.				
	Finally the boards are to be jointed and finished so as to have a flush look which includes filling as finishing the tapered and square edge of the boards with joining compound, paper tape and two coats of primer. Extra frame work for electrical fittings, and/or any other cutout, trap doors ( if any), wooden shadow battens (hollock wood black enamel painted-25x40mm) at wall peripheries and end. 12mm thick MDF board for pelmet etc. complete including opening to be made for AC grills, light fittings, trap doors etc. (The quoted rate shall be inclusive of suspenders at all heights)				
	Cove Lighting shall be made at no additional cost.				
29.1	24" X24" GRID CEILING	Sq. Ft.	480.00		
	24"x24" Grid False Ceiling ( SILHOUTE GRID ): Providing and Fixing False ceiling Grid using hot dipped Galvonised steel sections, exposed surface chemically cleaned capping pre-finished in baked polyster paint. Main tee of size 3000 x 32 x 24 mm at every 1200mm c/c maximum, 1200mm cross Tee of size 1200 x 27 x 24mm at every 600mm intervals and 600 mm cross Tee of size 600 x 25 x 24mm at every 1200mm max and 3000 x 19 x 19mm wall angle all around the wall to form grid size of 600mm x 600mm . The Main grid to be suspended to the MS frame with 2mm pre-straightened GI wire and GI adjustable clamp and Laying of fibre wool board having Fire rating of 60 min. as per BS 476/ 23 of 1987 , Noise reduction co-eff. ( NRC ) of 0.50, Light reflectance of 83%, Sound attenuation of 32db, thermal conductivity of k=0.052 W/m, wt of 4kgs/ mts and humidity resistance of RH-95 , with paint finish of 600x600mm x 12mm thick over the Grid. All as per the design and instructions Archlitects.				
F	PAINTING WORKS				
30	Painting with Putty	Sq. Ft.	3000.00		

	Providing and Applying two or more coats of Emulsion Paint over 2 coats of putty and 2 coats of primer of approved make over internal walls and ceilings of banking hall and manager cabin. Appropriate surface preparation shall be carried out as per the company specification.				
	<b>MISCELLANEOUS WORKS</b>				
31	<b>Glass Dividers for Counters</b>	SQFT	0.00		
	Providing and Fixing free standing dividers using 12 mm thick Toughened Glass of size 3'-3"x2'-0", above the Table Top. The glass shall be fixed using 3 nos of heavy duty table top glass partition clamps. The free corners of the glass shall be curved with a radius of 1" and the edges shall be polished. Stickers / Frosting shall be carried out on glass as instructed.				
	Size-				
32	<b>Glass Banner with Bank's Name and Logo</b>	Sq. Ft.	0.00		
	Providing and Fixing Banner using 12 mm thick Toughened Glass fixed on SS Studs of 1" diameter and 1" spacing. The banner shall be stickered with Bank's name and Logo, at the designated proportions at the front surface and with frosted film at the back surface.				
	size - 3'-0" x 2'-0"				
	Make				
	12 mm thick Toughened Glass - Saint Gobain				
33	<b>Floor Spring for Single Shuttered Glass Doors</b>	No:s	2.00		
	Providing and Fixing of Heavy Duty Floor Spring for Single Shuttered Glass Doors either on Twin Style Aluminium frame or on Patch Fittings.				
	for Single Shuttered Glass Door of size 3'-0" x 7'-0"				
	Make				
	Floor Spring - Hafele - 932.79.030				
34	<b>Floor Spring for Double Shuttered Glass Doors</b>	No:s			
	Providing and Fixing of Heavy Duty Floor Spring for Double Shuttered Glass Doors either on Twin Style Aluminium frame or on Patch Fittings.				
	for Double Shuttered Glass Door of size 2'-6" x 7'-0" each				
	Make				
	Floor Spring - Hafele - 932.79.020				
35	<b>Door Closer for Flush Doors</b>	No:s	5.00		
	Providing and Fixing of Door Closers for Flush Doors.				
	Make				
	Door Closer with Hold Open Arm - Hafele - 932.84.759				
36	<b>Vertical blinds</b>	Sq. Ft.	160.00		
	Providing and fixing of VISTA make vertical blinds with synthetic fabric strips. The top rail shall be made of powder coated aluminium section with best quality sliding arrangement. Colour of vertical blinds shall be light shade matching with the light laminate (Colorado Pine (489- Light))				
	Make				
	Blinds - Vista				
37	<b>Line sticker work on glass</b>	Sq. Ft.	80.00		
	Providing and Fixing Sticker work on front entrance glass partition.				
38	<b>Bank's Logo Work on Main Door</b>	Sq. Ft.	52.50		
	Providing and Fixing Bank's Logo on front entrance glass door.				
2	<b>Brick Work</b>				
1	Providing and erecting 4 1/2" thk, Single brick wall (first class bricks) in cement and Coarse Sand mortar 1:3 with flush joint complete with material, labour, scaffolding, curing etc. The rate to include RCC stiffner at every 1 metre intervals in 1:2:4 concrete. (Excluding plastering). The work to include cost for lintels / cills in RCC required for Doors , windows, openings etc. INCLUDING plaster.	Sq. ft	192.00		