

Zonal Office Bahraich

NOTICE INVITING TENDER

Sub: COMPETITIVE QUOTATION FOR CIVIL WORK OF STRONG ROOM AT HARIHARPUR RANI BRANCH NEW PREMISES AT NAVEEN MANDI STHAL BHINGA, DISTT- SHRAWASTI

Competitive Sealed Quotations are invited in the prescribed format from the Contractors who are already empanelled with Bank executed civil work (having civil Works License) of Nationalized Banks in last three years.

Format of Quotation Document is enclosed for submission of civil work of strong room at Hariharpur Rani Branch new premises at Naveen Mandi Sthal Bhinga, Distt. Shrawasti .Full details and tender documents are available on Bank's website: www.indianbank.in or can be obtained from Zonal Office, Bahraich Dully filled in tenders should be submitted as per following schedule:

1	Issue of Tender Document	From 02.12.2024 to 17.12.2024
2	Submission of Tender	On or before 17.12.2024 up to 05:00 PM
3	Opening of Tender	On 18.12.2024 at 03:00 PM
4	Date of Commencement	7 Days from the date of issue of letter awarding the job.
5	Time of Completion	20 days
6	Defect Liability Period	12 Months
7	Earnest Money	Rs.5000/- in the form of DD/IOI in favour of Indian Bank payable at Bahraich.
8	Liquidated Damages for delay	Rs.2000/- per day subject to Max. of 10% of total accepted contract amount. (If the work is not completed to the satisfaction of the Employer within the stipulated period, the contractor shall be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.)
9	Payment Terms	Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period.
10	Documents to be attached with the Bill	Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.
11.	Retention Money	10% (Including Earnest Money)

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tender without assigning any reason whatsoever. Late/delayed tender shall not be accepted after due date and time of submission of tender.

(Assistant General Manager)

[Handwritten signature]



CLIENT

INDIAN BANK

ZONAL OFFICE, Bahraich - PREMISES DEPARTMENT
114, Raipur Raja
Jail Road, bahraich
Uttar Pradesh- 271801

WORK / PROJECT

PROPOSED CIVIL WORK OF STRONG ROOM AT INDIAN BANK, HARIHARPUR RANI
BRANCH NEW PREMISES AT NAVEEN MANDI STHAL BHINGA, DISTT. SHRAWASTI

COMPETITIVE QUOTATION

FOR INTERIOR FURNISHING, ELECTRICALS WORK AND DATA NETWORK CABLEING AT
ABOVE PROJECT

Tender Issued to:

M/S _____

Address _____


Contact No: _____

Tender Issued on: _____

Last Date of Submission: _____

Signature of the Contractor

Seal



Zonal Office Bahraich

NOTICE INVITING COMPETITIVE QUOTATION

Work: COMPETITIVE QUOTATION FOR CIVIL WORK OF STRONG ROOM AT HARIHARPUR RANI BRANCH NEW PREMISES AT NAVEEN MANDI STHAL BHINGA, DISTT-SHRAWASTI UNDER BAHRAICH ZONE

General terms & Conditions:-

- 1) Sealed quotation should be addressed to The AGM, Indian Bank, Zonal Office, Bahraich and super scribed name of civil work of strong room at Hariharpur Rani Branch new premises at Naveen Mandi sthal Bhinga, Distt - Shrawasti **and should reach before 5:00 p.m. on 17.12.2024 at Zonal Office Bahraich.**

Mailing Address:

INDIAN BANK

ZONAL OFFICE, Bahraich - PREMISES DEPARTMENT

114, Raipur Raja

Jail Road, Bahraich

Uttar Pradesh- 271801

- 2) No quotation will be accepted after 5:00 pm on 17.12.2024 and quotations will be opened on 18.12.2024 at 3:00 pm unless otherwise informed.
- 3) The quotations will remain valid for a period of 3 months from the date of opening.
- 4) Bank reserves the right to accept or reject any or all the quotations accept part of any tender, entrust the entire work to any contractor or divide the work to more than one contractor (item wise) without assigning any reason to do so or giving any explanation. The rates quoted by the contractors will help well for bifurcation and no compensation will be paid on this account.
- 5) At the time of submission every quotation must be accompanied by IOI/ Demand Draft for an amount of Rs.5000/- in favour of INDIAN BANK payable at Bahraich towards EMD. Any quotation which is not accompanied by EMD will be summarily rejected.
- 6) Contract should quote rates in figures as well as in words.
- 7) All erasures and alterations made must be attested with the initials of tenderers. No overwriting is permitted.
- 8) The EMD of the unsuccessful bidders will be returned within 45 days from the date of opening the tender.
- 9) Joint tenders shall not be considered. Conditional tenders quoted by the contractor are liable to be rejected.
- 10) No escalation in the rates will be allowed under any circumstances.
- 11) On receipt of the intimation from the bank of the acceptance of his quotation, the contractor should submit his acceptance within 3 days. If the successful contractor/ tenderer fail to undertake the work within 7 days after work allotment, the EMD will be forfeited and acceptance of his tender may be withdrawn.
- 12) The rate quoted in the tenders shall be inclusive of all materials as required and shall be inclusive of all charges of scaffoldings, lifting, tools and plants, freights/ transportation, labour conditions and fluctuations in rates of excise duty, octroi,

GST, VAT, Excise Duty, service tax and any other taxes or expenditure of carrying out the works.

- 13) The Agency is advised to inspect and examine the sites and satisfy himself as to the condition prevailing at sites and its surrounding extent of work, scope and conditions under which the work is to be executed. The contractor shall also satisfy himself about the accessibility to the premises.
- 14) The agency shall submit the offer which satisfies each and every condition laid down in this notice, failing which the tender will be liable to be rejected. Conditional bids shall not be considered and will be out rightly rejected in the very first instance.
- 15) Work will be completed within the period of 20 days from the date of issue of tender or work order whichever is earlier. If the work be not completed to the satisfaction of employer within the stipulated period, the contractor will be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of Max 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date. The contract may be rescind by giving one week notice incase work is not executed as per specification and as per time schedule given in tender document.
- 16) The liquidated damages as mentioned in the Notice inviting tender may not be enforced if the contractor applies for extension of time mentioning the genuine reasons for extension. If an extension of time of completion of the work is sought on the grounds of having unavoidable hindrances in its execution or any other ground, the contractor shall apply in writing to the Assistant General Manager, Zonal Office, Bahraich with full details of the circumstances which is causing such an extension. Extension of time in days will be granted by the bank if it is proved that the contractor is not at fault for extending the work beyond stipulated date of completion. All the decisions in this regard taken by the Bank shall be binding to the contractor.
- 17) The successful contractor is bound to carry item of work necessary for completion of job even though the same are not included in the schedule of quantity. Rates of extra item will be derived from quotation. In case the rates do not exist in quotation and extra item is not similar to the quoted item, then the rates will be worked out on actual cost of material and labor, any other expenditure for completing that work plus 15% towards contractors profit and overheads.
- 18) The work shall be carried out in such a way that, there is least disturbance to the staff of Bank. Contractors are required to organize the work in such a way that workings of staff and officers/executives of Office are not affected. Contractor is required to take adequate care during progress of work to protect belongings. In case any damage, contractors at their own cost shall make the same good.
- 19) The contractor must co-operate with other contractors appointed by the bank so that entire work shall proceed smoothly and to the complete satisfaction of the Bank.
- 20) Contractor will arrange necessary tools and plants for completing own work at their cost. In case of any accident the total responsibility will be on the contractor. Contractors are required to submit time schedule of work. After completion of work, cleaning of floors, walls etc are to be done on daily basis to the satisfaction of Branch Head / engineer-in-charge. After completion of jobs, the site shall be cleared of all rubbish malba /debris etc in all respect and handover the site in proper manner on completion of the work.
- 21) No advance will be paid. Payment will be released on satisfactory completion of job and submission of bills. Retention Money @10% will be deducted from the bill and to be released after twelve months from the date of virtual completion provided no defects is observed during the period.

- 22) In case of non-completion or delay in completion of work or removal of defects in time, the bank shall be free to appoint another agency to get the job done at contractors risk and cost.
- 23) The contractor will attend to all the defects noticed during defect liability period. If the contractor fails to attend the defects these defects will be got rectified by the bank and the expenditure incurred on this account will be recovered from security deposit / retention money.
- 24) The work shall be got approved by the Architect / engineer and the contractor shall rectify any bad workmanship pointed out at any stage and remove from the site all the rejected materials immediately at his own cost.
- 25) The contractor shall acquaint himself with the site conditions making his own arrangements for storing of materials at site, lift, cartage etc. at his own risk and safety.
- 26) The contractor shall make adequate arrangement for watch and ward of material and shall ensure the safety, breakage and any theft of material fixed or unfixed by him or the other sub contractors. The bank shall not be liable for any sort of loss incurred.
- 27) The contractor shall be responsible for application of labor laws, compensation for injury and accident to person, whether employed by him or his sub-contractor.
- 28) The contractor shall ensure that the workmen employed by him for the execution of work are suitably covered against Workmen Compensation Act and that all liabilities arising out of Workmen's compensation Act, ESIS and other legislative enactment applicable to such works and workmen shall be to the contractor's account and responsibility.
- 29) Civil, ELECTRICALS WORK and Electrical Works will be carried out as per Bank's standard drawing / specifications and to the entire satisfaction of the bank.
- 30) The contractor shall inform the bank, well in time, to check measurements of any work, which is likely to be hidden before covering.
- 31) Income tax at the prevailing rates will be deducted at source from contractor's bill and will be deposited with I.T.O. as per rules.
- 32) Any extra work or item can only be started by contractor after obtaining written approval from the Zonal Office. Item executed without prior approval from the Zonal Office will not be considered for payment.
- 33) The quantities mentioned in the schedule of quantities are approximate. Payment will be made on the actual work done by the contractor. However the contractor should not deviate the quantity without Banks permission.
- 34) The Bank has the right to alter the nature of work and to add or omit any items of work or to have the option of the same carried out departmentally or otherwise and such alterations or variations shall be carried out without prejudices to the contract.
- 35) The Bank has the right to terminate the contract if the contractor abandons the work or fails to commence the work in time, or fails to abide by the terms & conditions of the contract.

I have read and understood all the instructions/conditions given above and I have taken into account the above instructions/conditions while quoting the rates.

(SIGNATURE OF THE CONTRACTOR)

Date:

Place: BAHRAICH

SEAL

Seal & Signature of Contractor

Mohit & Associates.

Architects, Interiors .Estimators

L-2/554-, Vineet Khand, Gomti Nagar, Lucknow.

Phone.742821765,9582218092

E-Mail: mohitg.gupta2783@gmail.com

BOQ FOR CIVILWORK FOR INDIAN BANK BRANCH AT HARIHER PUR RANI AT MANDI SUMMITI BUILDING -BHINGA-DISTRICT SHRAVASTI (UP)

S.NO	DESCRIPTION	QTY.	UNIT	RATE (Rs.)	AMT (Rs.)
A	STRONG ROOM CIVIL WORKS				
1	Dismantling 6" thk, brick wall carefully by using chisel to cut & making good wall edges with 1:4 cement plaster including removal of debris from site.	150.00	S.F.T.		
2	Specification same as above but for 9" thk and above Brick walls.	20.00	C.F.T.		
3	Dismantling and removing doors and windows wherever required in a manner which facilitates easy fixing of new doors and windows without undue expense. the rate shall include removal of debris from site.	3.00	NOS.		
4	Dismantling marble, granite, kota, marble mosaic, ceramic tile flooring & dado including skirting and excavation up to 6" in plinth wherever required, etc. In a manner which facilitates laying of new flooring without undue extra expense. The rate shall include removal of debris from site.	130.00	S.F.T.		
1	RCC WALL WITH PLASTER FINISH ON BOTH SIDES	500	C.F.T.		
	Constructing RCC Wall in 1:1.5:3 mix (M20) concrete of required thickness as per the structural design. All RCC works should be machine mixed and vibrated, clear cover provided for reinforcement. The Rate shall include plastering with ¾" thk. 1:4 cement plaster on both the sides. The rate shall be inclusive of any scaffolding required, curing etc. Complete.				
2	RCC FLOORING	140	C.F.T.		
	Constructing RCC Flooring in 1:1.5:3 mix (M20) concrete of required thickness as per the structural design. All RCC works should be machine mixed and vibrated, clear cover provided for reinforcement. The rate shall be inclusive of any scaffolding required, curing etc. Complete.				
3	STEEL REINFORCEMENT FOR ALL RCC WORKS	1,200.00	Kgs		
	Providing and Fixing Structural Steel Reinforcement as per the structural details for the slabs, beams, walls, lintels, staircases etc. including shuttering, binding etc. complete in all respect				
4	MS GRILL FOR CEILING OF STRONG ROOM	130	S.FT		
	Providing and fixing MS grills for ceiling of Strong room using 20 mm MS Square Bars @ 75 mm c/c as per design given. The edges to be supported on IS angle 25mmx25mmx3mm on all sides. The side angles to be fixed to the walls firmly with anchor bolts. The rate is inclusive of 2 coats of Antirust paint.				
5	VITRIFIED TILES FLOORING				
a	600mm x 600mm type (approx.)	130	S.FT		

	Providing and fixing VITRIFIED Tiles of approved make, shade and pattern as shown in the drwng. / as aproved by Bank/ Architect. In CM 1:4 in proper line and level with out spacers for maintaining the grid lines. Rate shall be inclusive of providing and laying necessary PCC and Cement Mortar for a thickness of 3" and joint filling compound of the same shade of the tiles and including pop covering on the new flooring for the protection of tiles with base covering plastic.				
B	OTHER CIVIL WORKS				
1	ROLLING SHUTTER BRANCH				
	NEW SHUTTERS (WITH RED OXIDE & PAINT FINISH)				
a	USING 18 GAUGE SHEETS	80	S.FT		
b	USING 22 GAUGE SHEETS	0	S.FT		
2	Providing & fixing M. S. Rolling shutters (18/22 gauge sheets) for the facade openings (middle 1/3rd grill). Rate shall include all necessary locking arrangements. 2 coats of anti rust paint to be provided for the shutters.				
3	M.S.COLLAPSIBLE GATE FOR BRANCH	50.00	S.FT		
	Providing and Fixing MS Collapsible Gate Single shutter made out of vertical double channels 12mmx8mm x 3mm at maximum 125 mm apart when fully stretched as specified, braced with flat iron diagonals 12 mm x 5 mm as specified in the item. The top and bottom rails shall be of M.S. section 25mm x 25mm x 6mm with 25 mm dia rollers in every fourth double channels.				
	the outer surface of opening; the M.S. section at top shall be replaced by M.S. flat 40mm x 10mm. The necessary fittings such as bolts, nuts, locking arrangements, stoppers, handles, etc. shall be provided. The gates shall open and close smoothly and easily. T-iron rails shall be fixed to the lintel and floor with masonry nails embedded in cement concrete of lintel and floors at suitable spacing. The bottom runner shall be embedded with floor and proper groove formed and the floor shall be made good to match the rest of the flooring. At the sides, the end double channels shall be fixed with T-iron rails and also by holdfasts 200mm x 40mm x 4 mm bolted at one end to the end double channels and in the masonry in cement concrete 1:2:4 (nominal mix) blocks of size 115 mm x 75 mm x 230 mm, 3 nos. each side. The side masonry shall be made good to match the rest of the masonry finish. Two coats of anti rusting paint to be provided to the gate.				
4	ENAMEL PAINT	150	S.FT.		
	Providing & applying 1 st quality oil paint of approved make, quality & shade. The rate shall include scrapping, levelling & preparing the surface with primer quote.				
5	OBD PAINT INTERNAL AREA	400	S.FT.		
	Providing & applying OBD paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make, quality & finish shall be provided.				
	Total Rs				