



Zonal Office Tiruppur
2nd Floor KRBS Towers PN Road Tiruppur
Email: ZOTiruppur@indianbank.co.in

NOTICE INVITING QUOTATION

Indian Bank, Zonal Office Tiruppur invites sealed quotes for Interior Work for the proposed space for setting up MCB Namakkal Branch at 119 B Aarthi Complex Salem Road, Namakkal.

Quotation document may be downloaded from Indian Bank website from 30.01.2025.

RFQ Issue date : 30.01.2025
RFQ Closing date : 03.02.2025 12.00 PM




Zonal Manager



S.No	Description	Unit	QTY	Rate	Amount
1	<p>FALSE CEILING (Gypsum Board)</p> <p>Providing and fixing suspended false ceiling, which includes providing and fixing G.I. Perimeter channels of size 0.55mm tk having one flange of 20mm and another flange of 30mm and a web of 27mm along with perimeter of ceiling, screw fixed to brick wall / partition with the help of nylon sleeves and screw at 610 mm centres. Then suspending G.I. Intermediate channels of size 45mm, 0.9mm thick with two flanges of 15mm each from the soffit at 1.22 mts centre to centre with ceiling angle of width 25mm x 10mm x 0.5mm tk fixed to soffit G.I. clean and steel expansion fasteners. Ceiling section of 0.55mm thickness having knurled web of 51.5mm and two flanges 26mm each with clips of 10.5mm are then fixed to the intermediate channel with the help of connecting clips and in direction perpendicular to the intermediate channel at 457mm centre to centre. 12.5mm tapered edge Star Brand / India Gypsum Gypboard (conforming to IS-2095-1982) is then screw fixed to ceiling sections with 25mm dry wall screws at 230mm centres. Screw fixing is done mechanically either with screwdriver or drilling machine with suitable attachment. Finally the boards Properly finished with topcoat as per Architect direction.</p> <p>(This includes painting)</p> <p>a.) BM cabin b.) Customer waiting & workstation area</p>	Sq.ft Sq.ft	100 300		
1.1	<p>FALSE CEILING (Armstrong)</p> <p>Providing & fixing in position false ceiling in Armstrong 600 x 600mm x 15/16 mm Dune supreme RH 99 Prima tile with tegular edge frame work as specified by Armstrong co. with suspends wherever required. Making necessary framework for A.C ducting, if any, and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level, including making grooves and trap doors for A.C unit in 18 mm thick M.R grade plywood with Stainless steel hinges & locks with moulding 1" x 1" for edges including finishing with white plastic emulsion paint etc.complete in all respects.</p> <p>(Note: - Only the plan area will be measured for payment. No payment will be made for cutouts, grooves, mouldings etc.)</p> <p>a.) BM cabin b.) Customer waiting & workstation area</p>	Sq.ft Sq.ft	150 660		
2	FULL HIGH WOODEN PARTITION (Laminate finish)				

	<p>Fabrication and erection of glazed partition, with use of aluminium sections 2 1/2" x 1 1/2" of size spaced 2'0" x 2'0" both horizontally and vertically in a grid fashion, for a thickness of 3", both sides of the section to be finished with 8mm tk plywood duly treated for termite resistance and finished with 1 mm tk laminate as per direction. All openings are to be strengthened on the edges with additional wooden sections in order to fix glass (float glass). Inclusive of fixed glazing of size 5'6"x 4'0" with 8mm tk glass fixed as per specification. 3" high laminate skirting to be provided.</p> <p>Up to a height of 9'6" from finished floor</p> <p>i level for VC room</p> <p>Up to a height of 11'0" from finished floor</p> <p>ii level for back office.</p>	0	0		
	<p>Up to a height of 9'6" from finished floor</p> <p>i level for VC room</p> <p>Up to a height of 11'0" from finished floor</p> <p>ii level for back office.</p>	Sq.ft	250		
3	<p>GLAZED DOOR</p> <p>Fabrication and fixing of glazed door for cabins using 4" x 2 1/2" country wood frame filled with 8mm glass duly worked (fused pattern) as per the architect design. The door is to be fixed with pivots at top and bottom running on a flat hinge with necessary accessories, fixed on the outer side to be flush with the partition. All hardware locks handle and brass hinges etc for the door to be provided as per the design approved by the architect. Frame to be painted with automotive paint to match that of the partition.</p> <p>Size - 3'0" x 7'0" x 1 Nos, BM,ABM & VC room</p>	Sq.ft	63		
4	<p>NORMAL DOOR</p> <p>Full ht.solid 33 mmthk flush door of size as specified fully finished in 1mm laminate of equivalent brand, pattern, provide d with door closer ,edge lipping lock and SS handle all complete including 4" x 3" wooden door frame.</p> <p>Size - 3'0" x 7'0" x 3 Nos</p>	Sq.ft	63		
5	<p>ENTRANCE DOOR</p> <p>Fabrication and fixing of front entrance door made of 12mm thick glass (Fused Glass to be worked as per the design). With the help of 6" x 2 1/2" Burma teak sections both on top and bottom. Brushed steel SS pipes worked as handrail per detail. The door is to be fitted with pivot on top and bottom with floor spring Everlite or ISI approved and all accessories etc complete.</p> <p>Size - 6'0" x 7'0" x 1</p>	Sq.ft	42		
6	<p>EXTERNAL FIXED GLASS</p> <p>Supplying & fixing of fully glazed partition upto 8'0" ht. 12mm thk float glass with top & bottom section for the same as entrance door etc;, complete ae per architect direction.</p>	Sq.ft	80		
7	<p>WALL PANELLING</p> <p>Fabrication & Paneling with 8mm tk branded Bision Panel</p>	Sq.ft	150		

	<p>/ Hilux / V Board Partition and finished with 4mm tk OST duly polished / 1mm tk laminate to match the interior décor, as per architect direction. Wall paneling - BM Cabin</p>				
8	<p>FULL HIGH GLAZED PARTITION - MODULAR Supplying and fixing in position fully glazed full height modular partition work in frame work at 2' x 2' grid (horizontally and vertically) comprising of 2" x 1½" T.W section and/ or as per frame work with 6mm plywood on both sides finished with 1mm thick laminates of approved shade and colour. Item to include door of size 3'0" x 7'0" with etching and frosting as per design and 2" x 2" T.W. member for door sides and glass sides and T.W door frame to take 8mm thick glass with etching and frosting. All exposed T.W surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary stainless steel finish fittings/ hardware, door closers, Godrej locks and wood preservative paint etc. as per list of approved material and as approved by the project consultant/ bank complete in all respects including door. (Note : In case of false ceiling, the vertical T.W members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only) BM cabin & vc & ups room partition (9'6" ht) - modular</p>	Sq.ft	432		

9	<p>HALF HT GLAZED MODULAR PARTITION Supplying and fixing in position half ht glazed modular partition comprising of GI floor channels 48 mm x 50 mm & 0.45 mm thk at 4'0" intervals fixed with 8mm tk fiber cement board on both sides & joints filled with joint tape & jointing compount. All openings & doors to be reinforced with GI intermeditate channels of .7mm thk. Both sides finished with 1mm thk laminate of approved shade & colour. Item to include 8mm thick glass with etching and frosting. All exposed surfaces to be finished with Teak Wood lipping in melamine polish of matching laminate colour as directed including all necessary stainless steel finish fittings/ hardware, door closers, Godrej locks and wood preservative paint etc. as per list of approved material and as approved by the project consultant/ bank complete in all respects. Skirting to be provided as per archietct direction.</p> <p>i 4'6" from finished floor level for side modular pa 4'6" ht from finished floor level for modular II workstations III 9'6" ht modular oneside partition for waiting lou</p>	Sq.ft	0		
10	<p>STORAGE CABINET - MODULAR (HALF/FULL HEIGHT) Supplying & fixing of Storage cabinets upto a height of 2'6"/7'0", size 1'3"/1'6" wide and 1'3" deep, made of 18mm thick termite treated, water proof plywood. The backside of the cabinet is to be covered with 12mm thick plywood. The front door is to be lipped withteak wood on all four sides. The doors are to be fitted with 3" brass hinges and proper locks are to be fixed. The outer sides of the cupboard are are to be finished with 1.5mm thick laminate.The inner side of the cabinet is to be finished with 2 coats of putty and 2 coats of enamel.</p> <p>a.) Full heigh (FCB) VC Room store only 7'0" ht b.) Half heigh (HCB) Behind MTB & OTBs (2'6"ht) c.) Half heigh (HCB) Behind cubical OTBs (5'0" ht)</p>	Sq.ft	310		
11	<p>PANTRY COUNTER - DINING - MODULAR Fabrication and Fixing of modular dining counter of 19 mm plywood finished with 1mm tk laminate on the outer exposed sides and duco automotive paint on the inner sides so as to match the color of the interiors. The work has to be completed as per architect direction. Pantry (Dining) & Dafthry counter - 2'0" wide</p>	Nos	2		

12	<p>NOTICE BOARD</p> <p>Fabrication and fixing of Notice board made of wooden frame filled with soft board covered with fur. The colour of the fur is to be selected by the Architect. The outer frame of the notice board is to be finished with automotive paint so as to match the colour of the existing wall. (Size 4'0" x 3'0")</p>	Sq.ft	12		
13	<p>BOXING FOR ROLLING SHUTTER</p> <p>Box with open able shutter & ceiling in 19mm tk ply for rolling shutter servicing with support in wooden frame, etc& complete with paint finish on all the sides</p>	Sq.ft	135		