

**INVITATION OF TENDER**

**INSTRUCTION TO TENDERERS**

**AND**

**GENERAL CONDITIONS OF CONTRACT**

**FOR**

**COMPOSITE TENDER FOR INTERIOR AND FURNISHING WORKS  
AT  
INDIAN BANK  
TIRUNAGAR BRANCH**

**ARCHITECTS**

**MATHURA ASSOCIATES.**

47 – B TOWN HALL ROAD, 1ST FLOOR, MADURAI – 625001  
9965881704  
arch.mathura@gmail.com

**INDIAN BANK**

**Zonal Office,  
100-101, East Avani Moola Street,  
Madurai 625001**

**NOTE: Necessary drawings/ details may be collected from Architects office**

# A

**INDIAN BANK, ZONAL OFFICE MADURAI  
COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH  
TENDER NOTICE**

Sealed item rate tenders are invited on behalf of:  
**Zonal Office,100-101, East Avani Moola Street, Madurai 625001**

Name of the Work	Composite tender for furnishing works
Location	TIRUNAGAR branch
Time of Completion	2 weeks from the date of Work Order.
Earnest Money	Rs- 10000 /- (Rupees Ten thousand only) to be deposited in the form of Crossed Demand Draft / Pay order / Bankers Cheque drawn in favour of Indian Bank , payable at Madurai. No interest will be paid on the Earnest Money deposit.
Tender Cost	500/- (Rupees Five Hundred Only).
Availability of Tender Document	Indian Bank Zonal Office, 100-101, First Floor, Premises Department, East Avani Moola Street, Madurai 625001 from 20.01.2025 at 10:00 AM to 05:00 PM (Except Sunday and 2 <sup>ND</sup> & 4 <sup>th</sup> Saturday & Bank Holidays).
Submission of Tender	At Indian Bank, Indian Bank Zonal Office, 100-101, First Floor, Premises Department, East Avani Moola Street, Madurai -
Last date of Submission	<u>On or before 3.30 PM on 03.02.2025</u>
Opening of Tender	At 4 PM on <u>03.02.2025</u> . At Indian Bank Zonal Office, 100-101, First Floor, Premises Department, East Avani Moola Street, Madurai 625001
Mode of submission of Tender	The tender shall be submitted in accordance to the procedure detailed herein. Specified documents shall be sealed & signed by authorized person of the firm in envelope of appropriate size, each of which shall be sealed. "Tender for Interior and Furnishing works for TIRUNAGAR Branch and ATM" And be addressed to Zonal Manager, Indian Bank Zonal Office, 100-101, First Floor, Premises Department, East Avani Moola Street, Madurai 625001
Clarification , if any	To be obtained from the Architect, M/s MATHURA ASSOCIATES, 47 – B TOWN HALL ROAD, IST FLOOR, MADURAI – 625001
Validity of tenders	Three calendar months from the last date of submission of Tender

The Bank does not bind it to accept the lowest tender and reserves the right to reject any or all the tenders received without assigning any reason/s there of. The notification of award of contract will be made to the successful tenderer only in writing by the Bank.

Yours faithfully  
**For Indian Bank**

**Zonal Manager**

# A

**INDIAN BANK, ZONAL OFFICE MADURAI  
COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH  
OTHER TERMS & CONDITION**

- 1 Defect Liability Period: One year after actual completion of work.
- 2 Total security deposit (TSD): 5 % of the total value of the work, this will be released after the defect liability period.
- 3 The contractor shall have the responsibility of complying with the local shops/ establishments Act and other labour / minimum wages Act and shall keep all such records/ accounts on payment of wages/attendance as deemed necessary.
- 4 Arbitration: As per the standard arbitration clause under the jurisdiction of Tamilnadu.
- 5 Organization: The contractor shall employ competent / qualified supervisor / Engineer-in-charge who shall be responsible for the day to day work and coordinate as necessary with the Architect's supervisor. Any workman found guilty of misconduct / theft shall be removed from the site.
- 6 Damage to property: Any damage to the Bank's property during the work period will be recovered from the contractor.
- 7 The Contractor shall be penalized if the work is not completed within the scheduled time at a rate of Rs.2000 per day.
- 8 The Contractor should be registered under GSTIN, failing which the tender will be rejected.
- 9 Deduction: Income tax at source as per I.T Act.
- 10 Billing Procedure: All measurements shall be recorded in duplicate on standard measurement sheets prepared jointly by the Architect's Site engineer & the contractor's representatives duly signed by them. All bills shall be submitted along with this checked measurement sheets.
- 11 The payment of the bill shall be made as per the actual measurement as certified by the architect.
- 12 The Architect or any officer of the Employers will be free to inspect the work at the site during the period of execution. Any suggestion of change or modification to improve the quality of work will be carried out subject to prior approval of the competent authority of the employers and that of the Architect

# A

## INDIAN BANK, ZONAL OFFICE MADURAI COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH

- 13 In case of failure to take up the work even after accepting the work order, or leaving the work incomplete, or for defective work not rectified, or violation of the terms and conditions, the Bank may take suitable action against the contractor as appropriate.
- 14 The Contractor shall have to make their own arrangement at their own cost for storing materials, plants, tools etc. The employer will not be liable for security of the Contractor's materials.
- 15 In case of breach of contract by the Contractor for slow progress or works or any other claim of damage, the Employer or the Architect may have the power to re assign the contract without assigning any reasons thereof.
- 16 The Architect shall have the power to ask the contractor to furnish the sample, colour etc. for any materials used / to be used in the works.
- 17 The Employer shall not be liable for any damages or compensation payable as a consequence of any accident or injury to any workman or other persons in the employment of the Contractor.
- 18 On completion of the Works, all rubbish, debris, materials, tools, Labourers, etc. to be removed by the contractor from the site and the contractor will hand over the site clean & clear & in usable condition within 3 days of completion of the works. Failing which, the employer may dispose the materials at the cost of the contractor.
- 19 In case of any dispute, the matter will be referred to the Zonal Manager, Indian Bank , Zonal Office Madurai .
- 20 Tender submitted without earnest Money Deposit, Tender Cost and other documents specified above will be disqualified. Further, if any of the above information found false or incorrect the Bank reserves the right to summarily reject the application without assigning any reason thereof.

# A

**INDIAN BANK, ZONAL OFFICE MADURAI  
COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH  
THE CONDITIONS OF TENDER**

1. The tender form must be filled in English and all entries must be made by hand and written in ink.
2. Each and every page of the tender document must be signed by an authorized person.
3. The tenders must be submitted in the prescribed format only. The tenderers must quote the rates in the schedule of quantities, rates and amount. The rates should be written both in words and figures without any erasures and alterations. However, if errors are made, the wrong figures or words must be neatly scored Out under full signature of the tenderers and the correct figures and words neatly rewritten. Over writing is not permitted. Applying white fluid for correcting rates and amount is also prohibited.
4. VAT and GST as applicable will not be paid separately. The Tenderer must include these charges in the rates quoted, if applicable. No separate claim on this account will be entertained under any circumstances whatsoever. The tenderer shall quote his rates inclusive of cost of materials, corresponding wastages, labour, sales tax and any other taxes and duties, octroi, and cost of transportation of materials to work site etc.
5. Errors in the schedule of quantities, rates and amount shall be dealt with in the following manner:
  - a. In the event of a discrepancy between the rates quoted in words and the rates in figures, lowest rate will be taken into consideration.
  - b. In the event of an error occurring in the amount column as a result of wrong calculation the unit rate shall be regarded as firm and the amount shall be amended accordingly based on the quantity given.
  - c. All errors in totaling in the amount column and in carrying forward, the totals shall be corrected.
6. The quantities indicated in the schedule of quantities are only probable quantities and are liable to alteration by omission, reduction or addition. Payment shall be made on the basis of actual quantities of work done at the accepted rates.
7. No alterations which are made by the tenderer in the drawings, specifications or in probable quantities accompanying the tender will be recognized and if any such alterations are made the tender is likely to be

# A

INDIAN BANK, ZONAL OFFICE MADURAI  
COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH  
rejected and invalidated.

8. The tenderer must at his own expenses all the information necessary for the at his own expenses all the information necessary for the at his own expenses all the information necessary for the to. The site can be inspected on all working days from Monday to Friday from Dt 26.12.2024 to 09.01.2025 between 10 AM to 5 PM

9. The tenderer shall also bear all expenses in connection with the preparation and submission of this tender.

10. **EARNEST MONEY DEPOSIT (E.M.D) :**

The tenderer shall also deposit an amount of **Rs 10000/- (Rs. Ten thousand only)** in the form of a Demand Draft drawn on any scheduled Bank in favour of **Indian Bank Zonal Office** , Payable at **Madurai** at the time of submission of the tender as Earnest Money. Indian Bank is not liable to pay any interest on Earnest Money.

The EMD of unsuccessful tenderer shall be refunded to them without any interest after the decision to award the work is taken. The EMD of the successful tenderer shall be retained as part of security deposit and for the due fulfillment of the contract.

11. **SECURITY DEPOSIT (S.D) :**

Security Deposit shall be deducted from running/progressive bill/s of the contractor @ 5 % of the gross value of the each bill. Security Deposit shall not bear any interest. The security deposit shall retained by **Zonal Office Madurai Indian Bank**, till the end of defect liability period.

12. **COMPLETION PERIOD :**

The time is the essence of contract. The entire work shall be completed by the contractor within 2 WEEKS from the date of issue of the work order. The work shall be commenced immediately at the site.

The work is of urgent nature and the completion time schedule should be strictly adhered to by the contractor.

13. The tenders submitted shall remain valid for acceptance for a period of **3 months** from the date of their opening. Should any tenderer after being declared as successful bidder withdraws his tender or makes any modifications to his tender, the tender shall be treated as having been rejected or abandoned and his EMD will be forfeited.

# A

## INDIAN BANK, ZONAL OFFICE MADURAI COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH

14. It is not binding on **Zonal Manager Indian Bank** to accept the lowest tender and reserves the rights to reject any or all the tenders received without assigning any reasons thereof. Further **Zonal Manager Indian Bank** reserves the right to award any portion of the work or portions of the work to different tenderers or to award the entire work to one tenderer.
15. The tenderer whose tender is accepted is bound to execute a formal agreement **Zonal Manager Indian Bank** in accordance with the draft agreement which will include the notice inviting tender, tender conditions, other papers herein, special conditions, drawings and specifications etc. Irrespective of whether a formal agreement is drawn or not the contractor on being awarded the contract is liable based on acceptance of his tender. The contractor shall bear all expenses in connection with the execution of the said agreement including fees for stamps and registration of documents as required.
16. The compensation or other sums of money payable by the contractor to **Zonal Manager Indian Bank** the terms of contract may be deducted from his EMD/SD if the amount so permits and the contractor shall unless such deposit has become otherwise payable, within ten days after such deduction make good in cash the amount so deducted.
17. The work shall be carried out under the directions and supervision of and subject to the approval in all respects by the **Consultants/ Zonal Manager Indian Bank** .
18. On acceptance of the tender the contractor shall in writing at once inform **Zonal Manager Indian Bank** and the Consultants the names of his accredited representatives who will be responsible to take instructions from the **Consultants/ Zonal Manager Indian Bank** .
19. The work or any part of it shall not be transferred or assigned without the consent of the **Zonal Manager Indian Bank**.
20. The contractor shall be required to co-operate and work in accordance with and afford reasonable facilities for such other agencies/specialists as may be employed by **Zonal Manager Indian Bank** on other works / sub works in connection with the work.
21. The contractor will be required to insure the work and keep it insured until one month after the date of taking over the works by **Zonal Manager Indian Bank** or otherwise as per the terms of the contract, against loss or damage by fire and other usual risks other than the risks accepted in the terms of the contract with an approved in **Zonal Manager Indian Bank**.

# A

## INDIAN BANK, ZONAL OFFICE MADURAI COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH

22. The contractor is required to comply with all acts of Govt. relating to labour rules and regulations made there under from time to time submit at the proper times all particulars and statements required to be furnished to the labour authorities.
23. For all the items of work executed by him, the contractor will be required to supply, at his own expenses, to the Consultants, copies of post card size photographs in triplicate for each of the works, taken from two approved portions of each item of work at intervals of not more than two weeks during the progress of the work and also at every important stages of the work or as directed by the **Consultants/ Zonal Manager Indian Bank**.
24. In carrying out the work, the contractor shall comply with the provisions of the safety code, annexed to these papers.
25. The bidder shall furnish an undertaking duly attested by notary in a non-judicial stamp paper of value Rs.100/- (**Rupees Hundred Only**) regarding their non-blacklisting/Left any work abandoned in any of the government department and public sector undertaking/enterprise in India and central vigilance commission during the last five financial years as per Annexure-X.



A

**INDIAN BANK, ZONAL OFFICE MADURAI  
COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH**

**PROPOSED INTERIOR FURNISHING WORK FOR INDIAN BANK - MADURAI THIRUNAGAR  
BRANCH ( NEW PREMISES) – BILL OF QUANTITIES**

Sl.No	Particulars	Qty	Unit	Rate (Rs)	Amount (Rs)
	<b>INTERIOR/FURNISHING WORKS</b>				
<b>I</b>	<b>BRANCH</b>				
<b>1</b>	<b>Full height partitions with glass panels for manager cabin:</b>				
	Supplying and fixing glazed partitions using aluminium section of size 2"x 2" frame work having 2'x2' square grid on both sides covered with 6mm ply wood of approved make and finished with 1.0mm thk lamination which is to be used as per the drawing mentioned. Partitions frame is to be fixed properly to the roof slab, wood lipping with <b>Teak wood finish</b> to be fixed to fix the <b>12mm thk glass</b> with etching for full height partition. A glazed door has to be provided as per the drawing with <b>door closer and locks of godrej make.</b> (the partitions area given below the false ceiling level cost includes for aluminium frame to be extended and fitted up to roof ceiling. <b>Doors</b> to be made out of <b>10mm</b> thk glass with etching as per the design glass with etching has to be fixed on aluminium channel and the aluminium frame shall be covered with <b>6mm plywood</b> with 1.0mm thk lamination which is to be used as per the drawing mentioned the cost include 5" brass hinges(4nos/door) and door handle as approved by architect.				
	<b>Partition size : (4'0" X 7'0" ) x 2 Nos</b>	<b>56</b>	/ Sq.ft		
<b>2</b>	<b>Glazed partitions with entrance door:</b>				
	Supply and fixing of first class <b>Burma teak wood</b> . Main frame specifications-4"x3".Supply and fixing burma teak wood door frame size 5"x2"side and top and 6"x2" at bottom, stainless steel 1'0" ht handles to be fixed on both sides with <b>door closer and lock of godrej make</b> . 12mm thk glass with edging is to be fixed on the door frame. Proper teak wood lipping is to be provided to fix the 12mm thk glass. Cost includes brass hinges 5"-4Nos with 10" brass tower bolt-2Nos. All round with locker polish of approved shade and colour.2" teak wood lipping is to be provided on outer frame all sides. <b>Door size (6'0"X7'0")</b>	<b>42</b>	/sq.ft		

# A

## INDIAN BANK, ZONAL OFFICE MADURAI COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH

<b>3</b>	<b>Cash cabin partition with Table</b>				
	<u>Partition</u>				
	Providing and fixing in position of <b>2"x2"</b> aluminium section (2feetx2feet grid)both side covered with <b>8mm thk</b> ply wood and finished with 1.0 mm thk lamination which is to be used as per the drawing mentioned. Cash cabin size is 5'0"x8'0". wood lipping with teak wood finish to be fixed to fix the <b>12mm thk glass</b> with etching for cash counter partition. Cash counter 7'0" ht consists of plywood/glass partition with provision of opening at customer side and clerical side as per drawing.				
	<b>Door</b> to be made out of aluminium channel and the aluminium frame shall be covered with 8mm plywood with 1.0mm thk lamination with <b>godrej night latch and godrej door closer</b> . wood lipping with teak wood finish is to be used to fix . The cost includes 5" brass hinges-3Nos and door handle as approved by architect.				
	door size(2'6"x6'9")				
	<u>Table height 2'6"</u>				
	The table having 25mm thk machine made post formed top with side and front side drop made of 18mm thk ply wood and drawer units/shutter made of 18mm plywood. All exposed area is finished with 1.0mm thk lamination of which is to be used as per the drawing of approved make. For keyboard drawer and table drawers/shutters <b>set lock (godrej)</b> , stainless steel handles to be provided. Shutter is to be fitted with SS hinges of approved make to be provided for each clericals table. Front side edges of table/drops (clerical side) are to be finished with wood with teak wood finish painting with one coat of primer and two coats of paint after doing patty is to be undertaken inside the drawer/shutter/table inner side. Powder coated metal key board of good quality is to be provided.				
	25mm thk table machine made post formed top				
	<b>5'6"x 2'6"- 1No</b>	<b>1</b>	/ No		
	<b>5'0"x 2'6"- 1No</b>	<b>1</b>	/ No		
<b>4</b>	<b>Front &amp; side partition with door as per drawing</b>				
	Front side <b>(5'6" + 5'0") X 4'6"</b>				
	Side partition <b>( 7'0" X 7'0") 1 No (9'6"x7'0") 1No</b>	<b>371</b>	/sq.ft		
	Top side & Aluminum grills <b>(5'6"x 7'0") 1 No + (6'0"x7'0") 1 No</b>				
	Rear side : <b>(11'3"X7'0")</b>				

# A

## INDIAN BANK, ZONAL OFFICE MADURAI COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH

<b>5</b>	<b>Clerical/officer table-25mm thk Machine made post formed table top and side table top</b>				
	<u>Table height 2'6"</u>				
	<p>The table having 25mm thk machine made post formed top with side and front side drop, bottom base made of 18mm thk plywood and drawer units /shutter made of 18mm plywood. All exposed area is finished with 1.0mm thk lamination of which is to be used as per the drawing of approved make. For keyboard drawer and table drawers/shutters set lock (godrej), stainless steel handles to be provided. Shutter is to be fitted with SS hinges of approved make to be provided for each clericals table. Front side edges of table/drops(clerical side) are to be finished with wood with teak wood finish painting with one coat of primer and two coats of paint after doing patty is to be undertaken inside the drawer/shutter/table inner side. For the customer side of clerical table 10mm glass partition with edging of 1'3" ht to be fixed above the table using metal clamp to be fixed on side partitions /front pillar partition to be fixed between tables. The front pillar partition is to be made with 2"x 2" aluminium section both side covered with 6mm thk ply wood and finished with 1.0mm thk lamination as per drawing. The last table –side partition size 4'6" htx4'0" customer side and 3'6" ht clerical side supported with 2"x 2" aluminium section both side covered with 6mm thk plywood and finished with 1.0mm thk lamination as per drawing at the bottom and at top table 10mm thk edged glass fixed with metal clamp.</p>				
	Table with 25mm P/F table top <b>6'0" X 2'6" - 1 No (B.M)</b>	<b>1</b>	/ No		
	Table with 25mm P/F table top <b>4'6"X 2'6"- 1 Nos (O.T-2)</b>	<b>0</b>	/ No		
	Table with 25mm P/F Side table top <b>(3'6"x 1'6") (Mr)</b>	<b>1</b>	/ No		
	Table with 25mm P/F table top <b>(4'0"X 2'6") – 6 Nos</b>	<b>6</b>	/ No		
	Table with 25mm P/F table top <b>(7'0"X 2'6") – 1 No (GLA)</b>	<b>1</b>	/ No		
	Table with 25mm P/F table top <b>(3'6"X 2'0") – 2 No (SS)</b>	<b>2</b>	/ No		
	Table with 25mm P/F table top <b>(3'0"X 2'0") – 1 No</b>	<b>1</b>	/ No		
<b>6</b>	<b>Storage Unit(Full / low height) :</b>				

# A

## INDIAN BANK, ZONAL OFFICE MADURAI COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH

	Providing and fixing 1'6" wide storage unit made of 18 mm plywood finished with 1 mm lamination of approved colour & pattern on top and all visible sides with shelves. Inside painting with one coat of primer and two coats of paint after doing patty is to be undertaken. All exposed edges are finished with hardwood lipping. Provided openable shutters with SS handles, lock and auto closing hinges as per design.				
	<b>F.H.S</b>	<b>0</b>	/sq.ft		
<b>7</b>	<b>Front pillar partition &amp; side partition with glass</b>				
	<b>(3'6" X 4'0") 8 Nos</b>	<b>112</b>	/sq.ft		
<b>8</b>	<b>Full Height Partition with Glass Door:</b>				
	Supplying and fixing <b>PLYWOOD</b> partitions using aluminium section of size <b>2"x 2"</b> frame work having 2'x2' square grid on both sides covered with 6mm plywood of approved make and finished with 1.0mm thk lamination which is to be used as per the drawing mentioned. Partitions frame work to be fixed properly to the roof slab. A glazed door has to be provided as per the drawing with door closer and locks of Godrej make. <b>Doors</b> to be made out of <b>8mm</b> thk glass with etching as per the design glass with etching has to be fixed on aluminium channel and the aluminium frame shall be covered with 6mm plywood with 1.0mm thk lamination which is to be used as per the drawing mentioned. The cost include 5" brass hinges (4 nos) and door handle as approved by architect. Door size 3'0"X 7'0"				
	<b>Partition size :</b>				
<b>c</b>	Plywood Partition with <b>double side lamination</b> ( <b>12'3"X9'3"</b> ) + ( <b>9'9"X7'0"</b> ) + ( <b>3'0"X 7'0"</b> ) X 3 Nos <b>L.H.P :</b> ( <b>7'3"X 4'0"</b> )	<b>210</b>	/sq.ft		
<b>9</b>	<b>Fixing of glass</b>				
	Glass with all side edging is to be fixed in between pillar partition on the table top using SS clamp as per drawing.				
	12mm thk glass of size <b>4'0" X 1'3"</b> - <b>3 Nos</b>	<b>3</b>	/ No		
	12mm thk glass of size <b>3'6" X 1'3"</b> - <b>2 Nos</b>	<b>2</b>	/ No		
	10mm thk glass for table top <b>6'0" X 2'6"</b> - <b>1 Nos</b>	<b>1</b>	/ No		

# A

## INDIAN BANK, ZONAL OFFICE MADURAI COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH

<b>10</b>	<b>False ceiling:</b>				
<b>a</b>	<p>Supplying and Erecting of Saint Approved make Gypsum board false ceiling at different heights as per drawing and Framework shall be made with "Gyrpoc " G.I. Section. Perimeter shall be fixed around the wall and partition of size 20 x 28 x 30 x 0.5 thick / Ceiling angle of size 25 x 10 x 0.5 thick shall be suspended from structural soffit with 1220 c/c distance on both direction and fixed with soffit cleat of size 27 x 37 x 25 x 1.6 thick and rawl plug / Intermediate channel of size 15 x 45 x 15 x 0.9 thick to support the ceiling section / Ceiling section of size 80 x 26 x 51 x 0.5 thick shall be connected to the intermediate section at 457mm c/c with connecting clip of size 2.64 diameter. 12.5mm thick Gypsum plain board to be fixed on the ceiling section with drywall screws at 230mm c/c on both direction. Gypsum board joints shall be connected with fibre tape and joints to be finished with putty, the putty shall be applied fully on the gypsum board area. Cost include 2 coats of emulsion paint and 1 coat of primer, cutout opening for light fittings, stepping, box opening, provision for hidden lights arrangements. Cost include wastage, hardwares, tools, lead, lift, loading, unloading charges, labour charges, transport and etc.</p>				
	Note: Measurements shall be made flat area and verticals in SFT.	<b>1560</b>	/ sq.ft		
<b>11</b>	<b>Writing ledge/challon holder</b>				
	Fabricating and fixing of writing ledge and challon holder made of 10mm glass supported with plywood stand finished with lamination glass edges beveled to half round safe suitably supported on ply wood as per drawing.	<b>1</b>	/No		
<b>12</b>	<b>Notice board</b>				
	Fabricating and fixing of notice board made of teak wood frame filled with soft board and covered with fabric, a color of the fabric to be math the décor the outer frame of the notice board is to be finished with locker polish.	<b>1</b>	/ No		
	(size 4'0"x3'0")				
<b>13</b>	<b>Wicket door : 3'3" x4'0"</b>	<b>13</b>	/sq.ft		
<b>14)</b> <b>a</b>	Applying two coats of interior grade emulsion paint of approved colour to internal walls and ceiling including labour charges, cost and conveyance of material etc complete.	<b>3270</b>	/sq.ft		

# A

## INDIAN BANK, ZONAL OFFICE MADURAI COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH

<b>b</b>	<b>Painting</b> Entrance grill gate and Rolling Shutter etc.,				
	using <b>synthetic enamel paint</b> two coats of approved colour including all frameworks and related elements after removing the existing paint with sand paper and thereafter cleaning the surface including all labour charges, material charges etc complete.	<b>240</b>	/sq.ft		
<b>c</b>	Applying two coats of putty with two coats of interior grade emulsion paint of approved colour to internal walls including labour charges, cost and conveyance of material etc complete.	<b>1440</b>	/sq.ft		
<b>15</b>	<b>Wall paneling:</b>				
	Aluminum section of size 2"x1" (grid 2'0"x2'0") frame work and covered with <b>8mm commercial plywood</b> (one side fixing) finished in lamination. The paneling area given below the false ceiling level. Cost includes for aluminum frame to be extended and fitted up of roof ceiling. Size : (8'0"+5'0") X 8'0"	<b>104</b>	/sq.ft		
<b>16</b>	Providing and fixing <b>Cheque Drop Box</b> of size				
	<b>(1'6" x 1'6"x 1'0")</b>	<b>2</b>	/ No		
<b>17</b>	Providing and fixing <b>Roller blinds</b> for all windows Colour and materials selection by the Architect, Rates including material cost and labour charges etc. complete.	<b>0</b>	/sq.ft		
	<b>(4'6"X 4'6") X 2 Nos + (5'6"X4'6") 1 No</b>				
	<b>TOTAL (I)</b>				
	(inclusive of all taxes and expenses & GST etc.)				

# A

**INDIAN BANK, ZONAL OFFICE MADURAI  
COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH**

<b>PROPOSED INTERIOR FURNISHING WORK FOR INDIAN BANK - MADURAI THIRUNAGAR</b>					
<b><u>ATM (NEW PREMISES) – BILL OF QUANTITIES</u></b>					
<b>Sl.No</b>	<b>Particulars</b>	<b>Qty</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>
				<b>(Rs)</b>	<b>(Rs)</b>
	<b>INTERIOR/FURNISHING WORKS</b>				
	<b>ATM</b>				
<b>1</b>	<b>False ceiling</b>				
<b>a</b>	Supplying and Erecting of Saint Approved make Gypsum board false ceiling at different heights as per drawing and Framework shall be made with "Gyrpoc " G.I. Section. Perimeter shall be fixed around the wall and partition of size 20 x 28 x 30 x 0.5 thick / Ceiling angle of size 25 x 10 x 0.5 thick shall be suspended from structural soffit with 1220 c/c distance on both direction and fixed with soffit cleat of size 27 x 37 x 25 x 1.6 thick and rawl plug / Intermediate channel of size 15 x 45 x 15 x 0.9 thick to support the ceiling section / Ceiling section of size 80 x 26 x 51 x 0.5 thick shall be connected to the intermediate section at 457mm c/c with connecting clip of size 2.64 diameter. 12.5mm thick Gypsum plain board to be fixed on the ceiling section with drywall screws at 230mm c/c on both direction. Gypsum board joints shall be connected with fibre tape and joints to be finished with putty, the putty shall be applied fully on the gypsum board area. Cost include 2 coats of emulsion paint and 1 coat of primer, cutout opening for light fittings, stepping, box opening, provision for hidden lights arrangements. Cost include wastage, hardwares, tools, lead, lift, loading, unloading charges, labour charges, transport and etc. Size : (11'3"x6'6")				
	Note: Measurements shall be made flat area and verticals in SFT.	<b>73</b>	/Sq.ft		

# A

## INDIAN BANK, ZONAL OFFICE MADURAI COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH

<b>b</b>	Providing and fixing tile Grid ceiling of Mineral fiber ceilings of board with "Narrow Reveal edge Corner bevel" 14mm grid (Bolt Slot) section ) and RH99 (H1893M)" tile with "BEVELLED TEGULAR Suprafine 15 mm/ Silhouette grid section ) in aluminium powder coated sections supported from ceiling (4'0"x4'0"grid for support rods) with necessary GI framework of every 2'0"x2'0" grid junction, proper levelling and finished of the joints & top surface as per manufactures specifications and all accessories, arrangements and etc. All edges shall be perfectly straight. Tile shall be carefully laid with neat arrangements like hand gloves and etc. Cost include replacement of damaged or stained tile. Cost include all necessary hardwares like nails, screws, wastages, transports, loading, unloading charges, labours, lead, lift, materials, tools and etc. Complete as per drawings and instructions of the Architect. APPROVED MAKE	<b>0</b>	/Sq.ft		
<b>2</b>	<b>ATM-Entrance door</b>				
	To be made out of 8mm thk glass etching as per the design glass with etching has to be fixed on aluminium channel the bottom frame size is 6"x1½" and the middle, vertical frame size is 2½"x1½" and the top frame size is 3"x1½". The cost include floor spring of everite make and door handle as approved by architect door size (3'0"x7'0") cost include <b>Godrej</b> make floor spring	<b>21</b>	/Sq.ft		
<b>3</b>	<b>ATM fixed glazed partition</b>				
	To be made out of 8mm thk glass with etching as per the design glass with etching has to be fixed on aluminium channel the bottom frame size is 3"x1½" and the vertical frame size is 2½"x1½" and the top frame size is 3"x1½". <b>Size (3'0" X 7'0")</b>	<b>21</b>	/Sq.ft		
<b>4</b>	<b>ATM-wall paneling</b>				
	Aluminium section of size 2"x1" (grid 2'0"x2'0") frame work and covered with <b>alcopanel sheet</b> (one side fixing) The paneling area given below the false ceiling level. Cost includes for aluminium frame to be extended and fitted up of roof ceiling.	<b>192</b>	/Sq.ft		
<b>5</b>	<b>Painting</b> Rolling shutter using <b>synthetic enamel paint</b> two coats of approved colour including all frameworks and related elements after removing the existing paint with sand paper and thereafter cleaning the surface including all labour charges, material charges etc complete.	<b>136</b>	/Sq.ft		



# A

## INDIAN BANK, ZONAL OFFICE MADURAI COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH

<b>6</b>	Providing and fixing <b>Switch board coverage box with lamination including Godrej locks and handles etc.,size : (2'0"x1'6") max. depth 6"</b>	<b>1</b>	/no		
<b>7</b>	<b>Storage Unit(Full / low height) :</b>				
	Providing and fixing 1'6" wide storage unit made of 18 mm plywood finished with 1 mm lamination of approved colour & pattern on top and all visible sides with shelves. Inside painting with one coat of primer and two coats of paint after doing patty is to be undertaken . All exposed edges are finished with hardwood lipping. Provided openable shutters with SS handles, lock and auto closing hinges as per design.				
	<b>F.H.P: 3'6" X 8'0" (DEPTH: 1'6")</b>	<b>0</b>	/sq.ft		
<b>8a</b>	<b>Full Height Partition with Glass Door:</b>				
	Supplying and fixing <b>PLYWOOD</b> partitions using aluminium section of size 2"x2" frame work having 2'x2' square grid on both sides covered with 8mm plywood of approved make and finished with 1.0mm thk lamination which is to be used as per the drawing mentioned. Partitions frame work to be fixed properly to the roof slab. A glazed door has to be provided as per the drawing with door closer and locks of Godrej make. <b>Doors</b> to be made out of <b>8mm</b> thk glass with etching as per the design glass with etching has to be fixed on aluminium channel and the aluminium frame shall be covered with 6mm plywood with 1.0mm thk lamination which is to be used as per the drawing mentioned. The cost include 5" brass hinges (4 nos) and door handle as approved by architect. Door size (6'6"X 9'3")				
	<b>Plywood Partition with one side Alcopanel Sheet and other side lamination</b>	<b>60</b>	/sq.ft		
<b>9</b>	Providing and fixing <b>Entrance Door ply Box</b> of size <b>(6'0" X 2'3" )</b> Aluminium section of size 2"x1" (grid 2'0"x2'0") frame work and covered with 6 mm commercial plywood (one side fixing) finished in lamination.	<b>14</b>	/Sq.ft		
<b>10</b>	Providing and fixing <b>Entrance Rolling shutter coverage box with</b> Aluminum section of size 2"x1" (grid 2'0"x2'0") frame work and covered with <b>Alco Panel sheet</b> of size <b>(7'9"x 6'0")+ (1'6"x 3'0" ) 2 Nos</b>	<b>56</b>	/Sq.ft		

A

INDIAN BANK, ZONAL OFFICE MADURAI  
COMPOSITE TENDER FOR FURNISHING OF TIRUNAGAR BRANCH

	(Note: Please Visit the Site Before You Quote the Value)				
	<b>TOTAL</b>				
	(inclusive of all taxes and expenses & GST etc.,)				

**SUMMARY**

FOR INDIAN BANK TIRUNAGAR BRANCH ATM , MADURAI

#	DETAILS	TOTAL AMT IN RS
A	BRANCH INTERIOR AND FURNISHING WORK	
B	ATM INTERIOR WORK	
	TOTAL	

TOTAL

(Rs )

DATE:

SIGNATURE OF CONTRACTOR

**CONTRACTORS ARE REQUESTED TO VISIT THE SITE AND COLLECT ALL OTHER NECESSARY DETAIL DRAWINGS FROM THE CONSULTANTS OFFICE BEFORE QUOTING.**

**IF ANY DOUBT IN THE DRAWING AND SPECIFICATION PLEASE GET IT CLARIFIED FROM THE CONSULTANT/ ARCHITECT BEFORE SUBMISSION OF TENDER.**

**NO EXTRA WILL BE PAID TO COMPLETE ONE SINGLE ITEM MENTIONED IN THE TENDER.**