



REQUEST FOR QUOTATION (RFQ)

**SCHEDULE FOR ELECTRICAL AND DATA CABLING WORKS
(ANNEXURE B)**

FOR

**INTERIOR FURNISHING INTERIOR FURNISHING,
ELECTRICAL AND DATA CABLING WORKS AT
INDIAN BANK, UDAGAMANDALAM BRANCH PREMISES
P.B.NO:- 108S, BURN FOOT, ROSE GARDEN ROAD,
UTHAGAMANDALAM- 643 001**

Indian Bank, Zonal Office, Coimbatore,
No: 31, Variety Hall Road, Coimbatore,
Tamil Nadu – 641 001.
Ph: 0422-2309242 / 0422-2309243.
Mob: 9884792700 /9900643942
Email: zocoimbatore@indianbank.co.in



TENDER SCHEDULE FOR THE ELECTRICAL WORKS
AT M/s. INDIAN BANK,UDAGAMANDALAM,OOTY BRANCH,TAMIL NADU.

Annexure - B

S.No	Description	Qty	Unit	Rate (Rs.)	Amount (Rs.)
1	Supply & laying of following PVC insulated copper wire in suitable PVC conduit pipe/PVC channels as per site condition) necessary clampings etc., for branch				
a	4C x 25 sq mm AL Ar UG Cable from EB Mains to main power panel.	64.00	mtrs		
b	4C x 6 Sqmm + 1R x 4.0 Sqmm copper cable from main power panel to UPS input Mains 4 point & AC DB	65.00	mtrs		
c	4C x 4 Sqmm + 1R x 2.5 Sqmm copper cable from main power DB to Lightning DB's.	27.00	mtrs		
d	2 x 4 Sqmm + 1R x 2.5 Sqmm copper wire for Raw Power DB's, UPS Output DB's & AC DB, AC DB to AC units	205.00	mtrs		
e	2 x 2.5 sq mm + 1 x 1 sq mm MCB to computer (UPS.)	325.00	mtrs		
f	2 x 2.5 sq mm + 1 x 1 sq mm RAW power & lightings (including sinage lighting)	295.00	mtrs		
g	1 x 6 sq mm from dedicated UPS Earth pit to UPS	75.00	mtrs		
2	Supply & Wiring using 3 run of 4 sq mm and 2 run of 2.5 sq mm 600 V grade. PVC insulated FR copper wire through 25 mm dia PVC conduit with all necessary accessories like bend collar, saddle, screws etc. complete - from main panel to UPS mains.	30.00	mtrs		
3	Supply & installation of 63 A 4 P change over switch with SS enclosure	1.00	No		
4	Supply & intallation of UPS Power 3Nos 6 A 3 Pin sockets, 1No 16Aswitch in suitable box modular type.Work stations -13, Server - 1 No. 6A (5 pin socket) Manager cabin - 2 No.,	11.00	Nos		
5	32 A 3 Pin Metal Plug & soket with 1No 25A SP MCB - A/C	5.00	No		
6	Supply & intallation of RAW power for BC , POF,OTB and front office tables 16 A 3 pin sockets. 1 no 6 A switch in suitable box modular type	11.00	Nos		

- | | | |
|---|--|--------------|
| 7 | Supply & wiring for light points/ fan point wiring using 3 x 1.5 sq mm
PVC insulated copper wire in suitable PVC conduit pipe
with all accessories - concealed in wall including supply and
fixing of switch boxes, 6 A switches, ceiling rose etc. | 70.00 points |
| 8 | Supply, Fixing and wiring of wall fan with 1 No 6A socket
with 6A Switch with all necessary wirings.(Modular type)
(Burglar alarm & CCTV camera points at BM Cabin) | 14.00 points |

NET TOTAL AMOUNT (A)

Rs:

Rs:

(Rupees: _____)

Notes: All items are excluding of GST and other applicable taxes, unless specified

TENDER SCHEDULE FOR THE ELECTRICAL FITTING WORKS
AT M/s. INDIAN BANK,UDAGAMANDALAM,OOTY BRANCH, TAMIL NADU.

S.No	Description	Qty	Unit	Rate (Rs.)	Amount (Rs.)
I	<u>Fixtures & Fittings :</u>				
	Supply, delivery at site, receiving, storing, handling, carriage at site, assembling, erection including the drop down rods,chains,hooks & accessories connecting, testing and commissioning of the following Ceiling / wall mounted light fixtures including the lamps etc complete. (All fixtures to be of Wipro/ Philips/Havells make only and lamps of GE / Osram make only). (the rates are net and inclusive of cutouts and fixing).				
1)	Supply, fixing & connecting of following MCB DBs with necessary interconnections. Double Door type - concealed in wall as per site condition				
a)	MAIN POWER MCB DB: with ELCB This DB comprising of the following : Incoming: 125 A 4 P MCCB(25 Kilo amps) 1 No.				
(i)	63 A TP MCB = 1 for A/C				
(ii)	40 A TP MCB = 3 for ,UPS,Lightning,Raw power				
(iii)	63 A TP MCB = 1 for Spare				
	8way TPN vertical D.Door DB For MCCB Provision.	1.00	set		
b)	Lighting MCB DB : incoming: 40 A 4 P MCB - 1 No : Outgoing 10 A SP MCB - 9 Nos: Enclosure: 4 way TPN DB	1.00	set		
c)	UPS INPUT MCB DB: Incoming: 40 A 4 P MCB 1 No Outgoing: 20 A 2 P MCB 2 Nos Enclosure: 4 Way TPN DB	2.00	set		
d)	UPS OUTPUT CIRCUIT MCB DB: incoming 40 A 2 P MCB 1 Nos Outgoing: 10 A SP MCB 7 Nos Enclosure: 4 way 12 W SPN DB	2.00	set		

S.No	Description	Qty	Unit	Rate (Rs.)	Amount (Rs.)
c)	RAW POWER MCB DB: incoming 40 A 2 P MCB 1 Nos Outgoing: 10 A SP MCB 8 Nos Enclosure: 4 way TPN DB	1.00	set		
f)	AC POWER MCB DB: Incoming; 40 A 4 P MCB 1 No Outgoing: 20 A 2 P MCB 7 Nos Enclosure: 6 Way vertical DB	1.00	set		
a)	1 x 33 w LED square downlight Recess Mounted (Philips RC 375 B 30S) (2' x 2' fitting) (Incl Frame)	19	Nos		
b)	1 x 22 w Philips Square Ultraslim (Al body) 9"x 9"	11	Nos		
c)	1 x 18 w LED Ultraslim Round light (Al body) -BM	3	Nos		
d)	1 x 5 w / 7 w LED Ultraslim spot light (Al body)	1	Nos		
e)	1 x 7 w LED Round Spot light COB+ (Al body)	N.A	Nos	N.A	N.A
f)	CG Wall Mount Fan (Crompton / Usha)	8	Nos		
g)	48" CG Highspeed Ceiling Fan (Crompton / Usha / Hav	2	Nos		
h)	1 x 21 w LED Tube fitting Smart Bright 4feet (Al body)	8	No		
i)	Exhaust fan (9" exhaust almonored) Including provision for Opening & plsting wherever req (Toilet & UPS Battery Room)	3	Nos		
II General :					
a)	Rectifying, Testing, Erection and Commissioning of existing light points with fittings	5	Nos		
III EARTHING					
1	Providing dedicated earthing with 600 x 600 x 315 mm copper plate along with 50 mm dia. 10ft long GI pipe with other accessories in the earth filled with necessary salt, charcoal, etc, for upe it should be covered with GI manhole cover with necessary civil works. dedicated earth pit with earth resistance less than 1 ohm. A dedicated earth pit preferably the distance between one earth pit to another earth pit should not be less that 8ft inspection pit.	1	set		

S.No	Description	Qty	Unit	Rate (Rs.)	Amount (Rs.)
------	-------------	-----	------	---------------	-----------------

2	INSTALLATION OF UPS EARTH: Providing earth station comprising of 300 X 300 X 3mm copper plate with earthing resistance less than 2 ohms including watering PVC/GI pipe with funnel excavation back filling salt filling salt and coal filling in layers 10" x 10" masonry chambers with sand plaster etc complete as per architect direction.	2	No		
---	--	---	----	--	--

TOTAL AMOUNT

Rs.

SAY

Rs.

(In words:

Notes: All items are excluding of GST and other applicable taxes, unless specified

TENDER SCHEDULE FOR THE DATA CABLING WORKS
AT M/s. INDIAN BANK, UDAGAMANDALAM, OOTY BRANCH, TAMIL NADU.

S.No	Description	Qty	Unit	Rate (Rs.)	Amount (Rs.)
I	Telephone And Data Cabling Works				
1	Supply & laying of I.O Telephone point including cable in suitable PVC conduit pipe	10	Nos		
2	Supply & laying of 2 pair Telephone cable in suitable PVC conduit pipe	215	mtrs		
3	Supply & installation of RJ 11 Telephone socket(modular type)	10	Nos		
4	Supply & laying of 10 pair Telephone cable for Leased/ISDN Line including casing capping etc,. Complete.	205	mtrs		
5	Supply & installation of 20 pair krone block in suitable MS Enclosure with locking arrangements	1	No		
6	Supplying & Fixing of HCL CAT 6 10/100/1000 Mbps UTP Cable including the cost of laying the cable & PVC conduit pipe etc.complete (including ATM)	330	mtrs		
7	Supply & installation of RJ 45 information Outlets (Inclu ATM)	12	Nos		
8	Supply & providing of RJ 45 HCL CAT 6 patch cords - 3 Feet	12	Nos		
9	Supply & providing of RJ 45 HCL CAT 6 patch cords - 7 Feet	12	Nos		
10	Supply & Fixing of 10.5" 6U Rack with power manager & Cable Manager with fasteners including the cost of rack fixing etc.complete	1	No		
11	Supply & Fixing of HCL 24 Port 10/100/1000 Mbps Fast Ethernet Switch	1	No		
12	Supplying & Fixing of HCL CAT 24 Port Patch Panel including punching & Fixing etc.complete	1	Nos		

TOTAL AMOUNT

SAY

(Rupees: _____)

Rs:

Rs:

Notes: All items are excluding of GST and other applicable taxes, unless specified

Tender Schedule for Electrical Works at
M/s. Indian Bank, ATM of Udagamandalam, Ooty Branch, Tamilnadu.

S.No	Description	Qty	Unit	Rate(Rs.)	Amount(Rs.)
	Electrical Works – On Site ATM				
a	Supply & intallation of UPS Power 3Nos 6 A 3 Pin sockets, 1No 16A switch in suitable box - modular type.	5.00	Nos		
b	Supply & intallation of RAW Power 6 A 3 Pin sockets, 1No 16A switch in suitable box - modular type.	2.00	Nos		
c	4C x 4 Sqmm + 1R x 2.5 Sqmm copper cable from main DB to ATM main DB's .	45.00	mtrs		
d	2 x 4 Sqmm + 1R x 2.5 Sqmm copper wire from main DB to A/C units (2 A/c units)	34.00	mtrs		
e	2 x 2.5 sq mm + 1 x 1 sq mm MCB to ATM (2) UPS point	42.00	mtrs		
f	2 x 2.5 sq mm + 1 x 1 sq mm lightings from DB to switchboar	30.00	mtrs		
g	P/F electrical cables / switches / sockets / distribution boards for ATM Room as below.				
h	3 Phase Main 4 way DB	1.00	No		
i	40 A 4 P MCB for incoming	1.00	No		
j	20 A 2 P MCB for outgoing including A/C	5.00	No		
k	10 A SP MCB for lighting	3.00	No		
l	20 A 2 P MCB DB with enclosure for UPS points	3.00	No		
m	Lighting points	5.00	No		
n	5/15 amps. Power points	4.00	No		
o	16 A 3 Pin Metal Plug & socket with 1No 25A SP MCB for A/C control	2.00	No		
4	<u>EARTHING</u>				
a	INSTALLATION OF UPS EARTH: Providing earth station comprising of 300 X 300 X 3mm copper plate with earthing resistance less than 2 ohms including watering PVC/GI pipe with funnel excavation back filling salt and coal filling in layers 10" x 10" masonry chambers with sand plaster.	1.00	No		
	NET TOTAL AMOUNT (A)				Rs:
	SAY				Rs:
	<i>(Rupees: _____)</i>				<i>_____).</i>

Notes: All items are excluding of GST and other applicable taxes, unless specified

**INTERIOR FURNISHING INTERIOR FURNISHING,
ELECTRICAL AND DATA CABLING WORKS AT
INDIAN BANK, UDAGAMANDALAM BRANCH PREMISES
P.B.NO:- 108S, BURN FOOT, ROSE GARDEN ROAD, UTHAGAMANDALAM- 643 001**

**INTERIOR FURNISHING
(ANNEXURE A)**

Summary Sheet

SI No	Type of Work	Amount (Rs.)
1	Interior Furnishing Works – Branch • Interior Works	
2	Purchase of SFVM Items • Furniture & fixtures	
3	Interior Furnishing Works – ATM • Interior Works	
	Total (A)	

**ELECTRICAL AND DATA CABLING WORKS
(ANNEXURE B)**

Summary Sheet

SI No	Type of Work	Amount (Rs.)
1	Electrical Works – Branch	
2	Purchase of SFVM Items • Electrical fittings & fixtures	
3	Electrical Works – ATM	
4	Data Cabling Works	
	Total (B)	

CUMMULATIVE TOTAL

SI No	Type of Work	Amount (Rs.)
1	Interior furnishing Works - A	
2	Electrical and Data cabling works - B	
	Total (A+B)	

Note: All items are excluding of GST