

BILLS OF QUANTITIES FOR FURNISHING WORK OF INDIAN BANK FOR RANNAPARK BRANCH					
AHMEDABAD					
Sr. No.	Description	Quantity	Rate	Unit	Amount
[A]	<b>FURNISHING WORK FOR BRANCH</b>				
1	CASH COUNTER	5		RFT	
2	SINGLE WINDOW COUNTER			RFT	
3	LOW HEIGHT COUNTER FOR OFFICER			RFT	
4	Providing & fixing Full height <b>partition with door shutter</b> For Manager and other area <b>Note :Rate shall be same for solid partition</b>	188.30		SFT	
5	Providing and fixing low height partition For Cash /S.W Cabin and other partition	81		SFT	
6	Providing and fixing Isolated flush door shutter	49		SFT	
7	Providing and fixing Wicket Gate door in Cash cabin	16		SFT	
8	Providing and laying panneling on walls & pillars at main entrance door and 18mm thick plywood box for entrance door and AC pipe covering	142		SFT	
9	Providing and fixing Glass partition on Cash counter/ SW Counter / Low Height counter front side top as follows.	63.00		SFT	
10	Suppling and providing BM Table as per the following description Size 6'-0" x 2'-9". Table top shall be made for 18mm thick commercial	1		NO	
10	-DO- as above but S/P Officer Table Approx Size 4'-0" x 2'-6". With 1 Nos Drawer+ 1 Shutter unit for Officer	6		NO	
11	-DO- as above but S/P Officer Table Approx size <b>4'-6" x 2'-6" without Drawer storage unit in table</b>	0		NO	
12	Supplying and providing side cabinate for keeping computer and printer size 3'-3" Length 1'-4" Width and 2'-6" height. <b>Having openable shutters</b> as directed.	2		NO	
13	Supplying and providing side storage cabinate as per following description. <b>[Low Height and Full Height]</b>	167.5		SFT	
14	Providing and fixing Electric cup board using 18mm thick commercial ply wood with 1.0 mm thick laminate on outer side polishing/painting	35		SFT	
15	Providing soft board for pin up	8		SFT	
16	CUSTOMER WRITING DESK 'Size 3'-0" x 1'-0" x 6" ht.	1		NO	
17	Providing and fixing of letter box cum suggestion box of size 1' 3"x1'-0" x 3'-6" ht. Box	1		NO	
18	Providing and fixing "EG/Godrej" or equivalent make door closure.	4		NO	

Sr. No.	Description	Quantity	Rate	Unit	Amount
*	GLASS WORK				
	12 MM THICK TOUGHEND GLASS DOOR & PARTITION				
19	[I] OPENABLE PORTION Without Floor Spring	42		SFT	
20	[II] FIXED GLASS PORTION	236.03		SFT	
24	Providing and Fixing Floor Spring of Avertie or equivalent make heavy duty & double swing.	0		NO	
21	<b>ALUMINUM COMPOSITE PANEL FOR FRONT SIDE ELEVATION</b>	110		SFT	
22	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board	262.00		SFT	
23	Providing and fixing of Armstrong Mineral Fibre Acoustical Suspended Ceiling System with 16 mm thick FINE FISSURED (MICRO LOOK) EDGE TILES WITH ARMSTRONG SELECT (Black Reveal) 15 mm EXPOSED GRID.	608.00		SFT	
			<b>TOTAL COST "B"</b>	<b>RS.</b>	
<b>[B]</b>	<b>FURNISHING WORK FOR ATM ROOM</b>				
1	<b>ALUMINUM COMPOSITE PANEL FOR INSIDE WALL AND ABOVE MAIN DOOR BOX</b>	192.63		SFT	
2	MAIN ENTRANCE DOOR	21		SFT	
3	Providing and fixing Glass partition with coloured Anodise coated Aluminium frame on front side building [FIXED PORTION ADJ]	116.92		SFT	
4	Providing and Fixing Floor Spring of Avertie or equivalent make heavy duty & double swing.	0		NO	
5	S & P 24"X24" With Top Glass Tepoy	0		NO	
6	Providing and Fixing of Armstrong false ceiling specification same as Branch item	48		SFT	
7	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board	58.00		SFT	
			<b>TOTAL COST "B"</b>	<b>RS.</b>	
			<b>TOTAL COST OF FURNISHING WORK (A + B)</b>	<b>RS.</b>	

**Tender Amount(In Words) Rupees:**

---



---

(SIGNATURE OF TENDERER/FIRM)

NAME OF TENDERER

(SEAL OF FIRM)

PLACE:

DATE: