



INDIAN BANK, ZONAL OFFICE, PREMISES DEPARTMENT
228, First floor, M P Nagar, Zone I, Bhopal - 462011

INTERIOR FURNISHING WORK OF BHARNI BRANCH OF INDIAN BANK

SUMMARY

PART - A : Interior Furnishing Works of Branch :	Rs.	
PART - B : Furnishing Work of ATM	Rs.	
PART - C : Interior Furnishing Work of Server Room	Rs.	
Grand Total of Part A + B + C	Rs.	
Discount if any	Rs.	
Total Amount	Rs.	

Amount in words Rupees
..... Only)

Signature & Seal of Contractor

PART - A : Interior Furnishing Works of Branch

<u>Description</u>	<u>Amount (Rs.)</u>
Section - I : Partition & Panelling	Rs. <input type="text"/>
Section - II : False Ceiling	Rs. <input type="text"/>
Section - III : Hardware Fittings & Fixtures	Rs. <input type="text"/>
Section - IV : Furniture	Rs. <input type="text"/>
Section - V : Miscellaneous Work	Rs. <input type="text"/>
Total - PART A	Rs. <input type="text"/>

PART - A : INTERIOR FURNISHING WORK OF BRANCH

Section - I : Partition / Panelling

Sl. No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Frame Work				
	Providing and fixing non anodized aluminum rectangular hollow sections Alom 2348 : 50.80 x 25.40 x 1.16 mm wall thickness) or its approved equivalent for erection of frame work for partitions, paneling etc. to be placed 2' 0" apart in both vertical and horizontal direction. Extra members at corners / functions are also to be provided at no extra cost to the owner. The frame work shall be fabricated and installed in position firmly with the help of suitable Aluminum cleats, screws, clamps, rawl plugs and all necessary civil works and mending good to all damages complete with cost of all materials, labour, hardware etc. (Door and glass opening above shall be deducted from measurement for the purpose of payment.)	Sqm.	30.00		
2	Ply Wood				
	Providing and fixing 6mm thick of BWR (PF) grade ply wood as skin to existing frame works executed under item no. (1) above with screws at adequate intervals complete with cost of all labour and materials.	Sqm.	60.00		

Sl. No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
3	Laminate				
	Providing and fixing minimum 1.00 mm thick matt/satin finished laminates of approved colour and make to partitions & paneling and wherever directed to be fixed with suitable adhesive complete with cost of materials, labour and hardware etc. all as per drawing and direction of Architect.	Sqm.	60.00		
4	Frame to Doors				
	Providing and fixing Sal wood frames to door openings with suitable size of screws to be fixed directly on to the masonry walls in C. C. Lugs (1:2:4) as may be the case complete with providing minimum 2 or more coats of polish in superior malamine finish to the approval of Architect.	Cum.	0.15		
5	Glass				
	Providing and fixing plane float glass pane of following thickness on the frame works already erected and wherever directed in pattern as shown in the drawing with stainless steel Glazing Clips / D's or polished Gambhar Wood beading all along perimeter of the Glass as required including etching / grinding / polishing etc. as per approved design and pattern complete with the cost of all labour and materials.				
(a)	5.50 mm. thick (In partition walls only)	Sqm.	5.00		
(b)	12 mm. thick	Sqm.	3.50		
6	Flush Door				
	Providing and fixing in position 30 mm. thick solid core black board construction bonded with phenol phermaldehyde synthetic resign raising commercial faces which shall be laminated with 1.0 mm hick laminates on either sides, edges, sealed with 1st class Teak wood leaping complete.	Sqm.	3.50		
7	Partly Glazed Door Shutter				
	Providing Partly glazed door shutter all as above but with 8 mm. th. Plain float glass including etching / beveling / grinding / polishing etc. as per approved design and pattern as directed with 12 mm. x 20 mm. first class G.W. beading all along perimeter and on either sides duly polished to superior wax finish all as per the approval of the architect with the cost of all materials and labour required for the work.	Sqm.	8.00		

Sl. No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
8	Main Entrance Door				
	Providing and fixing fully glazed aluminum shutters to doors using minimum 12 mm. thick tinted glass, sheet with electrolytic colored powder coated aluminum top and bottom rails of minimum 125 mm. wide including supplying and fixing of electrolytic colored powder coated box type aluminum section as frame including providing, fixing of 2 nos. of necessary pivots complete with cost of all labour and materials.	Sqm.	3.00		
9	Moulding				
	Providing and fixing 12 mm x 80 mm decorative moulding as per design in Gambhar wood on edges on the partitions, counters etc. wherever directed including polishing in superior finish complete.	Rmt.	20.00		
	Total				

PART - A : Section - II : False Ceiling

Sl. No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Providing and fixing at site plain Gypsum board false ceiling made from 12.5 mm. thick paper reinforced gypsum board sheets fixed on existing channels already laid by removing the old Gypsum board ceiling wherever necessary and also removing the electrical fittings and fixtures and closing the gap with board. Boards are to be fixed to the above frame work using 25 mm. dry wall screws. Arrangements are to be made to accommodate light fixtures, by forming recessed channels etc. wherever directed. Depressions, nails and screws, jointing and finishing etc. shall be done with jointing compound of TOPCOAT primer, ceiling to be level and free from cracks. Item to be completed in all respects to the Architects approval	Sqm	-	-	-
2	Applying two coats of emulsion paint over a coat of primer over Gypsum board flase ceiling. Opening in ceiling are to be tied with perimeter channel complete with the cost of all labour and materials (Measurement for the purpose of payment shall be taken for the flat surface only.)	Sqm	20.00		
3	Cornice / Moulding				
	Sub Total				

PART - A : Section - III : Hardware Fittings & Fixtures

Sl. No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Butt Hinges				
	Supplying, fitting and fixing 100 x 75 x 10 gauge, stainless steel heavy duty Butt Hinges including screws of approved quality.	Nos.	22.00		
2	Cylindrical Lock				
	Supplying, fitting and fixing polished Brass Godrej Cylindrical lock including a pair of keys.	Nos.	6.00		
3	Door Stopper				
	Supplying, fitting and fixing Door Stopper with height and press adjustment in pleasure die casting and heat treated spring clasps (EbCo or its approved equivalent).	Nos.	6.00		
4	Door Closer				
	Supplying, fitting and fixing modular single speed hydraulic type Door Closer (Godrej 1939 or its equivalent)	Nos.	4.00		
5	Key Board				
	Providing and fixing Steel Key Board tray on telescopic channel approved quality.	Nos.	6.00		
6	Floor Spring				
	Providing and fixing in position heavy duty Floor-Spring with Stainless Steel plate, pivots etc. including all necessary civil works and mending good to damages.	Nos.	2.00		
7	Door Handle				
	Providing and fixing minimum 18" long Godrej buffed stainless steel door handle for glass door.	Pairs	2.00		
8	Tower Bolt				
	Providing and fixing S. S. minimum 8mm dia Rod and 150mm long Tower Bolt.	Nos.	2.00		
	Sub Total				

PART - A : Section - IV : Furniture

GENERAL NOTES:- The rate of each item under this Head must cover the following even if these are not specifically mentioned. Samples of all Hardware fixtures got to be approved before purchase. No extra whatsoever will be entertained under this Head. The rates quoted, therefore, deemed to have been included in individual item of works.

- (1) All Tables/Storage unit & filing cabinets under this head shall be strictly be made from 19 mm. thick BWR block board.
- (2) All drawers and shelves shall be over lapping type having all exposed edges perfectly sealed with min. 3 mm. th. T.W. leaping and painted/polished in superior malamine finish.
- (3) Hardware fittings and fixtures shall also be provided as under:
 - (i) All drawers to have a pair of telescope sliders of Godrej/Ebco or equivalent approved make.
 - (ii) All openable shutters of shelves/cabinets etc. to have minimum a pair of Auto closing hinges of Ebco or similar approved make.
 - (iii) All drawers/shelves shall have one no. each multipurpose lock of Godrej make and the lock nos. are also to be provided on surface of shutters in white paint.
 - (iv) All double leaf shutters of cabinet or storage unit shall be provided with a pair of min. 3" long stainless steel Tower bolts to be installed at one of inner faces of the shutter's leaf.
 - (v) All Table Tops are to be provided with 3" dia PVC wire Managers.
- 4 All exposed faces are to be laminated with min. 1.00 mm. thick laminate sheet of approved colour, shade and pattern whereas all internal faces are to be painted in two coats of enamel paint over a coat of primer.
- 5 All tables/work-stations are essentially be provided with duly painted/25 mm. x 150 mm. board/hard wood foot rest.

PART - A : Section - IV : Furniture

Sl. No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Table				
	Providing Tables of following sizes made from 19 mm phenol bonded block board Top, supports & modesty panel the edges of table top as well as supports should be made 38 mm in appearance and to be finished with 12 mm x 38 mm gambhar wood 'D' moulding to be polished in superior finish. The modesty panel t span between supports horizontally as well as from table top to floor vertically. All the exposed faces are also to be finished with 1 mm thick matt/satin finish laminate where as inner faces are to be painted in two or more coats of enamel paint over a coat of primer. Item to be completed with all labour and materials as per drawing and to the Architects approval.				
(a)	Branch Manager's Table	Nos.	1.00		
	(Size : 3' 0" x 5' 9" x 2' 6" high)				

Sl. No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
2	Cash Counters				
	Providing cash counters having working top of size 2' 6" wide x 5' 0" long and customer top 1' 0" wide x 5' 0" long made from 19 mm board spanning between partition walls already erected and to be supported over 25 x 25 x 2.0 mm Aluminum angle deats. The counter shall also have a modesty panel of 5' 0" long, 3' 10" high of 19 mm board. The edges of working top & customer top to appear 38 mm thick. The edges are also to be provided with 12 mm x 38 mm Gambhar wood 'D' molding finished in superior polish. The exposed faces of board also to be provided with 1.0 mm thick matt/satin finish laminate where as inner faces to be painted with two or more coats of enamel paint over a coat of primer. Item to be completed with cost of all labour, materials all as per drawing and Architects approval. (Size: 5' 0" x 2' 6" x 3' 10" high)	Nos.	1.00		
3	Counters				
	Providing wall to wall long tables for counters of following sizes and as shown in the drawing. The table top and modesty panel to span between the low height partitions walls already erected with aluminum angle cleats and to be made from 19 mm block board. The edges of top to appear 38 mm in thickness and to be provided with duly polished 12 mm x 38 mm Gambhar wood 'D' molding. The exposed faces including modesty panel to be provided with 1.00 mm thick laminate where as balance are to be painted in enamel paint. Complete with the cost of all labour and materials to the Architects approval.				
(a)	Size : 2' 6" x 5' 0" x 2' 6" high	Nos.	3.00		
(b)	Size : 2' 6" x 4' 0" x 2' 6" high	Nos.	1.00		

Sl. No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
4	Side Credenza				
	Providing Side Credenza units of following sizes. The top, bottom, sides and shutters are to be made in 19 mm board where as back to be provided with 6 mm ply. The drawers are to be made from 12 mm ply with front in 19 mm board. All the exposed faces are to be provided with 1.00 mm thick laminate where as inner faces to be painted. All the exposed edges are also to be finished in duly polished 3 mm thick gambhar wood leaping. The item to be completed in all respect with all hardware fittings and fixtures as detailed in general note to the architects approval.				
(a)	Credenza to have 1 Nos. of drawer and a shelf unit having openable shutters down below the drawers. (SC - 1) (Size : 16" deep x 2' 0" long x 2' 4" high)	Sets.	2.00		
(b)	Credenza to have 3 Nos. of drawers and a shelf unit having openable shutters side by side the drawers. (SC - 2) (Size : 16" deep x 3' 0" long x 2' 4" high)	Sets.	2.00		
(c)	Credenza to have 3 Nos. of drawers and a shelf unit having openable shutters side by side. (SC - 3) (Size : 16" deep x 4' 0" long x 2' 4" high)	Sets.	2.00		
5	Filing Cabinet				
	Providing approx. low-height filling cabinet. The top, bottom, sides, openable shutters and intermediate shelves of the cabinet are to be made from 19 mm. board. Where as the rear of the cabinet to be closed in 6 mm ply. The cabinets shall also be divided in parts with 19 mm board vertically placed inside. All the exposed faces are to be provided with 1.00 mm. thick laminated sheet whereas the interior faces are to be painted in enamel paint in min. 2 coats over a coat of primer. The exposed edges are also to be provided with min. 3 mm. thick Gambhar wood leaping duly polished in superior finish. (Only plan area to be measured for payment)				
(a)	2' 6" high	Sqm.	1.25		
	Sub Total				-

PART - A : Section - V : Miscellaneous Works

Sl. No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Writing Ledge				
	Providing and fixing writing ledge as per design made out 19 mm. Board with necessary grove patterns 1.0 mm thick laminate to be cladded. 12 mm thick machine polished glass to be provided on top of the writing ledge. Small boxes to be made out of 19 mm Board to be made within of the writing ledge finished with 1.0 mm. laminate, inside enamel painted. The work to be completed as per design and approval of the Architect.	Nos.	1.00		
2	Notice Board				
	Notice Board to be provided with min. 12 mm. th. Soft board with 6 mm. ply backing, velvate cloth covering and 1' x 3" decorative gambhar wood frame duly polished all complete. (App. Size 2' 6" x 4' 0")	Nos.	1.00		
3	Cheque Drop Box & Complain Box				
	Providing Cheque Drop Box made from 12 mm ply of size 6" x 12" x 15" high with slit, openable glass front, locking arrangement etc. complete. The exposed faces are to be provided with 1.00 mm. th. laminate where as inside to be painted complete.	Nos.	2.00		
	Total				

PART - B : Furnishing Work of ATM At Bharni Branch

PART - B : SUMMARY

<u>Description</u>	<u>Amount (Rs.)</u>
1 : Civil Work	Rs. <input type="text"/>
2 : Interior Furnishing Work	Rs. <input type="text"/>
3 : Miscellaneous Items	Rs. <input type="text"/>
4 : Painting & Paneling	Rs. <input type="text"/>
TOTAL PART - B	Rs. <input type="text"/>

PART - B : 1 - Civil Work

SI. No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
3(4)	Cladding to Entrance Wall				
	Providing and laying minimum 17mm thick machine cut and machine polished to mirror finish Black Granite slab to walls, risers of steps etc. including rounding off the corners / edges to superior finish to be laid over min. 10mm thick base course of cement and sand mortar (1:4) including white cement slurry, rendering and pointing mixed with pigment etc. complete with cost of all materials and labour.	Sq.m.	3.00		
	Sub Total				

PART - B : 2 - Interior Furnishing Work

Sl. No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1(7)	False Ceiling				
	Providing and fixing at site flush type plain Gypsum board false ceiling as per pattern and design made from 12.5 mm. thick paper reinforced gypsum board sheets fixed with main frame channels 80 mm x 26 mm. x 0.5 mm. at every 450 mm. center to center, with perimeter channel 20 mm. x 26 mm. x 0.5 mm. all along the wall shall be provide. The frame work to be suspended with strap hangers 25 mm. x 26 mm x 0.5 mm all along the wall shall be provided. The frame work to be suspended with strap hangers 25 mm. x 0.5 mm. from intermediate channels using nuts and bolts are recommended using rawl plugs 12.5 mm. dia x 35 mm. long with 6 mm. dia bolt and soffit cleat 27 mm x 37 mm. x 25 mm. x 1.6 mm. thick. Boards are to be screw fixed to the above frame work using 25 mm. dry wall screws.				
	Arrangements are to be made to accommodate light fixtures, by forming recessed channels etc. wherever directed. Depressions, nails and screws, jointing and finishing etc. shall be done with jointing compound of TOPCOAT primer, ceiling to be level and free from cracks. Item to be completed in all respects to the Architects approval including applying two coats of emulsion paint over a coat of primer. Opening in ceiling are to be tied with perimeter channel complete with the cost of all labour and materials (Measurement for the purpose of payment shall be taken for the flat surface only)	Sqm.	7.50		
2 (7)	Cornice / Molding				
	Supplying and fixing 65/80 mm ready made POP cornice of approved design along edges of false ceiling and walls inclusive of finishing with primer ad synthetic enamel paint. (Colour : Golden Yellow)	Rmt.	11.00		

Sl. No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
3 (8)	Glazed Partition at Entrance				
	Providing and fixing in position fully glazed partition made from 2" x 4" powder coated (20 microne in colour : Golden Yellow) aluminium box-section with single groove (3 nos. of horizontal members : Top, middle & bottom. 2 nos. of Vertical members) with 5.5mm thick clear float glass having etching, frosting and Bank's monogram etc. as shown in the drawing to be fixed in position with powder coated aluminum tepper clips etc. complete with cost of all materials and labour. [Note : The contractor to furnish certificate from laboratory to ascertain 20 micorne thickness of powder coating.]	Sqm.	2.50		
4 (9)	Entrance Door				
	Providing, fitting and fixing in position fully glazed entrance door with min. 20 micorne thick powder coated in colour : Golden Yellow aluminum 125mm x 25mm top, bottom, lock rails and vertical styles with 5.5mm thick plane float glass having stickering in etching, frosting Bank's Logo etc. matching with partition to be fixed with powder coated topper clips as per drawing.	Sqm.	2.00		
6(11)	Cover Hood				
	Providing and fixing wooden boxing to cover rolling shutter using 50.8 x 25.40 x 1.16 Aluminum rectangular hollow sections as frames to be placed @ 2' 0" apart along with 12mm thick marine grade ply confirming to I.S. 710 with a trap door having magnetic catcher, 3" long stainless steel tower bolts and also finished with minimum two cats of enamel paint over a coat of primer complete. (Colour : Silver Grey)	Sqm.	4.00		
7(13)	Cabinet				
	Providing & fixing of wooden storage cabinet to house UPS & batteries, VSAT IDU etc. of 3' x 3' x 18" deep in size along with one shelf all made from 19mm board and 6mm backing with 2 nos. of 3" dia wire managers and also edges perfectly sealed with 3mm leaping etc. having open shelves as per drawing. The cabinet to be painted inside and outside in 2 coats of enamel paint over a coat of primer.	Nos.	1.00		
	Sub Total				

PART - B : 3 - Miscellaneous Items

Sl. No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1(14)	Waste Paper Bin				
	Providing waste paper bin in perforated stainless steel of min. 8" dia x 12" long having rubber gasket at bottom.	Nos.	1.00		
2(15)	Writing Ledge Cum Drop Box				
	Providing writing ledge and cheque drop box with collapsible lid all in one integrated design made from powder coated, die pressed, 16 SWG metal sheet in Bank's approved shade and colour having PP coating for protection from UV light and also to make scratch resistance with 50 x 8 dome shaped mirror cap, wooden threaded metal screw etc. complete. (Colour : Silver)	Nos.	1.00		
5(18)	Bank's Logo				
	Supplying and fixing of Bank's Logo made in box type 1/2" stainless steel of approx. 18" in dia.	Nos.	1.00		
6(19)	Poster Frame				
	Providing and fixing in position poster frame fabricated from 2 nos. of clear acrylic sheets of 24" x 36". The outer sheet shall be 5mm thick having bevelled crystal edge polished for 3/4" at 8-10 degrees on all sides at front whereas the rear sheet shall be of plane 5mm thick flat. The rate therefore shall also include stainless steel	Nos.	1.00		
7(20)	Signage Including Lighting Vinyl Stickers				
	In approved pantone shade. Substrate - Meraflex - Meta (II) (metamark) Box - GI approved colour powder coated Aluminum sxtrusions for tensioning - top and bottom covered with 18 SWG AL Size is 9' 6" x 3' sheets, white powder coated with GI back cover. Drop cap to be provided. Electrical fitting : 1 36 watt Tubelight to be provided for every 4 Sqft. of area.	Sqm	3.00		
9	Pin-up Board				
	Providing and fixing 18" x 24" pin-up board made from 12mm thick soft board mounted over 6mm thick ply wood backing covered with satin cloth of approved colour with aluminum frame etc. complete.	Nos.	1.00		
10	Floor Spring				
	Providing and fixing in position heavy duty Floor-Spring with stainless steel plate, pivots etc. including all necessary civil works and mending good to damages.	Nos.	1.00		
11	Door Handle				
	Providing and fixing minimum 18" long x 1" dia buffed stainless steel door handle for glass door of approved design.	Pairs	1.00		
	Sub Total				

PART - B : 4 - Painting & Paneling

Sl. No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
2(23)	Wall Panelling				
	Providing and fixing in position aluminum composite panel (ACP) for wall cladding using 4mm thick ACP with aluminum foil thickness not less than 0.5mm on both faces having 3mm thick polythene core of approved make and shall be of PVDF paint coated in Bank's approved shade to withstand for at least 15 years against fadding (warranty certificate from the manufacturer is to be produced for min. period of 15 years against fadding, chalking and delamination) and to be fixed over aluminum frame work of non-anodized aluminum rectangular hollow sections (Alom:2348:50.80 x 25.40 x 1.16 wall thickness or its approved equivalent) and to be placed @ 2' 0" apart in both vertical and horizontal direction using cleats, screws clamps, rawl plugs etc. The joints of ACP shall be finished with silicon based weather proof sealant. The rate therefore shall include for all labour, materials, hardware and also multiple shades to achieve Bank's approved design. (Colour : Silver Grey)	Sqm.	15.00		
	Sub Total				

PART - C : INTERIOR FURNISHING WORKS OF SERVER ROOM

PART - C : SUMMARY

<u>Description</u>	<u>Amount (Rs.)</u>
Furnishing Work of Server room :	Rs.
Total PART - C	Rs.

PART - C : Furnishing Works of SERVER ROOM

SI No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Frame Work				
	Providing and fixing non anodized aluminum rectangular hollow sections Alom 2348 : 50.80 x 25.40 x 1.16 mm wall thickness) or its approved equivalent for erection of frame work for partitions, paneling etc. to be placed 2' 0" apart in both vertical and horizontal direction. Extra members at corners / functions are also to be provided at no extra cost to the owner. The frame work shall be fabricated and installed in position firmly with the help of suitable Aluminum cleats, screws, clamps, rawl plugs and all necessary civil works and mending good to all damages complete with cost of all materials, labour, hardware etc. (Door and glass opening above shall be deducted from measurement for the purpose of payment.)	Sqm.	5.50		
2	Ply Wood				
	Providing and fixing 6mm thick of BWR (PF) grade ply wood as skin to existing frame works executed under item no. (1) above with screws at adequate intervals complete with cost of all labour and materials.	Sqm.	11.00		
3	Laminate				
	Providing and fixing minimum 1.00 mm thick matt/satin finished laminates of approved colour and make to partitions & paneling and wherever directed to be fixed with suitable adhesive complete with cost of materials, labour and hardware etc. all as per drawing and direction of Architect.	Sqm.	11.00		

SI No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
4	Glass				
	Providing and fixing plane float 5.50 mm thick glass pane on the frame works already erected and wherever directed in pattern as shown in the drawing with stainless steel Glazing Clips / D's or polished Gambhar Wood beading all along perimeter of the Glass as required including etching / grinding / polishing etc. as per approved design and pattern complete with the cost of all labour and materials.	Sqm.	0.75		
5	Partly Glazed Door Shutter				
	Providing Partly glazed door shutter all as above but with 8 mm. th. Plain float glass including etching / beveling / grinding / polishing etc. as per approved design and pattern as directed with 12 mm. x 20 mm. first class G.W. beading all along perimeter and on either sides duly polished to superior wax finish all as per the approval of the architect with the cost of all materials and labour required for the work.	Sqm.	3.00		
6	Server Table				
	Providing and fixing wall to wall long table top supported over walls on either sides, having 19 mm board as table top & 1 mm thick laminate. Add additional piece of board at edge to appear 38 mm thick having Gambhar Wood 'D' moulding duly polished. The inside hidden face of board to be painted in 2 coats of enamel paint over a coat of primer complete. (Size : 6' 3" x 2' 0" x 2' 6" high)	Nos.	1.00		
7	Pedestal				
	Providing Pedestal of min. size of 18" wide x 2' 0" deep x 2' 6" high made from 19 mm board on all sides raised over 3" high recessed type skirting whereas the back to be provided with 6 mm thick ply. The Pedestal to have 5" deep drawer and a shelf below the sides of drawers are to be made from 12 mm ply with 6 mm ply on back and bottom where as front of drawer as well as shelf shall have 19 mm board. All the exposed edges are to have 3 mm leaping. The work to be completed in all respect with 1.00 mm thick laminate to all exposed faces whereas inner faces are to be painted in two coats of enamel paint over a coat of primer complete with all necessary hardware fittings and fixtures complete.	Sets	1.00		
	Total				