

<b>PART I ELECTRICAL INSTALLATION WORK PURI INDIAN BANK.</b>					
<b>Sl. No.</b>	<b>Particulars</b>	<b>Unit</b>	<b>Qty.</b>	<b>Rate (Rs.)</b>	<b>Amount (Rs.)</b>
1	<b>SERVICE CABLE</b>				
	Supplying and laying of size 50 Sq.mm. 3.5 core armoured cable of Aluminium conductor PVC insulated idamages.	Mtr.	7.00		
2	<b>COMPUTER DB</b>				
	Computer Terminal DB (Company made with double door cover to be used)	Set	1.00		
	Incoming : 25 amp. DP MCB - 1 No.				
	Outgoing : 6 amp. SP MCB - 10 Nos.				
	Rate in words : Rupees				
3	<b>SUB-MAIN WIRING</b>				
A)	From main panel to LDB and UPS output DB to computer DB and from AC DB to A.C.(6 Sqmm.x 2 + 2.5 Sqmm.x 1) PVC single core copper wire.	Mtr.	120.00		
B)	From computer terminal DB to computer terminal Board (2.5 Sqmm. x 2 + 1 Sqmm. x 1) PVC single core copper wire.	Mtr.	170.00		
4	<b>AC : INDUSTRIAL SOCKET:</b>				
	Supply and fixing 25 Amp. Power Unit of 'Havells' make comprises of industrial plug socket, plug top, MCB etc. complete (For A.C.)	Nos.	7.00		
5	Supplying & fixing no. of modular clip in type 5 amp. plug socket on galvanized boxes along with 16 Amp switch. The item to be made recessed in wall. .	Nos.	14.00		
6	<b>RAW-POWER:-</b>				

	Supplying & fixing no. of modular clip in type 5 <b>amp. plug socket</b> on galvanized boxes along with 16 Amp switch. The item to be made recessed in wall. (Raw power - 2 Nos. on counters).	Nos.	2.00		
7	<b>COMPUTER TERMINAL:</b>				
	Supplying and fixing recessed modular clip-in-type <b>Computer terminals</b> having : 4 Nos. of 6 Amp. switches, 4 Nos. of 6 Amp. sockets and 1 No. of indicator to be fixed on galvanized boxes of company made.	Sets.	10.00		
<b>PART II : LAN WIRING</b>					
1	Supplying and laying of all materials <b>CAT-6 cable for Lan- wiring</b> to Computer points	Rmt.	185.00		
2	Supplying of @ <b>1.00 Mtr.</b> long patch chord each with RJ 45 jacks	Nos.	10.00		
3	Supplying of <b>Patch Chord @ 2.00 Mtr.</b> Long with RJ 45 jacks	Nos.	10.00		
4	Supplying and fixing of <b>Information out-let box</b> (Single)(for RJ 45 connector of D-link make)	Nos.	10.00		
5	Supplying and fixing of <b>24 PORT Switch</b> : 10/100/1000 Mbps Gigabit Smart switch D-link make.	Nos.	1.00		
6	Supplying and fixing of <b>24 Port UTP Patch Panel.</b>	Nos.	1.00		
	Rate in words : Rupees				
<b>TOTAL</b>					

**PART III**  
**ELECTRICAL INSTALLATION WORK SERVER ROOM.**

Sl. No.	Particulars	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	<b>COMPUTER TERMINAL:</b>				
	Supplying and fixing recessed modular clip-in-type <b>Computer terminals</b> having : 3 Nos. of 6 Amp. switches, 3 Nos. of 6 Amp. sockets and 1 No. of indicator to be fixed on galvanized boxes of company made.	Sets.	3.00		
	Rate in words : Rupees				
2	Supplying and laying of all materials <b>CAT-6 cable for Lan- wiring</b> to Computer points	Rmt.	20.00		
	Rate in words : Rupees				
3	Supplying and fixing in position of <b>wall mounted rack</b> with cable manager of following sizes:-	No	1.00		
	Rate in words : Rupees				
4	Supplying and fixing of <b>Information out-let box</b> (Single)(for RJ 45 connector of D-link make)	Nos.	2.00		
	Rate in words : Rupees				
5	From computer terminal DB to computer terminal Board (2.5 Sqmm. x 2 + 1 Sqmm. x 1) PVC single core copper wire.	Mtr.	15.00		
	Rate in words : Rupees				