

Gunjan and Associates.
Architects, Engineers, Interiors &
Landscape Designers.
141, Sainik Nagar, Raebareilly Road,
Lucknow-226002
Phone: 09838818498, 839018489
E-Mail: arunjan@yahoo.com
studio@gunjanandassociates.com
www.gunjanandassociates.com

BILL OF QUANTITY FOR PROPOSED FURNISHING WORKS

AT INDIAN BANK, JHANSI (A.T.M.)

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
1	FALSE CEILING (ARMSTRONG)	45.00	Sq.ft.		
	Providing & Fixing Armstrong (Fine Fissured Micro Look with Tagular Edge using 15.0mm Grid sections) false ceiling of size 24"x24" at levels as shown in the drg. Rate shall be inclusive of providing the total system with installation etc. Contractor has to maintain all tiles in good order and replace the defected tiles (at his own cost) before handing over the site for Branch Operations. Rate shall include providing necessary cut-outs & additional support frames for electrical fixtures, A.C. grills etc.. (Note - : the work shall be executed as per design)				
3	MAIN DOOR WITH ANTISHATTER FILM WITH CUSTOMISED DOOR HANDLE	24.50	Sq.ft.		
	Providing and fixing Aluminium glass door comprising of approximately 100 mm height x 50mm thick aluminium bottom rail, 100 mm x 50 thick vertical and top rail 100 mm x 50 mm thick lock rail floor spring of ISI make, clip sections, 8mm thick clear float glass. aluminium members to be black powder coated. All members to be 16 gauge. The vertical shutter rail to house wool packing to act as a sealant for a gap between shutter and the frame fixed glazing. The Aluminium sectional dimensions may vary by 12 to 16 mm subject to availability. Standard height of the door should not exceed 6'-9" as per OBC norms.				
4	EXTERNAL FIXED GLAZING	16.00	Sq.ft.		
	Providing and fixing in position 8 mm Modifloat glass with Aluminium bottom rail comprising of approximately 100 mm height x 50 mm with clip section, top and bottom rail and vertical members approximately 100 x 50 mm height Aluminium sections to be provided to be black powder coated All work to be done in line level and plumb. The Aluminium sectional dimensions may vary by 12 to 6 mm.				
5	PILLAR LOCK	1.00	No.		
	Providing And fixing Access lock pillar comprising of 12 mm IS 303 ply finished with 1mm laminate.				

	2 sheets of 36" x 24" clear acrylic (poster to be sandwiched in between). Outer sheet is 5mm thick and bevelled crystal edge polished for 3/4" at 8-10 degrees on all sides in the front.Rear sheet is 5 mm thick flat.				
7	VISUAL MERCHANDISING WITH COMPLAINT & SUGGESTION BOX	1.00	NO.		
	Writing ledge with brochure holder and wooden box as per Bank norms.				
8	Wooden Wall Paneling	226.00	Sq.ft.		
	Providing and fixing in position wooden panneling with a frame work of 2" x2" finished with antitermite treatment and enamel paint and covered with 6 mm ply IS 3023 with trap door with magnetic catchers / tower bolt The ply to be finished with 1 mm thick laminate as per direction of the architect.				
9	Shutter Boxing with trap door (Only front face to be measured for paymnet purpose)	45.00	Sq.ft.		
	Manufacturing, supplying and fixing box type metre storage with overall depth of 1'6" and height as per the size of the mitre. comprising of the following.				
	19mm block board hinged double shutter, height as size of the panel with alround beadings 3/4" x 1/2", powder coated handles, piano hinges, magnetic ball catches, lock, locking arrangement, tower bolts etc., all as per directions.				
	All visible surfaces to be fixed with 1.0mm thick lamination sheet with matching grains & grooves as per instructions				
	All internal & rear surfaces to be painted with two coats of enamel paint over a coat of primer / putty as directed to get a smooth finish.				
	TOTAL				

Note:The Contractors should quote the rates without G.S.T. No Tender shall be accepted which claims the rates including G.S.T.